BRUHAT BANGALORE MAHANAGARA PALIKE

Name of work: Comprehensive development of bad roads and improvements to road side drain, footpaths, Asphalting and concreting including culvert selected main and other connecting roads of package No.1 in ward No.14, Bagalagunte of Dasarahalli Division in Dasrahalli zone Comprising of 8 works as indicated in Sl No. 122, 123, 124, 125, 126, 127, 128 & 129

Job Number: 014-20-000102							Est. Amount =	1500.00	Lakhs
Sl. No	Description of Work	Unit	No	Dimension L	B1	B2	D	Quantity	Rate in Rs.	Amount in Rs.
1	Removing & Refixing stone slabs of drains and pointing in C.M (1:3)									
	KPWD S.R 2018-19	It. No.	5.33.	Pg.No.			27			
	a) 10cm thick									
	Byraveshwara circle									
	Ch:00-110 1st Cross 80%		2	88.00	1.00			176.00		
	Ch:00-112 2nd Cross 80%		2	89.60	1.00			179.20		
	Ch:00-110-3rd Cross 80%		2	88.00	1.00			176.00		
	Ch:00-88 4th Cross 80%		2	70.40	1.00			140.80		
	Ch:00-82 5th Cross 80%		2	65.60	1.00			131.20		
	Ch:00-215 (From Byraveshwara Circle) 40%		2	58.00	1.00			116.00		
	Ch:-310 (Naga Devanta Temple Road) 50%		2	155.00	1.00			310.00		
	Consider							**1229.20**		
	Siddeshwara Layout									
	Ch:00-950 20%		2	190.00	1.00			380.00		
	Consider							**380.00**		
	Royal Enclave Layout									
	Ch:00-125 Royal Enclave Rd. 60%		2	75.00	1.00			150.00		
	Ch:125-255 Royal Enclave Rd. 80%		2	104.00	1.00			208.00		
	Ch:00-40 5th Cross 50%		2	20.00	1.00			40.00		
	Ch:40-90 5th Cross Lshape 40%		2	25.00	1.00			50.00		
	Consider							**448.00**		
	NMH Layout									
	Ch:00-220 Basava Dhyana Kendra 80%		2	164.00	1.00			328.00		
	Ch:00-230 1st main 30%		2	69.00	1.00			138.00		
	Ch:00-140 2nd main		2	125.00	1.00			250.00		
	Consider							**716.00**		
	Soundarya layout 2nd Main BS drain									
	Ch:00-530(2nd Main Road) 30%		2	145.50	1.00			291.00		
	Consider							**291.00**		
	Soundarya layout 1st Main BS drain									
	Ch:00-530(1st Main) RHS 80%		1	376.00	1.20			451.20		
	Ch:260-530(1st Main) LHS 20%		1	46.00	1.20			55.20		
	Consider							**506.40**		
	B) 7.5cm thick									
	Byraveshwara circle BS drain									
	Ch:00-82 5th Cross		2	82.00				164.00		
	30% Damage Portion		-1	49.20				-49.20		
	Consider		1	65.60			1.50	**98.40**		
	M.H.R. Layout BS drain									
	Ch:00-490(Chetana E lavada school Frant Rd to Siddhi Vinayaka Temple)		2	470.00				940.00		
	Ch:00-110 (4th Cross Road)		2	110.00				220.00		
	Ch:00-80 (5th Cross Road)		2	80.00				160.00		
	Ch:00-75 (6th Cross Road)		2	75.00				150.00		
	Ch:00-110 (7th Cross Road)		2	110.00				220.00		
	Ch:00-115 (8th Cross Road)		2	115.00				230.00		
	Ch:00-210 (1st main Road)		2	185.00				370.00		
							Total length	**2290.00**		
	30% Deduction for Damaged Portion		-1	687.00				-687.00		
	Consider		1	916.00			1.50	**1374.00**		
	MEENAKSHI layout BS drain									
	Ch:00-95(14th Cross Road)		2	95.00				190.00		
	Ch:00-110(12th Cross Road)		2	110.00				220.00		
	Ch:00-270 (1st B Main)		2	270.00				540.00		
	Ch:00-280 (1st C Main)		2	280.00				560.00		
	Ch:00-140(10th Cross Road)		2	140.00				280.00		
	Ch:00-96(9th Cross Road)		2	96.00				192.00		
	Ch:00-62(8th Cross Road)		2	62.00				124.00		

BRUHAT BANGALORE MAHANAGARA PALIKE

Name of work: Comprehensive development of bad roads and improvements to road side drain, footpaths, Asphalting and concreting including culvert selected main and other connecting roads of package No.1 in ward No.14, Bagalagunte of Dasarahalli Division in Dasrahalli zone Comprising of 8 works as indicated in Sl No. 122, 123, 124, 125, 126, 127, 128 & 129

Job Number: 014-20-000102							Est. Amount =	1500.00	Lakhs
Sl. No	Description of Work	Unit	No	Dimension L	B1	B2	D	Quantity	Rate in Rs.	Amount in Rs.
1	Removing & Refixing stone slabs of drains and pointing in C.M (1:3)									
	KPWD S.R 2018-19	It. No.	5.33.	Pg.No.			27			
	a) 10cm thick									
	Byraveshwara circle									
	Ch:00-110 1st Cross 80%		2	88.00	1.00			176.00		
	Ch:00-112 2nd Cross 80%		2	89.60	1.00			179.20		
	Ch:00-110-3rd Cross 80%		2	88.00	1.00			176.00		
	Ch:00-88 4th Cross 80%		2	70.40	1.00			140.80		
	Ch:00-82 5th Cross 80%		2	65.60	1.00			131.20		
	Ch:00-215 (From Byraveshwara Circle) 40%		2	58.00	1.00			116.00		
	Ch:-310 (Naga Devanta Temple Road) 50%		2	155.00	1.00			310.00		
	Consider							**1229.20**		
	Siddeshwara Layout									
	Ch:00-950 20%		2	190.00	1.00			380.00		
	Consider							**380.00**		
	Royal Enclave Layout									
	Ch:00-125 Royal Enclave Rd. 60%		2	75.00	1.00			150.00		
	Ch:125-255 Royal Enclave Rd. 80%		2	104.00	1.00			208.00		
	Ch:00-40 5th Cross 50%		2	20.00	1.00			40.00		
	Ch:40-90 5th Cross Lshape 40%		2	25.00	1.00			50.00		
	Consider							**448.00**		
	NMH Layout									
	Ch:00-220 Basava Dhyana Kendra 80%		2	164.00	1.00			328.00		
	Ch:00-230 1st main 30%		2	69.00	1.00			138.00		
	Ch:00-140 2nd main		2	125.00	1.00			250.00		
	Consider							**716.00**		
	Soundarya layout 2nd Main BS drain									
	Ch:00-530(2nd Main Road) 30%		2	145.50	1.00			291.00		
	Consider							**291.00**		
	Soundarya layout 1st Main BS drain									
	Ch:00-530(1st Main) RHS 80%		1	376.00	1.20			451.20		
	Ch:260-530(1st Main) LHS 20%		1	46.00	1.20			55.20		
	Consider							**506.40**		
	B) 7.5cm thick									
	Byraveshwara circle BS drain									
	Ch:00-82 5th Cross		2	82.00				164.00		
	30% Damage Portion		-1	49.20				-49.20		
	Consider		1	65.60			1.50	**98.40**		
	M.H.R. Layout BS drain									
	Ch:00-490(Chetana E lavada school Frant Rd to Siddhi Vinayaka Temple)		2	470.00				940.00		
	Ch:00-110 (4th Cross Road)		2	110.00				220.00		
	Ch:00-80 (5th Cross Road)		2	80.00				160.00		
	Ch:00-75 (6th Cross Road)		2	75.00				150.00		
	Ch:00-110 (7th Cross Road)		2	110.00				220.00		
	Ch:00-115 (8th Cross Road)		2	115.00				230.00		
	Ch:00-210 (1st main Road)		2	185.00				370.00		
							Total length	**2290.00**		
	30% Deduction for Damaged Portion		-1	687.00				-687.00		
	Consider		1	916.00			1.50	**1374.00**		
	MEENAKSHI layout BS drain									
	Ch:00-95(14th Cross Road)		2	95.00				190.00		
	Ch:00-110(12th Cross Road)		2	110.00				220.00		
	Ch:00-270 (1st B Main)		2	270.00				540.00		
	Ch:00-280 (1st C Main)		2	280.00				560.00		
	Ch:00-140(10th Cross Road)		2	140.00				280.00		
	Ch:00-96(9th Cross Road)		2	96.00				192.00		
	Ch:00-62(8th Cross Road)		2	62.00				124.00		

Ch:00-105(7th Cross Road)									
Ch:00-65(6th Cross Road)	2		105.00				210.00		
Ch:00-64(5th Cross Road)	2		65.00				130.00		
Ch:00-63(4th Cross Road)	2		64.00				128.00		
Ch:00-65(3rd Cross Road)	2		63.00				126.00		
Ch:00-66(2nd Cross Road)	2		65.00				130.00		
Ch:00-80(1st Cross Road)	2		66.00				132.00		
	2		80.00				160.00		
						Total length	3122.00		
30% Deduction for Damaged Portion	-1		936.60				-936.60		
Consider	1		1248.80			1.50	**1873.20**		
Soundarya layout 2nd Main BS drain									
Ch00-95(11th Cross Road) sqm	2		95.00				190.00		
Ch:00-85(10th Cross Road)	2		85.00				170.00		
Ch:00-75(9th Cross Road)	2		75.00				150.00		
Ch:00-68(8th Cross Road)	2		68.00				136.00		
Ch:00-50(7th Cross Road)	2		50.00				100.00		
Ch:00-43(6th Cross Road)	2		43.00				86.00		
Ch:00-60(4th Cross Road)	2		60.00				120.00		
Ch:000-152(3rd Cross Road)	2		152.00				304.00		
Ch:000-100 (Cross Road)	2		100.00				200.00		
Ch:000-225 (Cross Road)	2		225.00				450.00		
Ch:00-125(3rd Main Road)	2		125.00				250.00		
Ch:00-115(3rd Main Road)	2		115.00				230.00		
Ch:115-220(3rd Main Road)	2		105.00				210.00		
						Total length	**2596.00**		
30% Deduction for Damaged Portion	-1		778.80				-778.80		
Consider	1		1038.40			1.50	**1557.60**		
Soundarya layout 1st Main BS drain									
Ch:00-90(1st A Cross Road)	2		90.00				180.00		
Ch:00-100(2nd A Cross Road)	2		100.00				200.00		
Ch:00-90(4th A Cross Road)	2		90.00				180.00		
Ch:00-90(6th A Cross Road)	2		90.00				180.00		
Ch:00-90(7th A Cross Road)	2		90.00				180.00		
Ch:00-93(8th A Cross Road)	2		93.00				186.00		
Ch:00-92(9th A Cross Road)	2		92.00				184.00		
Ch:00-90(11th A Cross Road)	2		90.00				180.00		
Ch:00-93(12th A Cross Road)	2		93.00				186.00		
Ch:00-92(13th A Cross Road)	2		92.00				184.00		
Ch:00-92(14th A Cross Road)	2		92.00				184.00		
Ch:00-95(2nd B main Road)	2		95.00				190.00		
						Total length	2214.00		
30% Deduction for Damaged Portion	-1		607.20				-607.20		
Consider	1		885.60			1.50	**1328.40**		
Royal Enclave Layout BS drain									
Left Side cross Roads to Royal Enclave Main Rd.									
Ch:00-60 3rd Cross	2		60.00				120.00		
Ch:00-60 4th Cross	2		60.00				120.00		
Right Side cross Roads to Royal Enclave Main Rd.									
Ch:00-72 3rd Cross L shape	2		72.00				144.00		
Ch:00-32 4th Cross	2		32.00				64.00		
CC Roads									
Ch:00-40 1st cross LHS Royal Enclave	1		40.00				40.00		
Ch:00-55 2nd Cross road Royal Enclave	2		55.00				110.00		
						Total length	598.00		
30% Damage Portion	-1		179.40				-179.40		
Consider	1		239.20			1.50	**358.80**		
Siddeshwara Layout BS drain									
Ch:00-70 1st cross	2		70.00				140.00		
Ch:00-85 2nd Cross	2		85.00				170.00		
Ch:00-80 3rd Cross	2		80.00				160.00		
Ch:00-80 4rd Cross	2		80.00				160.00		
Ch:00-145 8th Cross	2		135.00				270.00		
						Total length	900.00		
30% Damage Portion	-1		270.00				-270.00		

	Consider									
	NMH Layout									
	Ch:00-220 Basava Dhyana Kendra	1		360.00			1.50	**540.00**		
	Ch:00-180 BESCOM Bagalugunte LHS									
		2		187.00				374.00		
		1		162.00				162.00		
						Total length		536.00		
	30% Damage Portion	-1		160.80				-160.80		
	Consider	1		214.40			1.50	**321.60**		
	Kirloskar connecting road									
	Ch:00-370 4nd main	2		355.00				710.00		
						Total length		710.00		
	30% Damage Portion	-1		213.00				-213.00		
	Consider	1		284.00			1.50	**426.00**		
							Total Qty	**11448.60**	**111.30**	**12,74,229.18**
2	Removing and resetting of kerb stones									
	KPWD S.R 2018-19	It. No.	37.57		Pg.No.		270			
	Soundarya layout 1st Main									
	Ch:00-530 RHS 1st main 70%	1		329.00				329.00		
	Ch:00-260 LHS 1st main 70%	1		168.00				168.00		
	Byraveshwara circle	m								
	Ch:150-200 LHS NMH conventional hall front 70%	1		35.00				35.00		
							Total Qty	**532.00**	**104.94**	**55,828.08**
3	KSRRB300-1. Earthwork excavation by manual means for roads, drains & similar works in ordinary soil excavated surface levelled and sides neatly dressed, the disposed earth to be levelled neatly after breaking of clods complete as per specifications.									
	KPWD S.R 2018-19	It. No.	5.29.1.		Pg.No.		27			
	DESILTING OF DRAIN									
	Byraveshwara circle									
	Ch:00-110 1st Cross	2		110.00	0.60		0.15	19.80		
	Ch:00-112 2nd Cross	2		112.00	0.60		0.15	20.16		
	Ch:00-110-3rd Cross	2		110.00	0.60		0.15	19.80		
	Ch:00-88 4th Cross	2		88.00	0.60		0.15	15.84		
	Ch:00-82 5th Cross	2		82.00	0.60		0.15	14.76		
	Ch:150-200 (Naga Devaata Temple Road) LHS	1		50.00	0.60		0.15	4.50		
	M.H.R. Layout									
	Ch:00-490(Chetana E lavada school Frant Rd to Siddhi Vinayaka Temple) LHS	2		442.00	0.50		0.20	88.40		
	Ch:00-110 (4th Cross Road)	2		110.00	0.45		0.20	19.80		
	Ch:00-80 (5th Cross Road)	2		80.00	0.45		0.20	14.40		
	Ch:00-75 (6th Cross Road)	2		75.00	0.45		0.20	13.50		
	Ch:00-110 (7th Cross Road)	2		110.00	0.45		0.20	19.80		
	Ch:00-115 (8th Cross Road)	2		115.00	0.45		0.20	20.70		
	Ch:00-210 (1st main Road)	2		185.00	0.45		0.20	33.30		
	MEENAKSHI layout									
	Ch:00-95(14th Cross Road)	2		95.00	0.50		0.20	19.00		
	Ch:00-110(12th Cross Road)	2		110.00	0.50		0.20	22.00		
	Ch:00-270 (1st B Main)	2		270.00	0.50		0.20	54.00		
	Ch:00-280 (1st C Main)	2		280.00	0.50		0.20	56.00		
	Ch:00-140(10th Cross Road)	2		140.00	0.50		0.20	28.00		
	Ch:00-96(9th Cross Road)	2		96.00	0.50		0.20	19.20		
	Ch:00-62(8th Cross Road)	2		62.00	0.50		0.20	12.40		
	Ch:00-105(7th Cross Road)	2		105.00	0.50		0.20	21.00		
	Ch:00-65(6th Cross Road)	2		65.00	0.50		0.20	13.00		
	Ch:00-64(5th Cross Road)	2		64.00	0.50		0.20	12.80		
	Soundarya layout 2nd Main									
	CH00-95(11th Cross Road)	2		95.00	0.45		0.20	17.10		
	Ch:00-85(10th Cross Road)	2		85.00	0.45		0.20	15.30		
	Ch:00-75(9th Cross Road)	2		75.00	0.45		0.20	13.50		
	Ch:00-68(8th Cross Road)	2		68.00	0.45		0.20	12.24		
	Ch:00-50(7th Cross Road)	2		50.00	0.45		0.20	9.00		
	Ch:00-43(6th Cross Road)	2		43.00	0.45		0.20	7.74		
	Ch:00-60(4th Cross Road)	2		60.00	0.45		0.20	10.80		
	Ch:000-152(3rd Cross Road)	2		152.00	0.45		0.20	27.36		
	Ch:000-100 (Cross Road)	2		100.00	0.45		0.20	18.00		
	Ch:000-225 (Cross Road)	2		225.00	0.45		0.20	40.50		
	Ch:00-125(3rd Main Road)	2		125.00	0.45		0.20	22.50		
	Ch:00-115(3rd Main Road)	2		115.00	0.45		0.20	20.70		
	Ch:115-230(3rd Main Road)	2		115.00	0.45		0.20	20.70		

Soundarya layout 1st Main								
Ch:00-530(1st Main) RHS	1		470.00	0.90		0.15	63.45	
Ch:00-260(1st Main) LHS	1		240.00	0.90		0.15	32.40	
Ch:00-90(1st A Cross Road)	2		90.00	0.45		0.15	12.15	
Ch:00-100(2nd A Cross Road)	2		100.00	0.45		0.15	13.50	
Ch:00-90(4th A Cross Road)	2		90.00	0.45		0.15	12.15	
Ch:00-90(6th A Cross Road)	2		90.00	0.45		0.15	12.15	
Ch:00-90(7th A Cross Road)	2		90.00	0.45		0.15	12.15	
Ch:00-93(8th A Cross Road)	2		93.00	0.45		0.15	12.56	
Ch:00-92(9th A Cross Road)	2		92.00	0.45		0.15	12.42	
Ch:00-90(11th A Cross Road)	2		90.00	0.45		0.15	12.15	
Ch:00-93(12th A Cross Road)	2		93.00	0.45		0.15	12.56	
Ch:00-92(13th A Cross Road)	2		92.00	0.45		0.15	12.42	
Ch:00-92(14th A Cross Road)	2		92.00	0.45		0.15	12.42	
Ch:00-95(2nd B main Road)	2		95.00	0.45		0.15	12.83	
Siddeshwara Layout								
Ch:140-200 RHS	1		60.00	0.50		0.30	9.00	
Ch:350-470 SLN Fruit Shop RHS	1		120.00	0.50		0.30	18.00	
Ch:00-80 Cross rd beside NMH Convention Hall	2		80.00	0.45		0.30	21.60	
Ch:00-70 1st cross	2		70.00	0.45		0.20	12.60	
Ch:00-85 2nd Cross	2		85.00	0.45		0.20	15.30	
Ch:00-80 3rd Cross	2		80.00	0.45		0.20	14.40	
Ch:00-80 4rd Cross	2		80.00	0.45		0.20	14.40	
Ch:00-145 8th Cross	2		135.00	0.45		0.20	24.30	
Royal Enclave Layout								
Ch:125-255 Royal Enclave Rd.	2		130.00	0.60		0.15	23.40	
Left Side cross Roads to Royal Enclave Main Rd.								
Ch:00-60 3rd Cross	2		60.00	0.50		0.15	9.00	
Ch:00-60 4th Cross	2		60.00	0.50		0.15	9.00	
Right Side cross Roads to Royal Enclave Main Rd.								
Ch:00-72 3rd Cross L shape	2		72.00	0.50		0.20	14.40	
Ch:00-32 4th Cross	2		32.00	0.50		0.20	6.40	
Ch:00-40 5th Cross	2		40.00	0.50		0.20	8.00	
Ch:40-90 5th Cross Lshape	2		50.00	0.50		0.20	10.00	
NMH Layout								
Ch:00-220 Basava Dhyana Kendra	1		187.00	0.60		0.20	22.44	
Ch:00-180 BESCOM Bagalugunte	1		162.00	0.50		0.45	36.45	
Ch:00-230 1st main	2		202.00	0.50		0.20	40.40	
Ch:00-140 2nd main	2		125.00	0.60		0.20	30.00	
Kirloskar connecting road								
Ch:00-370 4nd main	2		355.00	0.50		0.20	71.00	
NEW CC DRAIN								
Byraveshwara circle								
Ch:00-215 (From Byraveshwara Circle)	2		201.00	1.10		0.90	397.98	
Ch:00-310 (Naga Devaata Temple Road) RHS	1		294.00	1.10		0.90	291.06	
Ch:00-150 (Naga Devaata Temple Road) LHS	1		140.00	1.10		0.90	138.60	
Ch:200-310 (Naga Devaata Temple Road) LHS	1		95.00	1.10		0.90	94.05	
Ch:00-530 Soundarya layout 2nd main	2		485.00	1.10		0.90	960.30	
Ch:260-530 LHS Soundarya layout 1st main	1		250.00	1.40		1.05	367.50	
Siddeshwara Layout								
Ch:00-950 LHS	1		890.00	1.10		0.90	881.10	
Ch:00-140 RHS	1		140.00	1.10		0.90	138.60	
Ch:207-350 RHS	1		134.00	1.10		0.90	132.66	
Ch:475-950 RHS	1		438.00	1.10		0.90	433.62	
Ch:00-230 Siddeshwara Temple Road	2		205.00	1.10		0.90	405.90	
Royal Enclave Layout								
Ch:00-125 Royal Enclave Rd.	2		112.00	1.10		0.80	197.12	
New Culvert								
M.H.R. Layout								
Ch:00-490(Chetana E lavada school Frant Rd to Siddhi Vinayaka Temple)	2		10.00	1.80		1.20	43.20	
Byraveshwara circle								
Cross roads	7		6.00	1.50		1.05	66.15	

Cum

	MEENAKSHI layout								
	Cross roads		6		6.00	1.50		1.05	56.70
	Soundarya layout 2nd Main								
	Cross roads		12		6.00	1.50		1.05	113.40
	Soundarya layout 1st Main								
	Cross roads		12		6.00	1.50		1.05	113.40
	Siddeshwara Layout								
	Cross roads		10		6.00	1.50		1.05	94.50
	Royal Enclave Layout								
	Skew culvert near SWD		1		12.00	2.00		1.20	28.80
	Cross roads		3		6.00	1.50		1.05	28.35
	Recharge Pit								
	Byraveshwara circle		12		0.80			2.50	24.00
	Soundarya layout 2nd Main		10		0.80			2.50	20.00
	Soundarya layout 1st Main		20		0.80			2.50	40.00
	Siddeshwara Layout		22		0.80			2.50	44.00
	Royal Enclave Layout		6		0.80			2.50	12.00
							Total Qty	**6575.98**	**241.64**	**15,89,002.82**
4	KSRB 4-1.2 : Providing and laying in position plain cement concrete of Mix 1:3:6 with OPC @ 220kgs. with 40mm and down size graded granite metal coarse aggregates @0.892cum and fine aggregates @ 0.465cum machine mixed, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation including cost of all materials, labour, HOM curing complete as per specifications.								
	KPWD S.R 2018-19	It. No	4.2.			Pg.No.		13	
	NEW CC DRAIN								
	Byraveshwara circle								
	Ch:00-215 (From Byraveshwara Circle)		2		201.00	1.10		0.15	66.33
	Ch:00-310 (Naga Devaata Temple Road) RHS		1		294.00	1.10		0.15	48.51
	Ch:00-150 (Naga Devaata Temple Road) LHS		1		140.00	1.10		0.15	23.10
	Ch:200-310 (Naga Devaata Temple Road) LHS		1		95.00	1.10		0.15	15.68
	Ch:00-530 Soundarya layout 2nd main		2		485.00	1.10		0.15	160.05
	Ch:260-530 LHS Soundarya layout 1st main		1		250.00	1.40		0.15	52.50
	Siddeshwara Layout								
	Ch:00-950 LHS		1		890.00	1.10		0.15	146.85
	Ch:00-140 RHS		1		140.00	1.10		0.15	23.10
	Ch:207-350 RHS		1		134.00	1.10		0.15	22.11
	Ch:475-950 RHS		1		438.00	1.10		0.15	72.27
	Ch:00-230 Siddeshwara Temple Road		2		205.00	1.10		0.15	67.65
	Royal Enclave Layout								
	Ch:00-125 Royal Enclave Rd.		2		112.00	1.10		0.15	36.96
	New Culvert								
	M.H.R. Layout								
	Ch:00-490(Chetana E lavada school Frant Rd to Siddhi Vinayaka Temple)		2		10.00	1.80		0.15	5.40
	Byraveshwara circle								
	Cross roads		7		6.00	1.50		0.15	9.45
	MEENAKSHI layout								
	Cross roads		6		6.00	1.50		0.15	8.10
	Soundarya layout 2nd Main								
	Cross roads		12		6.00	1.50		0.15	16.20
	Soundarya layout 1st Main								
	Cross roads		12		6.00	1.50		0.15	16.20
	Siddeshwara Layout								
	Cross roads		10		6.00	1.50		0.15	13.50
	Royal Enclave Layout								
	Skew culvert near SWD		1		12.00	2.00		0.15	3.60
	Cross roads		3		6.00	1.50		0.15	4.05
	New Kerb PCC								
	Byraveshwara circle								
	Ch:00-215 (From Byraveshwara Circle)		2		201.00	0.20		0.10	8.04
	Ch:00-310 (Naga Devaata Temple Road) RHS		1		294.00	0.20		0.10	5.88
	Ch:00-530 Soundarya layout 2nd main		2		485.00	0.20		0.10	
	Ch:260-530 LHS Soundarya layout 1st main	Cum	1		250.00	0.20		0.10	19.40
	Siddeshwara Layout								
	Ch:00-950 LHS		2		890.00	0.20		0.10	35.60

Ch:00-230 Siddeshwara Temple Road		2		205.00	0.20		0.10	8.20		
Royal Enclave Layout										
Ch:00-125 Royal Enclave Rd.		2		112.00	0.20		0.10	4.48		
Ch:125-255 Royal Enclave Rd.		2		125.00	0.20		0.10	5.00		
CC Roads										
Royal Enclave Layout										
Ch:00-40 1st cross LHS Royal Enclave		1		40.00	5.00	5.00	0.15	30.00		
Ch:00-55 2nd Cross road Royal Enclave										
Ch:00-30		1		30.00	4.00	4.10	0.15	18.23		
Ch:30-55		1		25.00	4.10	4.10	0.15	15.38		
Ch:00-255 Royal Enclave Rd.										
Ch:00-30		1		30.00	5.50	5.40	0.15	24.53		
Ch:30-60		1		30.00	5.40	5.50	0.15	24.53		
Ch:60-90		1		30.00	5.50	5.20	0.15	24.08		
Ch:90-120		1		30.00	5.20	5.40	0.15	23.85		
Ch:120-150		1		30.00	5.50	5.40	0.15	24.53		
Ch:150-180		1		30.00	5.40	5.50	0.15	24.53		
Ch:180-210		1		30.00	5.50	5.20	0.15	24.08		
Ch:210-240		1		30.00	5.20	5.40	0.15	23.85		
Ch:240-255		1		15.00	5.40	5.60	0.15	12.38		
Left Side cross Roads to Royal Enclave Main Rd.										
Ch:00-60 3rd Cross										
Ch:00-30		1		30.00	4.50	4.40	0.15	20.03		
Ch:30-60		1		30.00	4.40	4.50	0.15	20.03		
Ch:00-60 4th Cross										
Ch:00-30		1		30.00	4.50	4.50	0.15	20.25		
Ch:30-60		1		30.00	4.50	4.50	0.15	20.25		
Right Side cross Roads to Royal Enclave Main Rd.										
Ch:00-72 3rd Cross L shape										
Ch:00-30		1		30.00	4.50	4.40	0.15	20.03		
Ch:30-60		1		30.00	4.40	4.50	0.15	20.03		
Ch:60-72		1		12.00	4.50	4.40	0.15	8.01		
Ch:00-32 4th Cross		1		32.00	4.80	4.90	0.15	23.28		
Ch:00-40 5th Cross		1		40.00	4.00	4.00	0.15	24.00		
Ch:40-90 5th Cross Lshape		1		50.00	4.50	4.50	0.15	33.75		
							Total Qty	**1377.78**	**5505.64**	**75,85,533.15**
5	KSRRB M2200-6. Providing TMT Bars Fe 500 steel reinforcement for R.C.C. work including straightening, cutting, bending, hooking, placing in position, lapping and/or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per disign (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM complete as per specification. MORTH Specification No.1600 & 2200									
KPWD Issue S.R 2020-21	It. No.	28.8.2		Pg.No.		229				
For CC Drain (60 Kg/Cum)	tonne		1	83.86				83.86		
For Culvert (90 Kg/Cum)			1	16.31				16.31		
							Total Qty	**100.17**	**65046.90**	**65,15,747.97**
6	Providing and laying plain/reinforced cement concrete for side drains using M20 nominal mix concrete with OPC at 300 kgs. with 20mm and down size granite metal coarse aggregates at 0.69 cum and fine aggregates at 0.43 cum machine mixed, well compacted for walls and bottom including centering, shuttering, cost of materials, HOM of machinery, curing etc., complete excluding cost of steel as per MORTH spec No. 1500,700,2200. including cost of materials, labour, HOM complete as per spec.									
KPWD S.R 2018-19	It. No.	4.49.3		Pg.No.		19				
Bed Concrete for New drain										
Byraveshwara circle										
Ch:00-215 (From Byraveshwara Circle)		2		201.00	0.90		0.15	54.27		
Ch:00-310 (Naga Devaata Temple Road) RHS		1		294.00	0.90		0.15	39.69		
Ch:00-150 (Naga Devaata Temple Road) LHS		1		140.00	0.90		0.15	18.90		
Ch:200-310 (Naga Devaata Temple Road) LHS		1		95.00	0.90		0.15	12.83		
Ch:00-530 Soundarya layout 2nd main		2		485.00	0.90		0.15	130.95		
Ch:260-530 LHS Soundarya layout 1st main		1		250.00	1.20		0.15	45.00		
Siddeshwara Layout										
Ch:00-950 LHS		1		890.00	0.90		0.15	120.15		
Ch:00-140 RHS		1		140.00	0.90		0.15	18.90		

	Ch:207-350 RHS								
	Ch:475-950 RHS	1		134.00	0.90		0.15	18.09	
	Ch:00-230 Siddeshwara Temple Road	1		438.00	0.90		0.15	59.13	
	Royal Enclave Layout	2		205.00	0.90		0.15	55.35	
	Ch:00-125 Royal Enclave Rd.								
	Side wall for New drain	2		112.00	0.90		0.15	30.24	
	Byraveshwara circle								
	Ch:00-215 (From Byraveshwara Circle)								
	Ch:00-310 (Naga Devaata Temple Road) RHS	2	2	201.00	0.15		0.60	72.36	
	Ch:00-150 (Naga Devaata Temple Road) LHS	1	2	294.00	0.15		0.60	52.92	
	Ch:200-310 (Naga Devaata Temple Road) LHS	1	2	140.00	0.15		0.60	25.20	
	Ch:00-530 Soundarya layout 2nd main	1	2	95.00	0.15		0.60	17.10	
	Ch:260-530 LHS Soundarya layout 1st main	2	2	485.00	0.15		0.60	174.60	
	Siddeshwara Layout	1	2	250.00	0.15		0.75	56.25	
	Ch:00-950 LHS	1	2	890.00	0.15		0.60	160.20	
	Ch:00-140 RHS	1	2	140.00	0.15		0.60	25.20	
	Ch:207-350 RHS	1	2	134.00	0.15		0.60	24.12	
	Ch:475-950 RHS	1	2	438.00	0.15		0.60	78.84	
	Ch:00-230 Siddeshwara Temple Road	Cum	2	2	205.00	0.15		0.60	73.80
	Royal Enclave Layout								
	Ch:00-125 Royal Enclave Rd.	2	2	112.00	0.15		0.50	33.60	
	New Culvert								
	M.H.R. Layout								
	Ch:00-490(Chetana E lavada school Frant Rd to Siddhi Vinayaka Temple)	2		10.00	1.80		0.20	7.20	
	Byraveshwara circle								
	Cross roads	7		6.00	1.50		0.20	12.60	
	MEENAKSHI layout								
	Cross roads	6		6.00	1.50		0.20	10.80	
	Soundarya layout 2nd Main								
	Cross roads	12		6.00	1.50		0.20	21.60	
	Soundarya layout 1st Main								
	Cross roads	12		6.00	1.50		0.20	21.60	
	Siddeshwara Layout								
	Cross roads	10		6.00	1.50		0.20	18.00	
	Royal Enclave Layout								
	Skew culvert near SWD	1		12.00	1.80		0.20	4.32	
	Cross roads	3		6.00	1.50		0.20	5.40	
	Sidewall for culvert								
	M.H.R. Layout								
	Ch:00-490(Chetana E lavada school Frant Rd to Siddhi Vinayaka Temple)	2	2	10.00	0.20		0.60	4.80	
	Byraveshwara circle								
	Cross roads	7	2	6.85	0.20		0.60	11.51	
	MEENAKSHI layout								
	Cross roads	6	2	6.00	0.20		0.60	8.64	
	Soundarya layout 2nd Main								
	Cross roads	12	2	5.50	0.20		0.60	15.84	
	Soundarya layout 1st Main								
	Cross roads	12	2	6.00	0.20		0.60	17.28	
	Siddeshwara Layout								
	Cross roads	10	2	6.00	0.20		0.60	14.40	
	Royal Enclave Layout								
	Skew culvert near SWD	1	2	12.00	0.20		0.60	2.88	
	Cross roads	3	2	6.00	0.20		0.60	4.32	
							Totai Qty	**1578.87**	**7070.20**	**111,62,926.67**

7 Providing granite slabs selected quality roughly dressed and fixed in cement mortar (1:6) including fixing curing etc., complete.

KPWD S.R 2018-19	It. No.	5.31.1	Pg no.	27					
a)7.5cm thick									
Byraveshwara circle									
30% Damage of BS Slab Drain		1		49.20	1.50			73.80	
M.H.R. Layout									
30% Damage of BS Slab Drain		1		687.00	1.50			1030.50	
MEENAKSHI layout									
30% Damage of BS Slab Drain		1		936.60	1.50			1404.90	

	Soundarya layout 2nd Main										
	30% Quantity of item no 1		1		778.80	1.50			1168.20		
	Soundarya layout 1st Main										
	30% Quantity of item no 1		1		607.20	1.50			910.80		
	Royal Enclave Layout										
	30% Quantity of item no 1		1		179.40	1.50			269.10		
	Siddeshwara Layout	Sqm									
	30% Quantity of item no 1		1		270.00	1.50			405.00		
	NMH Layout										
	30% Quantity of item no 1		1		160.80	1.50			241.20		
	Kirloskar connecting road										
	30% Quantity of item no 1		1		213.00	1.50			319.50		
								Total Qty	**5823.00**	**742.00**	**43,20,666.00**
	B) 10cm thick										
	Royal Enclave Layout										
	Ch:125-255 Royal Enclave Rd. missind and damaged		2		26.00	1.00			52.00		
								Total Qty	**52.00**	**966.72**	**50,269.44**
8	Providing and laying 100mm thick pre-cast cover slabs over drains of width m not exceeding 800 mm using M20 concrete reinforced with steel @ 6.00 kg/Sqm, slabs jointed in CM 1:3 proportion and nicely finished including providing holes in the Cover slabs wherever necessary for easy drainage of surface water including of labour, materials, HOM, curing, lead and lift charges etc, Complete as per MORTH specifications No. 1500,1700 (0.8m and 0.9m width slab)										
	KPWD S.R 2018-19	It. No.	37.66		Pg no.		272				
	New Slab for CC Drain										
	Byraveshwara circle										
	Ch:00-215 (From Byraveshwara Circle)		2		120.60	1.00			241.20		
	Ch:00-310 (Naga Devaata Temple Road) RHS		2		147.00	1.00			294.00		
	Ch:00-110 1st Cross missing and damaged		2		22.00	1.00			44.00		
	Ch:00-112 2nd Cross missing and damaged		2		22.40	1.00			44.80		
	Ch:00-110-3rd Cross missing and damaged		2		22.00	1.00			44.00		
	Ch:00-88 4th Cross missing and damaged		2		16.00	1.00			32.00		
	Ch:00-82 5th Cross missing and damaged	Sqm	2		16.40	1.00			32.80		
	Ch:00-530 Soundarya layout 2nd main		2		339.50	1.00			679.00		
	Ch:00-530 RHS Soundarya layout 1st main missing and damaged slab		1		94.00	1.20			112.80		
	Ch:00-260 LHS Soundarya layout 1st main missing and damaged slab		1		48.00	1.20			57.60		
	Ch:260-530 LHS Soundarya layout 1st main		1		250.00	1.20			300.00		
	Siddeshwara Layout										
	Ch:00-950		2		712.00	1.00			1424.00		
	Ch:00-230 Siddeshwara Temple Road		2		205.00	1.00			410.00		
	Royal Enclave Layout										
	Ch:00-125 Royal Enclave Rd.		2		44.80	1.00			89.60		
								Total Qty	**3805.80**	**1145.86**	**43,60,913.99**
9	Providing and laying Pre Cast Drain Cover slabs of 250mm thick of mix M20 using graded granite jelly 20mm down size with steel reinforcement, including from work, lift charges, curing and concrete finished surfaces on both side etc. complete and as per drawing and direction of Engineer-in-charge of work (data Rate enclosed)										
	Approved Data Rate										
	M.H.R. Layout										
	Ch:00-490(Chetana E lavada school Frant Rd to Siddhi Vinayaka Temple)		2		10.00	1.80			36.00		
	Byraveshwara circle										
	Cross roads		7		6.85	1.50			71.93		
	MEENAKSHI layout										
	Cross roads		6		6.00	1.50			54.00		
	Soundarya layout 2nd Main										
	Cross roads		12		5.50	1.50			99.00		
	Soundarya layout 1st Main	Sqm									
	Cross roads		12		6.00	1.50			108.00		
	Siddeshwara Layout										
	Cross roads		10		6.00	1.50			90.00		

	Royal Enclave Layout										
	Skew culvert near SWD		1		12.00	1.80			21.60		
	Cross roads		3		6.00	1.50			27.00		
	Open culvert in NMH layout Ch:00-180		1		8.00	2.00			16.00		
								Total Qty	523.55	3306.00	17,30,790.18
10	Providing and fixing Pre cast solid concrete kerb stones of size 450 x 200 x 400 mm made out of CC 1:2:4 and finished with CM 1:3 plastering and finishing cutting etc., complete.										
	KPWD S.R 2018-19	It. No.			5.29.1.		Pg.No.	27			
	Byraveshwara circle	no									
	Ch:00-215 (From Byraveshwara Circle)		2		447				893		
	Ch:00-310 (Naga Devaata Temple Road) RHS		2		653				1307		
	Ch:00-530 Soundarya layout 2nd main		2		1078				2156		
	Ch:260-530 LHS Soundarya layout 1st main		1		556				556		
	Ch:00-260 LHS Soundarya layout 1st main consider 30% damaged and missing kerb		1		160				160		
	Ch:00-530 RHS Soundarya layout 1st main consider 30% damaged and missing kerb		1		313				313		
	Siddeshwara Layout										
	Ch:00-950 LHS		2		1978				3956		
	Ch:00-230 Siddeshwara Temple Road		2		456				911		
	Royal Enclave Layout										
	Ch:00-125 Royal Enclave Rd.		2		249				498		
	Ch:125-255 Royal Enclave Rd.		2		278				556		
								Total Qty	11304	477.00	53,92,227.42
11	KSRRB 800-1. Painting two coats after filling the surface with synthetic enamel paint in approved shades on new plastered concrete surfaces, with materials, labour complete as per spec. MORTH Chap 8.										
	KPWD S.R 2018-19	It. No.			24.1.		Pg.No.	180			
	Byraveshwara circle	Sqm									
	Ch:00-215 (From Byraveshwara Circle)		2		201.00			0.45	180.90		
	Ch:00-310 (Naga Devaata Temple Road) RHS		2		294.00			0.45	264.60		
	Ch:00-530 Soundarya layout 2nd main		2		300.00			0.45	270.00		
	Ch:00-530 Soundarya layout 1st main		2		470.00			0.45	423.00		
	Siddeshwara Layout										
	Ch:00-950 LHS		2		890.00			0.45	801.00		
	Ch:00-230 Siddeshwara Temple Road		2		203.00			0.45	182.70		
	Royal Enclave Layout										
	Ch:00-125 Royal Enclave Rd.		2		112.00			0.45	100.80		
	Ch:125-255 Royal Enclave Rd.		2		125.00			0.45	112.50		
								Total Qty	2335.50	84.80	1,98,050.40
	ROADWORKS										
12	KSRRB 300-50. Scarifying bituminous course 50mm to 75mm thick along with premix carpet / surface dressing by mechanical means attached with scarifier without disturbing the base and stacking the debris including cost of all labour charges, HOM complete as per specifications. MORTH I Chapter 3										
	KPWD S.R 2018-19	It. No.			19.56		Pg.No.	146			
	Byraveshwara circle										
	Scarifying										
	Ch:00-310 (Naga Devaata Temple Road)		1		310.00	5.00			1550.00		
	Ch:00-215 (From Byraveshwara Circle)		1		215.00	5.00			1075.00		
	Ch:00-110 1st Cross		1		110.00	4.00			440.00		
	Ch:00-110-3rd Cross		1		110.00	3.00			330.00		
	M.H.R. Layout										
	Ch:00-490(Chetana E lavada school Frant Rd to Siddhi Vinayaka Temple)		1		490.00	5.00			2450.00		
	Ch:00-115 (8th Cross Road)		1		115.00	5.00			575.00		
	Ch:00-210 (1st main Road)		1		210.00	2.80			588.00		
	MEENAKSHI layout										
	Ch:00-280(1st Main)		1		280.00	5.20			1456.00		
	Ch:00-280(3rd Main)		1		280.00	4.80			1344.00		
	Ch:00-95(14th Cross Road)		1		95.00	5.20			494.00		
	Ch:00-110(12th Cross Road)		1		110.00	4.80			528.00		
	Ch:00-140(10th Cross Road)		1		140.00	4.50			630.00		
	Ch:00-96(9th Cross Road)		1		96.00	4.40			422.40		

Ch:00-62(8th Cross Road)		1		62.00	4.50			279.00		
Ch:00-105(7th Cross Road)		1		105.00	4.40			462.00		
Ch:00-65(6th Cross Road)		1		65.00	4.00			260.00		
Ch:00-64(5th Cross Road)		1		64.00	4.50			288.00		
Ch:00-63(4th Cross Road)		1		63.00	4.50			283.50		
Ch:00-65(3rd Cross Road)		1		65.00	4.40			286.00		
Ch:00-66(2nd Cross Road)		1		66.00	4.50			297.00		
Ch:00-80(1st Cross Road)		1		80.00	4.50			360.00		
Soundarya layout 2nd Main										
Ch:00-530(2nd Main Road)		1		530.00	6.00			3180.00		
Ch00-95(11th Cross Road)		1		95.00	4.80			456.00		
Ch:00-85(10th Cross Road)		1		85.00	4.80			408.00		
Ch:00-75(9th Cross Road)		1		75.00	4.80			360.00		
Ch:00-68(8th Cross Road)		1		68.00	5.00			340.00		
Ch:00-50(7th Cross Road)		1		50.00	4.80			240.00		
Ch:00-43(6th Cross Road)		1		43.00	5.00			215.00		
Ch:00-60(4th Cross Road)		1		60.00	4.90			294.00		
Ch:00-152(3rd Cross Road)		1		152.00	5.10			775.20		
Ch:00-100 (Cross Road)		1		100.00	5.10			510.00		
Ch:00-225 (Cross Road)		1		225.00	5.00			1125.00		
Ch:00-125(3rd Main Road)		1		125.00	4.50			562.50		
Ch:00-230(3rd Main Road)		1		230.00	4.00			920.00		
Soundarya layout 1st Main										
Ch:00-530(1st Main)		1		530.00	6.00			3180.00		
Ch:00-90(1st A Cross Road)		1		90.00	5.00			450.00		
Ch:00-100(2nd A Cross Road)		1		100.00	4.20			420.00		
Ch:00-90(4th A Cross Road)		1		90.00	4.80			432.00		
Ch:00-90(6th A Cross Road)		1		90.00	4.50			405.00		
Ch:00-90(7th A Cross Road)	Sqm	1		90.00	4.60			414.00		
Ch:00-93(8th A Cross Road)		1		93.00	5.00			465.00		
Ch:00-92(9th A Cross Road)		1		92.00	5.10			469.20		
Ch:00-90(11th A Cross Road)		1		90.00	5.30			477.00		
Ch:00-93(12th A Cross Road)		1		93.00	4.80			446.40		
Ch:00-92(13th A Cross Road)		1		92.00	4.90			450.80		
Ch:00-92(14th A Cross Road)		1		92.00	5.00			460.00		
Ch:00-95(2nd B main Road)		1		95.00	4.00			380.00		
Siddeshwara Layout										
Ch:00-195		1		195.00	4.80			936.00		
Ch:195-325		1		130.00	5.20			676.00		
Ch:325-465		1		140.00	5.00			700.00		
Ch:465-565		1		100.00	4.70			470.00		
Ch:565-605		1		40.00	4.80			192.00		
Ch:605-755		1		150.00	5.00			750.00		
Ch:755-950		1		195.00	4.80			936.00		
Ch:00-100 NMH Public school road		1		100.00	5.00			500.00		
Ch:00-145 Royal Enclave Rd.		1		145.00	5.20			754.00		
Royal Enclave Layout										
Ch:00-125 Royal Enclave Rd.		1		125.00	5.00			625.00		
Ch:125-255 Royal Enclave Rd.		1		130.00	4.80			624.00		
Left Side cross Roads to Royal Enclave Main Rd.										
Ch:00-60 3rd Cross		1		60.00	5.00			300.00		
Ch:00-60 4th Cross		1		60.00	5.20			312.00		
Right Side cross Roads to Royal Enclave Main Rd.										
Ch:00-72 3rd Cross L shape		1		72.00	4.80			345.60		
Ch:00-32 4th Cross		1		32.00	4.60			147.20		
Ch:00-40 5th Cross		1		40.00	5.00			200.00		
Ch:40-90 5th Cross L shape		1		50.00	4.70			235.00		
Ch:00-80 Cross rd beside NMH Convention Hall		1		80.00	4.30			344.00		
Ch:00-230 Siddeshwara Temple Road		1		230.00	4.00			920.00		
Ch:00-70 1st cross		1		70.00	4.20			294.00		
Ch:00-85 2nd Cross		1		85.00	4.60			391.00		
Ch:00-80 3rd Cross		1		80.00	4.80			384.00		
Ch:00-80 4th Cross		1		80.00	4.80			384.00		
NMH Layout										
Ch:00-220 Basava Dhyana Kendra		1		220.00	4.20			924.00		
Ch:00-180 BESCOM Bagalugunte		1		180.00	4.80			864.00		
Ch:00-230 1st main		1		230.00	4.80			1104.00		

	Ch:00-140 2nd main		1		140.00	4.90			686.00		
	Kirloskar connecting road										
	Ch:00-370 4nd main		1		370.00	4.80			1776.00		
								Total Qty	**49006.80**	**41.34**	**20,25,941.11**
	Leading Charges for 16Km	cum	1		49006.80			0.08	3920.54		
								Total Qty	**3920.54**	**43.42**	**1,70,220.61**
13	KSRRB M300-14. Excavation for roadwork in all types of soil by mechanical means including cutting and loading to tippers, trimming bottom and side slopes, in accordance with requirements of lines, grades and cross sections, and transportation with a lead of 25.00 km and complete as per specifications.										
	KPWD S.R 2018-19	It. No.			19.14	Pg.No.		143			
	New BC Road										
	Byraveshwara circle										
	Ch:00-110 1st Cross										
	Ch:00-30		1		30.00	4.50	4.50	0.43	58.05		
	Ch:30-60		1		30.00	4.50	4.30	0.43	56.76		
	Ch:60-90		1		30.00	4.30	4.40	0.43	56.12		
	Ch:90-110		1		20.00	4.40	4.60	0.43	38.70		
	Ch:00-112 2nd Cross										
	Ch:00-30		1		30.00	5.00	5.00	0.43	64.50		
	Ch:30-60		1		30.00	4.80	4.90	0.43	62.57		
	Ch:60-90		1		30.00	4.90	5.10	0.43	64.50		
	Ch:90-112		1		22.00	5.10	4.90	0.43	47.30		
	Ch:00-110-3rd Cross										
	Ch:00-30		1		30.00	4.00	4.00	0.43	51.60		
	Ch:30-60		1		30.00	3.90	4.00	0.43	50.96		
	Ch:60-90		1		30.00	4.00	3.80	0.43	50.31		
	Ch:90-110		1		20.00	3.80	3.80	0.43	32.68		
	Ch:00-88 4th Cross										
	Ch:00-30		1		30.00	4.50	4.40	0.43	57.41		
	Ch:30-60		1		30.00	4.40	4.60	0.43	58.05		
	Ch:60-88		1		28.00	4.60	4.30	0.43	53.58		
	Ch:00-82 5th Cross										
	Ch:00-30		1		30.00	4.00	3.80	0.43	50.31		
	Ch:30-60		1		30.00	3.80	4.00	0.43	50.31		
	Ch:60-82		1		22.00	4.00	3.80	0.43	36.89		
	M.H.R. Layout										
	Ch:00-490(Chetana E lavada school Frant Rd to Siddhi Vinayaka Temple)										
	Ch:00-30		1		30.00	5.30	5.10	0.43	67.08		
	Ch:30-60		1		30.00	5.10	5.40	0.43	67.73		
	Ch:60-90		1		30.00	5.40	5.50	0.43	70.31		
	Ch:90-120		1		30.00	5.50	5.50	0.43	70.95		
	Ch:120-150		1		30.00	5.50	5.00	0.43	67.73		
	Ch:150-180		1		30.00	5.00	5.00	0.43	64.50		
	Ch:180-210		1		30.00	5.20	5.50	0.43	69.02		
	Ch:210-240		1		30.00	5.50	5.20	0.43	69.02		
	Ch:240-270		1		30.00	5.20	5.00	0.43	65.79		
	Ch:270-300		1		30.00	5.00	5.00	0.43	64.50		
	Ch:300-330		1		30.00	5.20	5.20	0.43	67.08		
	Ch:330-360		1		30.00	5.20	5.20	0.43	67.08		
	Ch:360-390		1		30.00	5.20	5.50	0.43	69.02		
	Ch:390-420		1		30.00	5.50	5.20	0.43	69.02		
	Ch:420-450		1		30.00	5.20	5.00	0.43	65.79		
	Ch:450-480		1		30.00	5.00	5.00	0.43	64.50		
	Ch:480-490		1		10.00	5.00	5.00	0.43	21.50		
	Ch:00-110 (4th Cross Road)										
	Ch:00-30		1		30.00	4.10	3.90	0.43	51.60		
	Ch:30-60		1		30.00	3.90	4.00	0.43	50.96		
	Ch:60-90		1		30.00	4.00	3.90	0.43	50.96		
	Ch:90-110		1		20.00	3.90	4.20	0.43	34.83		
	Ch:00-80 (5th Cross Road)										
	Ch:00-30		1		30.00	4.00	4.00	0.43	51.60		
	Ch:30-60		1		30.00	3.80	4.20	0.43	51.60		
	Ch:60-80		1		20.00	4.20	3.90	0.43	34.83		
	Ch:00-75 (6th Cross Road)										
	Ch:00-30		1		30.00	5.90	5.80	0.43	75.47		
	Ch:30-60		1		30.00	5.80	5.90	0.43	75.47		
	Ch:60-75		1		15.00	5.90	5.90	0.43	38.06		
	Ch:00-110 (7th Cross Road)										
	Ch:00-30		1		30.00	5.00	4.80	0.43	63.21		

Ch:30-60	1		30.00	4.80	5.20	0.43	64.50		
Ch:60-90	1		30.00	5.20	5.00	0.43	65.79		
Ch:90-110	1		20.00	5.00	5.00	0.43	43.00		
Ch:00-115 (8th Cross Road)									
Ch:00-30	1		30.00	4.90	4.80	0.43	62.57		
Ch:30-60	1		30.00	4.80	4.90	0.43	62.57		
Ch:60-90	1		30.00	4.90	5.00	0.43	63.86		
Ch:90-115	1		25.00	5.00	4.90	0.43	53.21		
Ch:00-210(1st Main)									
Ch:00-30	1		30.00	4.50	4.50	0.43	58.05		
Ch:30-60	1		30.00	4.50	4.50	0.43	58.05		
Ch:60-90	1		30.00	4.50	4.50	0.43	58.05		
Ch:90-120	1		30.00	4.50	4.50	0.43	58.05		
Ch:120-150	1		30.00	4.50	4.60	0.43	58.70		
Ch:150-180	1		30.00	4.60	4.60	0.43	59.34		
Ch:180-210	1		30.00	4.60	4.60	0.43	59.34		
MEENAKSHI layout									
Ch:00-280(1st Main)									
Ch:00-30	1		30.00	5.50	5.40	0.43	70.31		
Ch:30-60	1		30.00	5.40	5.50	0.43	70.31		
Ch:60-90	1		30.00	5.50	5.20	0.43	69.02		
Ch:90-120	1		30.00	5.20	5.40	0.43	68.37		
Ch:120-150	1		30.00	5.40	5.60	0.43	70.95		
Ch:150-180	1		30.00	5.60	5.40	0.43	70.95		
Ch:180-210	1		30.00	5.40	5.50	0.43	70.31		
Ch:210-240	1		30.00	5.50	5.50	0.43	70.95		
Ch:240-270	1		30.00	5.50	5.20	0.43	69.02		
Ch:270-280	1		10.00	5.20	5.40	0.43	22.79		
Ch:00-280(2nd Main)									
Ch:00-30	1		30.00	5.00	5.00	0.43	64.50		
Ch:30-60	1		30.00	5.00	4.80	0.43	63.21		
Ch:60-90	1		30.00	4.80	5.20	0.43	64.50		
Ch:90-120	1		30.00	5.20	4.60	0.43	63.21		
Ch:120-150	1		30.00	4.60	5.00	0.43	61.92		
Ch:150-180	1		30.00	5.00	4.80	0.43	63.21		
Ch:180-210	1		30.00	4.80	5.20	0.43	64.50		
Ch:210-240	1		30.00	5.20	4.80	0.43	64.50		
Ch:240-270	1		30.00	4.80	5.20	0.43	64.50		
Ch:270-280	1		10.00	5.20	5.00	0.43	21.93		
Ch:00-270(1st B Main)									
Ch:00-30	1		30.00	5.20	5.20	0.43	67.08		
Ch:30-60	1		30.00	5.20	5.20	0.43	67.08		
Ch:60-90	1		30.00	5.20	5.20	0.43	67.08		
Ch:90-120	1		30.00	5.20	5.20	0.43	67.08		
Ch:120-150	1		30.00	5.20	5.20	0.43	67.08		
Ch:150-180	1		30.00	5.20	5.30	0.43	67.73		
Ch:180-210	1		30.00	5.30	5.30	0.43	68.37		
Ch:210-240	1		30.00	5.30	5.30	0.43	68.37		
Ch:240-270	1		30.00	5.30	5.30	0.43	68.37		
Ch:00-280(1st C Main)									
Ch:00-30	1		30.00	5.50	5.50	0.43	70.95		
Ch:30-60	1		30.00	5.50	5.50	0.43	70.95		
Ch:60-90	1		30.00	5.50	5.50	0.43	70.95		
Ch:90-120	1		30.00	5.50	5.50	0.43	70.95		
Ch:120-150	1		30.00	5.50	5.50	0.43	70.95		
Ch:150-180	1		30.00	5.50	5.50	0.43	70.95		
Ch:180-210	1		30.00	5.50	5.40	0.43	70.31		
Ch:210-240	1		30.00	5.40	5.40	0.43	69.66		
Ch:240-270	1		30.00	5.40	5.40	0.43	69.66		
Ch:270-280	1		10.00	5.40	5.40	0.43	23.22		
Ch:00-95(14th Cross Road)									
Ch:00-30	1		30.00	5.00	4.80	0.43	63.21		
Ch:30-60	1		30.00	4.80	5.00	0.43	63.21		
Ch:60-95	1		35.00	5.00	5.20	0.43	76.76		
Ch:00-110(12th Cross Road)									
Ch:00-30	1		30.00	5.00	4.80	0.43	63.21		
Ch:30-60	1		30.00	4.80	5.20	0.43	64.50		
Ch:60-90	1		30.00	5.20	4.80	0.43	64.50		
Ch:90-110	1		20.00	4.80	4.90	0.43	41.71		
Ch:00-140(10th Cross Road)									

Ch:00-30	1		30.00	4.50	4.40	0.43	57.41		
Ch:30-60	1		30.00	4.40	4.50	0.43	57.41		
Ch:60-90	1		30.00	4.50	4.00	0.43	54.83		
Ch:90-120	1		30.00	4.00	4.20	0.43	52.89		
Ch:120-140	1		20.00	4.20	4.40	0.43	36.98		
Ch:00-96(9th Cross Road)									
Ch:00-30	1		30.00	4.50	4.40	0.43	57.41		
Ch:30-60	1		30.00	4.40	4.50	0.43	57.41		
Ch:60-96	1		36.00	4.50	4.40	0.43	68.89		
Ch:00-62(8th Cross Road)									
Ch:00-30	1		30.00	4.50	4.40	0.43	57.41		
Ch:30-62	1		32.00	4.40	4.50	0.43	61.23		
Ch:00-105(7th Cross Road)									
Ch:00-30	1		30.00	4.50	4.40	0.43	57.41		
Ch:30-60	1		30.00	4.40	4.50	0.43	57.41		
Ch:60-90	1		30.00	4.50	4.00	0.43	54.83		
Ch:90-105	1		15.00	4.00	4.20	0.43	26.45		
Ch:00-65(6th Cross Road)									
Ch:00-30	1		30.00	4.50	4.40	0.43	57.41		
Ch:30-65	1		35.00	4.40	4.50	0.43	66.97		
Ch:00-64(5th Cross Road)									
Ch:00-30	1		30.00	4.50	4.40	0.43	57.41		
Ch:30-64	1		34.00	4.40	4.50	0.43	65.06		
Ch:00-63(4th Cross Road)									
Ch:00-30	1		30.00	4.50	4.40	0.43	57.41		
Ch:30-63	1		33.00	4.40	4.50	0.43	63.15		
Ch:00-65(3rd Cross Road)									
Ch:00-30	1		30.00	4.50	4.40	0.43	57.41		
Ch:30-65	1		35.00	4.40	4.50	0.43	66.97		
Ch:00-66(2nd Cross Road)									
Ch:00-30	1		30.00	4.50	4.40	0.43	57.41		
Ch:30-66	1		36.00	4.40	4.50	0.43	68.89		
Ch:00-80(1st Cross Road)									
Ch:00-30	1		30.00	4.50	4.50	0.43	58.05		
Ch:30-60	1		30.00	4.50	4.40	0.43	57.41		
Ch:60-80	1		20.00	4.40	4.50	0.43	38.27		
Soundarya layout 2nd Main									
Ch00-95(11th Cross Road)									
Ch:00-30	1		30.00	5.00	4.80	0.43	63.21		
Ch:30-60	1		30.00	4.80	5.20	0.43	64.50		
Ch:60-95	1		35.00	5.20	4.80	0.43	75.25		
Ch:00-85(10th Cross Road)									
Ch:00-30	1		30.00	5.00	4.80	0.43	63.21		
Ch:30-60	1		30.00	4.80	5.20	0.43	64.50		
Ch:60-85	1		25.00	5.20	4.80	0.43	53.75		
Ch:00-75(9th Cross Road)									
Ch:00-30	1		30.00	5.00	4.80	0.43	63.21		
Ch:30-60	1		30.00	4.80	5.20	0.43	64.50		
Ch:60-75	1		15.00	5.20	4.80	0.43	32.25		
Ch:00-68(8th Cross Road)									
Ch:00-30	1		30.00	5.00	4.80	0.43	63.21		
Ch:30-68	1		38.00	4.80	5.20	0.43	81.70		
Ch:00-50(7th Cross Road)									
Ch:00-30	1		30.00	5.00	4.80	0.43	63.21		
Ch:30-50	1		20.00	4.80	5.20	0.43	43.00		
Ch:00-43(6th Cross Road)									
Ch:00-30	1		30.00	5.00	4.80	0.43	63.21		
Ch:30-43	1		13.00	4.80	5.20	0.43	27.95		
Ch:00-60(4th Cross Road)									
Ch:00-30	1		30.00	5.00	4.80	0.43	63.21		
Ch:30-60	1		30.00	4.80	5.20	0.43	64.50		
Ch:00-152(3rd Cross Road)									
Ch:00-30	1		30.00	5.00	4.80	0.43	63.21		
Ch:30-60	1		30.00	4.80	5.20	0.43	64.50		
Ch:60-90	1		30.00	5.20	4.80	0.43	64.50		
Ch:90-120	1		30.00	4.80	5.20	0.43	64.50		
Ch:120-152	1		32.00	5.20	5.00	0.43	70.18		
Ch:00-100 (Cross Road)									
Ch:00-30	1		30.00	5.00	4.80	0.43	63.21		
Ch:30-60	1		30.00	4.80	5.20	0.43	64.50		

Ch:60-90	1		30.00	5.20	4.80	0.43	64.50		
Ch:90-100	1		10.00	4.80	5.20	0.43	21.50		
Ch:00-225 (Cross Road)									
Ch:00-30	1		30.00	5.50	5.40	0.43	70.31		
Ch:30-60	1		30.00	5.40	5.50	0.43	70.31		
Ch:60-90	1		30.00	5.50	5.20	0.43	69.02		
Ch:90-120	1		30.00	5.20	5.40	0.43	68.37		
Ch:120-150	1		30.00	5.40	5.40	0.43	69.66		
Ch:150-180	1		30.00	5.40	5.50	0.43	70.31		
Ch:180-210	1		30.00	5.50	5.20	0.43	69.02		
Ch:210-225	1		15.00	5.20	5.40	0.43	34.19		
Ch:00-125(3rd Main Road)									
Ch:00-30	1		30.00	5.00	4.80	0.43	63.21		
Ch:30-60	1		30.00	4.80	5.20	0.43	64.50		
Ch:60-90	1		30.00	5.20	4.80	0.43	64.50		
Ch:90-120	1		35.00	4.80	5.20	0.43	75.25		
Ch:00-230(3rd Main Road)									
Ch:00-30	1		30.00	5.00	4.80	0.43	63.21		
Ch:30-60	1		30.00	4.80	5.20	0.43	64.50		
Ch:60-90	1		30.00	5.20	4.80	0.43	64.50		
Ch:90-120	1		30.00	4.80	5.20	0.43	64.50		
Ch:120-150	1		30.00	5.20	4.80	0.43	64.50		
Ch:150-180	1		30.00	4.80	5.20	0.43	64.50		
Ch:180-210	1		30.00	5.20	4.80	0.43	64.50		
Ch:210-230	1		20.00	4.80	5.20	0.43	43.00		
Soundarya layout 1st Main									
Ch:00-90(1st A Cross Road)									
Ch:00-30	1		30.00	5.00	4.80	0.43	63.21		
Ch:30-60	1		30.00	4.80	5.20	0.43	64.50		
Ch:60-90	1		30.00	5.20	4.80	0.43	64.50		
Ch:00-100(2nd A Cross Road)									
Ch:00-30	1		30.00	5.00	4.80	0.43	63.21		
Ch:30-60	1		30.00	4.80	5.20	0.43	64.50		
Ch:60-90	1		30.00	5.20	4.80	0.43	64.50		
Ch:90-100	1		10.00	4.80	4.90	0.43	20.86		
Ch:00-90(4th A Cross Road)									
Ch:00-30	1		30.00	5.00	4.80	0.43	63.21		
Ch:30-60	1		30.00	4.80	5.20	0.43	64.50		
Ch:60-90	1		30.00	5.20	4.80	0.43	64.50		
Ch:00-90(6th A Cross Road)									
Ch:00-30	1		30.00	5.00	4.80	0.43	63.21		
Ch:30-60	1		30.00	4.80	5.20	0.43	64.50		
Ch:60-90	1		30.00	5.20	4.80	0.43	64.50		
Ch:00-90(7th A Cross Road)									
Ch:00-30	1		30.00	5.00	4.90	0.43	63.86		
Ch:30-60	1		30.00	4.90	5.20	0.43	65.15		
Ch:60-90	1		30.00	5.20	4.80	0.43	64.50		
Ch:00-93(8th A Cross Road)									
Ch:00-30	1		30.00	5.00	4.80	0.43	63.21		
Ch:30-60	1		30.00	4.80	5.20	0.43	64.50		
Ch:60-93	1		33.00	5.20	4.80	0.43	70.95		
Ch:00-92(9th A Cross Road)									
Ch:00-30	1		30.00	5.00	4.90	0.43	63.86		
Ch:30-60	1		30.00	4.90	5.20	0.43	65.15		
Ch:60-92	1		32.00	5.20	4.80	0.43	68.80		
Ch:00-90(11th A Cross Road)									
Ch:00-30	1		30.00	5.00	4.80	0.43	63.21		
Ch:30-60	1		30.00	4.80	5.20	0.43	64.50		
Ch:60-90	1		30.00	5.20	4.80	0.43	64.50		
Ch:00-93(12th A Cross Road)									
Ch:00-30	1		30.00	5.00	4.80	0.43	63.21		
Ch:30-60	1		30.00	4.80	5.20	0.43	64.50		
Ch:60-93	1		33.00	5.20	4.80	0.43	70.95		
Ch:00-92(13th A Cross Road)									
Ch:00-30	1		30.00	5.00	4.80	0.43	63.21		
Ch:30-60	1		30.00	4.80	5.20	0.43	64.50		
Ch:60-92	1		32.00	5.20	4.80	0.43	68.80		
Ch:00-92(14th A Cross Road)									
Ch:00-30	1		30.00	5.00	4.80	0.43	63.21		
Ch:30-60	1		30.00	4.80	5.20	0.43	64.50		

Cum

Ch:60-92								
Ch:00-95(2nd B main Road)								
Ch:00-30	1		32.00	5.20	4.80	0.43	68.80	
Ch:30-60								
Ch:60-95	1		30.00	5.00	5.10	0.43	65.15	
Siddeshwara Layout	1		30.00	5.10	5.20	0.43	66.44	
Ch:00-950	1		35.00	5.20	5.20	0.43	78.26	
Ch:00-30								
Ch:30-60								
Ch:60-90	1		30.00	5.50	5.40	0.43	70.31	
Ch:90-120	1		30.00	5.40	5.50	0.43	70.31	
Ch:120-150	1		30.00	5.50	5.20	0.43	69.02	
Ch:150-180	1		30.00	5.20	5.40	0.43	68.37	
Ch:180-210	1		30.00	5.40	5.40	0.43	69.66	
Ch:210-240	1		30.00	5.40	5.50	0.43	70.31	
Ch:240-270	1		30.00	5.50	5.20	0.43	69.02	
Ch:270-300	1		30.00	5.20	5.40	0.43	68.37	
Ch:300-330	1		30.00	5.40	5.40	0.43	69.66	
Ch:330-360	1		30.00	5.40	5.50	0.43	70.31	
Ch:360-390	1		30.00	5.50	5.20	0.43	69.02	
Ch:390-420	1		30.00	5.20	5.40	0.43	68.37	
Ch:420-450	1		30.00	5.40	5.40	0.43	69.66	
Ch:450-480	1		30.00	5.40	5.50	0.43	70.31	
Ch:480-510	1		30.00	5.50	5.20	0.43	69.02	
Ch:510-540	1		30.00	5.20	5.40	0.43	68.37	
Ch:540-570	1		30.00	5.40	5.40	0.43	69.66	
Ch:570-600	1		30.00	5.40	5.50	0.43	70.31	
Ch:600-630	1		30.00	5.50	5.20	0.43	69.02	
Ch:630-660	1		30.00	5.20	5.40	0.43	68.37	
Ch:660-690	1		30.00	5.40	5.40	0.43	69.66	
Ch:690-720	1		30.00	5.40	5.50	0.43	70.31	
Ch:720-750	1		30.00	5.50	5.20	0.43	69.02	
Ch:750-780	1		30.00	5.20	5.40	0.43	68.37	
Ch:780-810	1		30.00	5.40	5.40	0.43	69.66	
Ch:810-840	1		30.00	5.40	5.50	0.43	70.31	
Ch:840-870	1		30.00	5.50	5.20	0.43	69.02	
Ch:870-900	1		20.00	5.20	5.40	0.43	45.58	
Ch:900-930								
Ch:930-950	1		30.00	5.00	4.80	0.43	63.21	
Ch:00-100 NMH Public school road	1		30.00	4.80	5.20	0.43	64.50	
Ch:00-30	1		30.00	5.20	4.80	0.43	64.50	
Ch:30-60	1		10.00	4.80	5.00	0.43	21.07	
Ch:60-90								
Ch:90-100	1		30.00	5.20	5.20	0.43	67.08	
Ch:00-145 8th cross	1		30.00	5.20	5.20	0.43	67.08	
Ch:00-30	1		30.00	5.20	5.20	0.43	67.08	
Ch:30-60	1		30.00	5.20	5.30	0.43	67.73	
Ch:60-90	1		25.00	5.30	5.30	0.43	56.98	
Ch:90-120								
Ch:120-145								
Royal Enclave Layout								
Ch:00-80 Cross rd beside NMH Convention Hall	1		30.00	4.50	4.40	0.43	57.41	
Ch:00-30	1		30.00	4.40	4.50	0.43	57.41	
Ch:30-60	1		20.00	4.50	4.40	0.43	38.27	
Ch:60-80								
Ch:00-230 Siddeshwara Temple Road	1		30.00	6.00	5.80	0.43	76.11	
Ch:00-30	1		30.00	5.80	5.90	0.43	75.47	
Ch:30-60	1		30.00	5.90	6.10	0.43	77.40	
Ch:60-90	1		30.00	6.10	5.70	0.43	76.11	
Ch:90-120	1		30.00	5.70	5.90	0.43	74.82	
Ch:120-150	1		30.00	5.90	5.50	0.43	73.53	
Ch:150-180	1		30.00	5.50	6.00	0.43	74.18	
Ch:180-210	1		20.00	6.00	5.80	0.43	50.74	
Ch:210-230								
Ch:00-70 1st cross	1		30.00	4.50	4.40	0.43	57.41	
Ch:00-30	1		30.00	4.40	4.50	0.43	57.41	
Ch:30-60	1		10.00	4.50	4.40	0.43	19.14	
Ch:60-70								
Ch:00-85 2nd Cross								

Ch:00-30	1		30.00	4.50	4.40	0.43	57.41	
Ch:30-60	1		30.00	4.40	4.50	0.43	57.41	
Ch:60-85	1		25.00	4.50	4.40	0.43	47.84	
Ch:00-80 3rd Cross								
Ch:00-30	1		30.00	4.50	4.40	0.43	57.41	
Ch:30-60	1		30.00	4.40	4.50	0.43	57.41	
Ch:60-80	1		20.00	4.50	4.40	0.43	38.27	
Ch:00-80 4rd Cross								
Ch:00-30	1		30.00	4.50	4.40	0.43	57.41	
Ch:30-60	1		30.00	4.40	4.50	0.43	57.41	
Ch:60-80	1		20.00	4.50	4.40	0.43	38.27	
NMH Layout								
Ch:00-220 Basava Dhyana Kendra								
Ch:00-30	1		30.00	4.30	4.30	0.43	55.47	
Ch:30-60	1		30.00	4.30	4.30	0.43	55.47	
Ch:60-90	1		30.00	4.30	4.30	0.43	55.47	
Ch:90-120	1		30.00	4.30	4.40	0.43	56.12	
Ch:120-150	1		30.00	4.40	4.40	0.43	56.76	
Ch:150-180	1		30.00	4.40	4.50	0.43	57.41	
Ch:180-210	1		30.00	4.50	4.50	0.43	58.05	
Ch:210-220	1		10.00	4.50	4.40	0.43	19.14	
Ch:00-180 BESCOM Begalugunte								
Ch:00-30	1		30.00	5.30	5.30	0.43	68.37	
Ch:30-60	1		30.00	5.30	5.30	0.43	68.37	
Ch:60-90	1		30.00	5.30	5.40	0.43	69.02	
Ch:90-120	1		30.00	5.40	5.40	0.43	69.66	
Ch:120-150	1		30.00	5.40	5.50	0.43	70.31	
Ch:150-180	1		30.00	5.50	5.50	0.43	70.95	
Ch:00-230 1st main								
Ch:00-30	1		30.00	4.80	4.80	0.43	61.92	
Ch:30-60	1		30.00	4.80	4.80	0.43	61.92	
Ch:60-90	1		30.00	4.80	4.90	0.43	62.57	
Ch:90-120	1		30.00	4.90	4.90	0.43	63.21	
Ch:120-150	1		30.00	4.90	4.90	0.43	63.21	
Ch:150-180	1		30.00	4.90	4.90	0.43	63.21	
Ch:180-210	1		30.00	4.90	4.90	0.43	63.21	
Ch:210-230	1		20.00	4.90	4.90	0.43	42.14	
Ch:00-140 2nd main								
Ch:00-30	1		30.00	4.90	4.90	0.43	63.21	
Ch:30-60	1		30.00	4.90	4.90	0.43	63.21	
Ch:60-90	1		30.00	4.90	5.00	0.43	63.86	
Ch:90-120	1		30.00	5.00	5.00	0.43	64.50	
Ch:120-140	1		20.00	5.00	5.00	0.43	43.00	
Kirloskar connecting road								
Ch:00-370 4nd main								
Ch:00-30	1		30.00	5.80	5.80	0.43	74.82	
Ch:30-60	1		30.00	5.80	5.80	0.43	74.82	
Ch:60-90	1		30.00	5.80	5.80	0.43	74.82	
Ch:90-120	1		30.00	5.80	5.80	0.43	74.82	
Ch:120-150	1		30.00	5.80	5.80	0.43	74.82	
Ch:150-180	1		30.00	5.80	5.80	0.43	74.82	
Ch:180-210	1		30.00	5.80	5.80	0.43	74.82	
Ch:210-240	1		30.00	5.80	5.80	0.43	74.82	
Ch:240-270	1		30.00	5.80	5.70	0.43	74.18	
Ch:270-300	1		30.00	5.70	5.70	0.43	73.53	
Ch:300-330	1		30.00	5.70	5.70	0.43	73.53	
Ch:330-360	1		30.00	5.70	5.70	0.43	73.53	
Ch:360-370	1		10.00	5.70	5.70	0.43	24.51	
CC Roads								
Royal Enclave Layout								
Ch:00-40 1st cross LHS Royal Enclave	1		40.00	5.00	5.00	0.45	90.00	
Ch:00-55 2nd Cross road Royal Enclave								
Ch:00-30	1		30.00	4.00	4.10	0.45	54.68	
Ch:30-55	1		25.00	4.10	4.10	0.45	46.13	
Ch:00-255 Royal Enclave Rd.								
Ch:00-30	1		30.00	5.50	5.40	0.45	73.58	
Ch:30-60	1		30.00	5.40	5.50	0.45	73.58	
Ch:60-90	1		30.00	5.50	5.20	0.45	72.23	
Ch:90-120	1		30.00	5.20	5.40	0.45	71.55	

Ch:120-150	1		30.00	5.50	5.40	0.45	73.58		
Ch:150-180	1		30.00	5.40	5.50	0.45	73.58		
Ch:180-210	1		30.00	5.50	5.20	0.45	72.23		
Ch:210-240	1		30.00	5.20	5.40	0.45	71.55		
Ch:240-255	1		15.00	5.40	5.60	0.45	37.13		
Left Side cross Roads to Royal Enclave Main Rd.									
Ch:00-60 3rd Cross									
Ch:00-30	1		30.00	4.50	4.40	0.45	60.08		
Ch:30-60	1		30.00	4.40	4.50	0.45	60.08		
Ch:00-60 4th Cross									
Ch:00-30	1		30.00	4.50	4.50	0.45	60.75		
Ch:30-60	1		30.00	4.50	4.50	0.45	60.75		
Right Side cross Roads to Royal Enclave Main Rd.									
Ch:00-72 3rd Cross L shape									
Ch:00-30	1		30.00	4.50	4.40	0.45	60.08		
Ch:30-60	1		30.00	4.40	4.50	0.45	60.08		
Ch:60-72	1		12.00	4.50	4.40	0.45	24.03		
Ch:00-32 4th Cross	1		32.00	4.80	4.90	0.45	69.84		
Ch:00-40 5th Cross	1		40.00	4.00	4.00	0.45	72.00		
Ch:40-90 5th Cross Lshape	1		50.00	4.50	4.50	0.45	101.25		
Overlay BC Road									
Byraveshwara circle									
Ch:00-310 (Naga Devaata Temple Road)									
Ch:00-30	2		30.00	0.80	0.80	0.40	19.20		
Ch:30-60	2		30.00	0.80	0.80	0.40	19.20		
Ch:60-90	2		30.00	0.80	0.80	0.40	19.20		
Ch:90-120	2		30.00	0.80	0.80	0.40	19.20		
Ch:120-150	2		30.00	0.80	0.80	0.40	19.20		
Ch:150-180	2		30.00	0.80	0.80	0.40	19.20		
Ch:180-210	2		30.00	0.80	0.80	0.40	19.20		
Ch:210-240	2		30.00	0.80	0.80	0.40	19.20		
Ch:240-270	2		30.00	0.80	0.80	0.40	19.20		
Ch:270-300	2		30.00	0.80	0.80	0.40	19.20		
Ch:300-310	2		10.00	0.80	0.80	0.40	6.40		
Ch:00-215 (From Byraveshwara Circle)									
Ch:00-30	2		30.00	0.80	0.80	0.40	19.20		
Ch:30-60	2		30.00	0.80	0.80	0.40	19.20		
Ch:60-90	2		30.00	0.80	0.80	0.40	19.20		
Ch:90-120	2		30.00	0.80	0.80	0.40	19.20		
Ch:120-150	2		30.00	0.80	0.80	0.40	19.20		
Ch:150-180	2		30.00	0.80	0.80	0.40	19.20		
Ch:180-215	2		35.00	0.80	0.80	0.40	22.40		
Soundarya layout 2nd Main									
Ch:00-530(2nd Main Road)									
Ch:00-30	2		30.00	0.80	0.80	0.40	19.20		
Ch:30-60	2		30.00	0.80	0.80	0.40	19.20		
Ch:60-90	2		30.00	0.80	0.80	0.40	19.20		
Ch:90-120	2		30.00	0.80	0.80	0.40	19.20		
Ch:120-150	2		30.00	0.80	0.80	0.40	19.20		
Ch:150-180	2		30.00	0.80	0.80	0.40	19.20		
Ch:180-210	2		30.00	0.80	0.80	0.40	19.20		
Ch:210-240	2		30.00	0.80	0.80	0.40	19.20		
Ch:240-270	2		30.00	0.80	0.80	0.40	19.20		
Ch:270-300	2		30.00	0.80	0.80	0.40	19.20		
Ch:300-330	2		30.00	0.80	0.80	0.40	19.20		
Ch:330-360	2		30.00	0.80	0.80	0.40	19.20		
Ch:360-390	2		30.00	0.80	0.80	0.40	19.20		
Ch:390-420	2		30.00	0.80	0.80	0.40	19.20		
Ch:420-450	2		30.00	0.80	0.80	0.40	19.20		
Ch:450-480	2		30.00	0.80	0.80	0.40	19.20		
Ch:480-510	2		30.00	0.80	0.80	0.40	19.20		
Ch:510-530	2		20.00	0.80	0.80	0.40	12.80		
Soundarya layout 1st Main									
Ch:00-530(1st Main)									
Ch:00-30	2		30.00	0.80	0.80	0.40	19.20		
Ch:30-60	2		30.00	0.80	0.80	0.40	19.20		
Ch:60-90	2		30.00	0.80	0.80	0.40	19.20		

	Ch:90-120	2		30.00	0.80	0.80	0.40	19.20		
	Ch:120-150	2		30.00	0.80	0.80	0.40	19.20		
	Ch:150-180	2		30.00	0.80	0.80	0.40	19.20		
	Ch:180-210	2		30.00	0.80	0.80	0.40	19.20		
	Ch:210-240	2		30.00	0.80	0.80	0.40	19.20		
	Ch:240-270	2		30.00	0.80	0.80	0.40	19.20		
	Ch:270-300	2		30.00	0.80	0.80	0.40	19.20		
	Ch:300-330	2		30.00	0.80	0.80	0.40	19.20		
	Ch:330-360	2		30.00	0.80	0.80	0.40	19.20		
	Ch:360-390	2		30.00	0.80	0.80	0.40	19.20		
	Ch:390-420	2		30.00	0.80	0.80	0.40	19.20		
	Ch:420-450	2		30.00	0.80	0.80	0.40	19.20		
	Ch:450-480	2		30.00	0.80	0.80	0.40	19.20		
	Ch:480-510	2		30.00	0.80	0.80	0.40	19.20		
	Ch:510-530	2		20.00	0.80	0.80	0.40	12.80		
	Restoration For BWSSB Cutting (All roads)	2		9188.00	0.80		0.40	5880.32		
								Total Qty	**28068.50**	**86.88**	**24,38,523.92**
14	KSRB 2.6 : Providing and filling Stone Dust in trenches to required depth for sub soil treatment including watering ramming with all lead and lift complete as per specifications.									
	KPWD S.R 2018-19	It. No.		2.13						
	Restoration For BWSSB Cutting (All roads)	Cum	2		10773.00	0.80		0.2	3447.36		
								Total Qty	**3447.36**	**1461.79**	**50,39,326.72**
15	KSRRB M300-53. Construction of embankment with approved material Cum Gravel/Murrum with all lifts and leads, transporting to site, spreading, grading to required slope and compacting to meet requirement Table 300-2 complete as per specifications, including cost of gravel I murrum, watering charges & compaction by vibratory roller to 95% of modified proctors density. MORTH Specification No. 305									
	KPWD S.R 2018-19	It. No.		19.6		Pg.No.		147		
	Royal Enclave Layout									
	Ch:00-40 1st cross LHS Royal Enclave		1		40.00	5.00	5.00	0.30	60.00		
	Ch:00-55 2nd Cross road Royal Enclave		1		55.00	4.00	4.10	0.30	66.83		
	Ch:00-255 Royal Enclave Rd.		1		255.00	5.50	5.40	0.35	486.41		
	Ch:00-60 3rd Cross		1		60.00	4.50	4.40	0.30	80.10		
	Ch:00-60 4th Cross		1		60.00	4.50	4.40	0.30	80.10		
	Ch:00-72 3rd Cross L shape		1		72.00	4.50	4.40	0.30	96.12		
	Ch:00-32 4th Cross		1		32.00	4.80	4.90	0.30	46.56		
	Ch:00-40 5th Cross		1		40.00	4.00	4.00	0.30	48.00		
	Ch:40-90 5th Cross Lshape		1		50.00	4.50	4.50	0.30	67.50		
	Byraveshwara circle	cum									
	Ch:00-310 (Naga Devaata Temple Road)		1		310.00	6.50	6.40	0.35	699.83		
	Ch:00-215 (From Byraveshwara Circle)		1		200.00	7.00	7.00	0.35	490.00		
	M.H.R. Layout									
	Ch:00-490(Chetana E lavada school Frant Rd to Siddhi Vinayaka Temple)		1		200.00	5.00	5.10	0.35	353.50		
	Siddeshwara Layout									
	Ch:325-465		1		140.00	5.10	4.80	0.35	242.55		
	Ch:465-565		1		100.00	4.80	5.10	0.35	173.25		
	Ch:565-620		1		55.00	5.10	5.00	0.35	97.21		
	Ch:00-145 8th cross		1		140.00	5.20	5.20	0.35	254.80		
									Total Qty	**3342.76**	**385.46**	**12,88,498.34**
16	Constructing un-reinforced, plain cement concrete for pavements using Grade concrete M30 over a prepared base with OPC at 360 kg/cum and coarse aggregate 0.69cum, fine aggregate 0.46cum. OPC coarse aggregate at 0.69 cum, fine aggregates at 0.46 cum,Coarse and fine aggregate conforming to IS:383-2016, with Superplastizer at 3 Its conforming to IS 9103-2008. mixed in a concrete mixer of not less than 0.6 cum capacity and appropriate weigh batcher as per approved mix design, laid in approved fixed side form work (steel channel, laying and fixing of 125 micron thick polythene film, wedges, steel plates including levelling the form work as per drawing). Spreading the concrete with shovels, rackers compacted using needle, screed and plate vibrator and finished with floaters in a continuous operation including provision of contraction, expansion, construction and longitudinal joints,including groove cutting charges, joint filler, soparation membrane of impermiable plastic sheet of 125 micron, sealant primer, joint sealant, admixtures as approved, curing compound, finishing to lines and grades, textured with texturing machine, and curing including cost of all materials, labour,hire charges of machineries,all lead & lift charges etc., complete as per specifications.									
	KPWD S.R 2018-19	It. No.		22.6.1		Pg.No		176		
	Royal Enclave Layout									
	Ch:00-40 1st cross LHS Royal Enclave		1		40.00	5.00	5.00	0.15	30.00		
	Ch:00-55 2nd Cross road Royal Enclave									
	Ch:00-30		1		30.00	4.00	4.10	0.15	18.23		

Comprehensive development of bad roads and improvements to road side drain, footpaths, Asphalting and concreting including culvert selected main and other connecting roads of package No.1 in ward No.14, Bagalagunte of Dasarahalli Division

	Ch:30-55		1		25.00	4.10	4.10	0.15	15.38		
	Ch:00-255 Royal Enclave Rd.										
	Ch:00-30		1		30.00	5.50	5.40	0.15	24.53		
	Ch:30-60		1		30.00	5.40	5.50	0.15	24.53		
	Ch:60-90		1		30.00	5.50	5.20	0.15	24.08		
	Ch:90-120		1		30.00	5.20	5.40	0.15	23.85		
	Ch:120-150		1		30.00	5.50	5.40	0.15	24.53		
	Ch:150-180		1		30.00	5.40	5.50	0.15	24.53		
	Ch:180-210		1		30.00	5.50	5.20	0.15	24.08		
	Ch:210-240		1		30.00	5.20	5.40	0.15	23.85		
	Ch:240-255		1		15.00	5.40	5.60	0.15	12.38		
	Left Side cross Roads to Royal Enclave Main Rd.	Cum									
	Ch:00-60 3rd Cross										
	Ch:00-30		1		30.00	4.50	4.40	0.15	20.03		
	Ch:30-60		1		30.00	4.40	4.50	0.15	20.03		
	Ch:00-60 4th Cross										
	Ch:00-30		1		30.00	4.50	4.50	0.15	20.25		
	Ch:30-60		1		30.00	4.50	4.50	0.15	20.25		
	Right Side cross Roads to Royal Enclave Main Rd.										
	Ch:00-72 3rd Cross L shape										
	Ch:00-30		1		30.00	4.50	4.40	0.15	20.03		
	Ch:30-60		1		30.00	4.40	4.50	0.15	20.03		
	Ch:60-72		1		12.00	4.50	4.40	0.15	8.01		
	Ch:00-32 4th Cross		1		32.00	4.80	4.90	0.15	23.28		
	Ch:00-40 5th Cross		1		40.00	4.00	4.00	0.15	24.00		
	Ch:40-90 5th Cross Lshape		1		50.00	4.50	4.50	0.15	33.75		
									Total Qty	**479.57**	**5210.96**	**24,98,994.03**
17	Construction of granular sub-base Grading-V as Sub-base and drainage layer by providing coarse graded crushed stone aggregatesof granite/trap/basalt material, mixing by mix in place method by rotavator at OMC, spreading in uniform layers with motor grader on prepared surface and compacting with vibratory power roller to achieve the 98 % proctor density, complete as per specifications.										
	KPWD S.R 2018-19	It. No.		20.6		Pg.No		153			
	New BC Road										
	Byraveshwara circle										
	Ch:00-110 1st Cross										
	Ch:00-30		1		30.00	4.50	4.50	0.15	20.25		
	Ch:30-60		1		30.00	4.50	4.30	0.15	19.80		
	Ch:60-90		1		30.00	4.30	4.40	0.15	19.58		
	Ch:90-110		1		20.00	4.40	4.60	0.15	13.50		
	Ch:00-112 2nd Cross										
	Ch:00-30		1		30.00	5.00	5.00	0.15	22.50		
	Ch:30-60		1		30.00	4.80	4.90	0.15	21.83		
	Ch:60-90		1		30.00	4.90	5.10	0.15	22.50		
	Ch:90-112		1		22.00	5.10	4.90	0.15	16.50		
	Ch:00-110-3rd Cross										
	Ch:00-30		1		30.00	4.00	4.00	0.15	18.00		
	Ch:30-60		1		30.00	3.90	4.00	0.15	17.78		
	Ch:60-90		1		30.00	4.00	3.80	0.15	17.55		
	Ch:90-110		1		20.00	3.80	3.80	0.15	11.40		
	Ch:00-88 4th Cross										
	Ch:00-30		1		30.00	4.50	4.40	0.15	20.03		
	Ch:30-60		1		30.00	4.40	4.60	0.15	20.25		
	Ch:60-88		1		28.00	4.60	4.30	0.15	18.69		
	Ch:00-82 5th Cross										
	Ch:00-30		1		30.00	4.00	3.80	0.15	17.55		
	Ch:30-60		1		30.00	3.80	4.00	0.15	17.55		
	Ch:60-82		1		22.00	4.00	3.80	0.15	12.87		
	M.H.R. Layout										
	Ch:00-490(Chetana E lavada school Frant Rd to Siddhi Vinayaka Temple)										
	Ch:00-30		1		30.00	5.30	5.10	0.15	23.40		
	Ch:30-60		1		30.00	5.10	5.40	0.15	23.63		
	Ch:60-90		1		30.00	5.40	5.50	0.15	24.53		
	Ch:90-120		1		30.00	5.50	5.50	0.15	24.75		
	Ch:120-150		1		30.00	5.50	5.00	0.15	23.63		
	Ch:150-180		1		30.00	5.00	5.00	0.15	22.50		
	Ch:180-210		1		30.00	5.20	5.50	0.15	24.08		
	Ch:210-240		1		30.00	5.50	5.20	0.15	24.08		

Comprehensive development of bad roads and improvements to road side drain, footpaths, Asphalting and concreting including culvert selected main and other connecting roads of package No.1 in ward No.14, Bagalagunte of Dasarahalli Division

Ch:240-270	1		30.00	5.20	5.00	0.15	22.95	
Ch:270-300	1		30.00	5.00	5.00	0.15	22.50	
Ch:300-330	1		30.00	5.20	5.20	0.15	23.40	
Ch:330-360	1		30.00	5.20	5.20	0.15	23.40	
Ch:360-390	1		30.00	5.20	5.50	0.15	24.08	
Ch:390-420	1		30.00	5.50	5.20	0.15	24.08	
Ch:420-450	1		30.00	5.20	5.00	0.15	22.95	
Ch:450-480	1		30.00	5.00	5.00	0.15	22.50	
Ch:480-490	1		10.00	5.00	5.00	0.15	7.50	
Ch:00-110 (4th Cross Road)								
Ch:00-30	1		30.00	4.10	3.90	0.15	18.00	
Ch:30-60	1		30.00	3.90	4.00	0.15	17.78	
Ch:60-90	1		30.00	4.00	3.90	0.15	17.78	
Ch:90-110	1		20.00	3.90	4.20	0.15	12.15	
Ch:00-80 (5th Cross Road)								
Ch:00-30	1		30.00	4.00	4.00	0.15	18.00	
Ch:30-60	1		30.00	3.80	4.20	0.15	18.00	
Ch:60-80	1		20.00	4.20	3.90	0.15	12.15	
Ch:00-75 (6th Cross Road)								
Ch:00-30	1		30.00	6.00	5.80	0.15	26.55	
Ch:30-60	1		30.00	5.80	5.90	0.15	26.33	
Ch:60-75	1		15.00	5.90	6.10	0.15	13.50	
Ch:00-110 (7th Cross Road)								
Ch:00-30	1		30.00	5.00	4.80	0.15	22.05	
Ch:30-60	1		30.00	4.80	5.20	0.15	22.50	
Ch:60-90	1		30.00	5.20	5.00	0.15	22.95	
Ch:90-110	1		20.00	5.00	5.00	0.15	15.00	
Ch:00-115 (8th Cross Road)								
Ch:00-30	1		30.00	4.90	4.80	0.15	21.83	
Ch:30-60	1		30.00	4.80	4.90	0.15	21.83	
Ch:60-90	1		30.00	4.90	5.00	0.15	22.28	
Ch:90-115	1		25.00	5.00	4.90	0.15	18.56	
Ch:00-210(1st Main)								
Ch:00-30	1		30.00	4.50	4.50	0.15	20.25	
Ch:30-60	1		30.00	4.50	4.50	0.15	20.25	
Ch:60-90	1		30.00	4.50	4.50	0.15	20.25	
Ch:90-120	1		30.00	4.50	4.50	0.15	20.25	
Ch:120-150	1		30.00	4.50	4.60	0.15	20.48	
Ch:150-180	1		30.00	4.60	4.60	0.15	20.70	
Ch:180-210	1		30.00	4.60	4.60	0.15	20.70	
MEENAKSHI layout								
Ch:00-280(1st Main)								
Ch:00-30	1		30.00	5.50	5.40	0.15	24.53	
Ch:30-60	1		30.00	5.40	5.50	0.15	24.53	
Ch:60-90	1		30.00	5.50	5.20	0.15	24.08	
Ch:90-120	1		30.00	5.20	5.40	0.15	23.85	
Ch:120-150	1		30.00	5.40	5.60	0.15	24.75	
Ch:150-180	1		30.00	5.60	5.40	0.15	24.75	
Ch:180-210	1		30.00	5.40	5.50	0.15	24.53	
Ch:210-240	1		30.00	5.50	5.50	0.15	24.75	
Ch:240-270	1		30.00	5.50	5.20	0.15	24.08	
Ch:270-280	1		10.00	5.20	5.40	0.15	7.95	
Ch:00-280(2nd Main)								
Ch:00-30	1		30.00	5.00	5.00	0.15	22.50	
Ch:30-60	1		30.00	5.00	4.80	0.15	22.05	
Ch:60-90	1		30.00	4.80	5.20	0.15	22.50	
Ch:90-120	1		30.00	5.20	4.60	0.15	22.05	
Ch:120-150	1		30.00	4.60	5.00	0.15	21.60	
Ch:150-180	1		30.00	5.00	4.80	0.15	22.05	
Ch:180-210	1		30.00	4.80	5.20	0.15	22.50	
Ch:210-240	1		30.00	5.20	4.80	0.15	22.50	
Ch:240-270	1		30.00	4.80	5.20	0.15	22.50	
Ch:270-280	1		10.00	5.20	5.00	0.15	7.65	
Ch:00-270(1st B Main)								
Ch:00-30	1		30.00	5.20	5.20	0.15	23.40	
Ch:30-60	1		30.00	5.20	5.20	0.15	23.40	
Ch:60-90	1		30.00	5.20	5.20	0.15	23.40	
Ch:90-120	1		30.00	5.20	5.20	0.15	23.40	
Ch:120-150	1		30.00	5.20	5.20	0.15	23.40	
Ch:150-180	1		30.00	5.20	5.30	0.15	23.63	

ES FOR 1SQM AREA

Ch:180-210	1		30.00	5.30	5.30	0.15	23.85	
Ch:210-240	1		30.00	5.30	5.30	0.15	23.85	
Ch:240-270	1		30.00	5.30	5.30	0.15	23.85	
Ch:00-280(1st C Main)								
Ch:00-30	1		30.00	5.50	5.50	0.15	24.75	
Ch:30-60	1		30.00	5.50	5.50	0.15	24.75	
Ch:60-90	1		30.00	5.50	5.50	0.15	24.75	
Ch:90-120	1		30.00	5.50	5.50	0.15	24.75	
Ch:120-150	1		30.00	5.50	5.50	0.15	24.75	
Ch:150-180	1		30.00	5.50	5.50	0.15	24.75	
Ch:180-210	1		30.00	5.50	5.40	0.15	24.53	
Ch:210-240	1		30.00	5.40	5.40	0.15	24.30	
Ch:240-270	1		30.00	5.40	5.40	0.15	24.30	
Ch:270-280	1		10.00	5.40	5.40	0.15	8.10	
Ch:00-95(14th Cross Road)								
Ch:00-30	1		30.00	5.00	4.80	0.15	22.05	
Ch:30-60	1		30.00	4.80	5.00	0.15	22.05	
Ch:60-95	1		35.00	5.00	5.20	0.15	26.78	
Ch:00-110(12th Cross Road)								
Ch:00-30	1		30.00	5.00	4.80	0.15	22.05	
Ch:30-60	1		30.00	4.80	5.20	0.15	22.50	
Ch:60-90	1		30.00	5.20	4.80	0.15	22.50	
Ch:90-110	1		20.00	4.80	4.90	0.15	14.55	
Ch:00-140(10th Cross Road)								
Ch:00-30	1		30.00	4.50	4.40	0.15	20.03	
Ch:30-60	1		30.00	4.40	4.50	0.15	20.03	
Ch:60-90	1		30.00	4.50	4.00	0.15	19.13	
Ch:90-120	1		30.00	4.00	4.20	0.15	18.45	
Ch:120-140	1		20.00	4.20	4.40	0.15	12.90	
Ch:00-96(9th Cross Road)								
Ch:00-30	1		30.00	4.50	4.40	0.15	20.03	
Ch:30-60	1		30.00	4.40	4.50	0.15	20.03	
Ch:60-96	1		36.00	4.50	4.40	0.15	24.03	
Ch:00-62(8th Cross Road)								
Ch:00-30	1		30.00	4.50	4.40	0.15	20.03	
Ch:30-62	1		32.00	4.40	4.50	0.15	21.36	
Ch:00-105(7th Cross Road)								
Ch:00-30	1		30.00	4.50	4.40	0.15	20.03	
Ch:30-60	1		30.00	4.40	4.50	0.15	20.03	
Ch:60-90	1		30.00	4.50	4.00	0.15	19.13	
Ch:90-105	1		15.00	4.00	4.20	0.15	9.23	
Ch:00-65(6th Cross Road)								
Ch:00-30	1		30.00	4.50	4.40	0.15	20.03	
Ch:30-65	1		35.00	4.40	4.50	0.15	23.36	
Ch:00-64(5th Cross Road)								
Ch:00-30	1		30.00	4.50	4.40	0.15	20.03	
Ch:30-64	1		34.00	4.40	4.50	0.15	22.70	
Ch:00-63(4th Cross Road)								
Ch:00-30	1		30.00	4.50	4.40	0.15	20.03	
Cn:30-63	1		33.00	4.40	4.50	0.15	22.03	
Ch:00-65(3rd Cross Road)								
Ch:00-30	1		30.00	4.50	4.40	0.15	20.03	
Ch:30-65	1		35.00	4.40	4.50	0.15	23.36	
Ch:00-66(2nd Cross Road)								
Ch:00-30	1		30.00	4.50	4.40	0.15	20.03	
Ch:30-66	1		36.00	4.40	4.50	0.15	24.03	
Ch:00-80(1st Cross Road)						0.15		
Ch:00-30	1		30.00	4.50	4.50	0.15	20.25	
Ch:30-60	1		30.00	4.50	4.40	0.15	20.03	
Ch:60-80	1		20.00	4.40	4.50	0.15	13.35	
Soundarya layout 2nd Main								
Ch00-95(11th Cross Road)								
Ch:00-30	1		30.00	5.00	4.80	0.15	22.05	
Ch:30-60	1		30.00	4.80	5.20	0.15	22.50	
Ch:60-95	1		35.00	5.20	4.80	0.15	26.25	
Ch:00-85(10th Cross Road)								
Ch:00-30	1		30.00	5.00	4.80	0.15	22.05	
Ch:30-60	1		30.00	4.80	5.20	0.15	22.50	
Ch:60-85	1		25.00	5.20	4.80	0.15	18.75	
Ch:00-75(9th Cross Road)								

ES[illegible] FOR 1SQM AREA

Comprehensive development of bad roads and improvements to road side drain, footpaths, Asphalting and concreting including culvert selected main and other connecting roads of package No.1 in ward No.14, Bagalagunte of Dasarahalli Division

Ch:00-30		1		30.00	5.00	4.80	0.15	22.05	
Ch:30-60		1		30.00	4.80	5.20	0.15	22.50	
Ch:60-75		1		15.00	5.20	4.80	0.15	11.25	
Ch:00-68(8th Cross Road)									
Ch:00-30		1		30.00	5.00	4.80	0.15	22.05	
Ch:30-68		1		38.00	4.80	5.20	0.15	28.50	
Ch:00-50(7th Cross Road)									
Ch:00-30		1		30.00	5.00	4.80	0.15	22.05	
Ch:30-50		1		20.00	4.80	5.20	0.15	15.00	
Ch:00-43(6th Cross Road)									
Ch:00-30		1		30.00	5.00	4.80	0.15	22.05	
Ch:30-43		1		13.00	4.80	5.20	0.15	9.75	
Ch:00-60(4th Cross Road)									
Ch:00-30		1		30.00	5.00	4.80	0.15	22.05	
Ch:30-60		1		30.00	4.80	5.20	0.15	22.50	
Ch:00-152(3rd Cross Road)									
Ch:00-30		1		30.00	5.00	4.80	0.15	22.05	
Ch:30-60		1		30.00	4.80	5.20	0.15	22.50	
Ch:60-90		1		30.00	5.20	4.80	0.15	22.50	
Ch:90-120		1		30.00	4.80	5.20	0.15	22.50	
Ch:120-152		1		32.00	5.20	5.00	0.15	24.48	
Ch:00-100 (Cross Road)									
Ch:00-30		1		30.00	5.00	4.80	0.15	22.05	
Ch:30-60	Cum.	1		30.00	4.80	5.20	0.15	22.50	
Ch:60-90		1		30.00	5.20	4.80	0.15	22.50	
Ch:90-100		1		10.00	4.80	5.20	0.15	7.50	
Ch:00-225 (Cross Road)									
Ch:00-30		1		30.00	5.50	5.40	0.15	24.53	
Ch:30-60		1		30.00	5.40	5.50	0.15	24.53	
Ch:60-90		1		30.00	5.50	5.20	0.15	24.08	
Ch:90-120		1		30.00	5.20	5.40	0.15	23.85	
Ch:120-150		1		30.00	5.40	5.40	0.15	24.30	
Ch:150-180		1		30.00	5.40	5.50	0.15	24.53	
Ch:180-210		1		30.00	5.50	5.20	0.15	24.08	
Ch:210-225		1		15.00	5.20	5.40	0.15	11.93	
Ch:00-125(3rd Main Road)									
Ch:00-30		1		30.00	5.00	4.80	0.15	22.05	
Ch:30-60		1		30.00	4.80	5.20	0.15	22.50	
Ch:60-90		1		30.00	5.20	4.80	0.15	22.50	
Ch:90-120		1		35.00	4.80	5.20	0.15	26.25	
Ch:00-230(3rd Main Road)									
Ch:00-30		1		30.00	5.00	4.80	0.15	22.05	
Ch:30-60		1		30.00	4.80	5.20	0.15	22.50	
Ch:60-90		1		30.00	5.20	4.80	0.15	22.50	
Ch:90-120		1		30.00	4.80	5.20	0.15	22.50	
Ch:120-150		1		30.00	5.20	4.80	0.15	22.50	
Ch:150-180		1		30.00	4.80	5.20	0.15	22.50	
Ch:180-210		1		30.00	5.20	4.80	0.15	22.50	
Ch:210-230		1		20.00	4.80	5.20	0.15	15.00	
Soundarya layout 1st Main									
Ch:00-90(1st A Cross Road)									
Ch:00-30		1		30.00	5.00	4.80	0.15	22.05	
Ch:30-60		1		30.00	4.80	5.20	0.15	22.50	
Ch:60-90		1		30.00	5.20	4.80	0.15	22.50	
Ch:00-100(2nd A Cross Road)									
Ch:00-30		1		30.00	5.00	4.80	0.15	22.05	
Ch:30-60		1		30.00	4.80	5.20	0.15	22.50	
Ch:60-90		1		30.00	5.20	4.80	0.15	22.50	
Ch:90-100		1		10.00	4.80	4.90	0.15	7.28	
Ch:00-90(4th A Cross Road)									
Ch:00-30		1		30.00	5.00	4.80	0.15	22.05	
Ch:30-60		1		30.00	4.80	5.20	0.15	22.50	
Ch:60-90		1		30.00	5.20	4.80	0.15	22.50	
Ch:00-90(6th A Cross Road)									
Ch:00-30		1		30.00	5.00	4.80	0.15	22.05	
Ch:30-60		1		30.00	4.80	5.20	0.15	22.50	
Ch:60-90		1		30.00	5.20	4.80	0.15	22.50	
Ch:00-90(7th A Cross Road)									
Ch:00-30		1		30.00	5.00	4.90	0.15	22.28	
Ch:30-60		1		30.00	4.90	5.20	0.15	22.73	

ES FOR 1SQM AREA

Ch:60-90								
Ch:00-93(8th A Cross Road)								
Ch:00-30	1		30.00	5.20	4.80	0.15	22.50	
Ch:30-60								
Ch:60-93	1		30.00	5.00	4.80	0.15	22.05	
Ch:00-92(9th A Cross Road)	1		30.00	4.80	5.20	0.15	22.50	
Ch:00-30	1		33.00	5.20	4.80	0.15	24.75	
Ch:30-60								
Ch:60-92	1		30.00	5.00	4.90	0.15	22.28	
Ch:00-90(11th A Cross Road)	1		30.00	4.90	5.20	0.15	22.73	
Ch:00-30	1		32.00	5.20	4.80	0.15	24.00	
Ch:30-60								
Ch:60-90	1		30.00	5.00	4.80	0.15	22.05	
Ch:00-93(12th A Cross Road)	1		30.00	4.80	5.20	0.15	22.50	
Ch:00-30	1		30.00	5.20	4.80	0.15	22.50	
Ch:30-60								
Ch:60-93	1		30.00	5.00	4.80	0.15	22.05	
Ch:00-92(13th A Cross Road)	1		30.00	4.80	5.20	0.15	22.50	
Ch:00-30	1		33.00	5.20	4.80	0.15	24.75	
Ch:30-60								
Ch:60-92	1		30.00	5.00	4.80	0.15	22.05	
Ch:00-95(2nd B main Road)	1		30.00	4.80	5.20	0.15	22.50	
Ch:00-30	1		32.00	5.20	4.80	0.15	24.00	
Ch:30-60								
Ch:60-95	1		30.00	5.00	5.10	0.15	22.73	
Siddeshwara Layout	1		30.00	5.10	5.20	0.15	23.18	
Ch:00-950	1		32.00	5.20	5.10	0.15	24.72	
Ch:00-30								
Ch:30-60								
Ch:60-90	1		30.00	5.50	5.40	0.15	24.53	
Ch:90-120	1		30.00	5.40	5.50	0.15	24.53	
Ch:120-150	1		30.00	5.50	5.20	0.15	24.08	
Ch:150-180	1		30.00	5.20	5.40	0.15	23.85	
Ch:180-210	1		30.00	5.40	5.40	0.15	24.30	
Ch:210-240	1		30.00	5.40	5.50	0.15	24.53	
Ch:240-270	1		30.00	5.50	5.20	0.15	24.08	
Ch:270-300	1		30.00	5.20	5.40	0.15	23.85	
Ch:300-330	1		30.00	5.40	5.40	0.15	24.30	
Ch:330-360	1		30.00	5.40	5.50	0.15	24.53	
Ch:360-390	1		30.00	5.50	5.20	0.15	24.08	
Ch:390-420	1		30.00	5.20	5.40	0.15	23.85	
Ch:420-450	1		30.00	5.40	5.40	0.15	24.30	
Ch:450-480	1		30.00	5.40	5.50	0.15	24.53	
Ch:480-510	1		30.00	5.50	5.20	0.15	24.08	
Ch:510-540	1		30.00	5.20	5.40	0.15	23.85	
Ch:540-570	1		30.00	5.40	5.40	0.15	24.30	
Ch:570-600	1		30.00	5.40	5.50	0.15	24.53	
Ch:600-630	1		30.00	5.50	5.20	0.15	24.08	
Ch:630-660	1		30.00	5.20	5.40	0.15	23.85	
Ch:660-690	1		30.00	5.40	5.40	0.15	24.30	
Ch:690-720	1		30.00	5.40	5.50	0.15	24.53	
Ch:720-750	1		30.00	5.50	5.20	0.15	24.08	
Ch:750-780	1		30.00	5.20	5.40	0.15	23.85	
Ch:780-810	1		30.00	5.40	5.40	0.15	24.30	
Ch:810-840	1		30.00	5.40	5.50	0.15	24.53	
Ch:840-870	1		30.00	5.50	5.20	0.15	24.08	
Ch:870-900	1		20.00	5.20	5.40	0.15	15.90	
Ch:900-930								
Ch:930-950	1		30.00	5.00	4.80	0.15	22.05	
Ch:00-100 NMH Public school road	1		30.00	4.80	5.20	0.15	22.50	
Ch:00-30	1		30.00	5.20	4.80	0.15	22.50	
Ch:30-60	1		10.00	4.80	5.00	0.15	7.35	
Ch:60-90								
Ch:90-100	1		30.00	5.20	5.20	0.15	23.40	
Ch:00-145 8th cross								
Ch:00-30								

Comprehensive development of bad roads and improvements to road side drain, footpaths, Asphalting and concreting including culvert selected main and other connecting roads of package No.1 in ward No.14, Bangalore of Dasarahalli Division

Ch:30-60	1		30.00	5.20	5.20	0.15	23.40		
Ch:60-90	1		30.00	5.20	5.20	0.15	23.40		
Ch:90-120	1		30.00	5.20	5.30	0.15	23.63		
Ch:120-145	1		25.00	5.30	5.30	0.15	19.88		
Royal Enclave Layout									
Ch:00-80 Cross rd beside NMH Convention Hall									
Ch:00-30	1		30.00	4.50	4.40	0.15	20.03		
Ch:30-60	1		30.00	4.40	4.50	0.15	20.03		
Ch:60-80	1		20.00	4.50	4.40	0.15	13.35		
Ch:00-210 Siddeshwara Temple Road									
Ch:00-30	1		30.00	6.00	5.80	0.15	26.55		
Ch:30-60	1		30.00	5.80	5.90	0.15	26.33		
Ch:60-90	1		30.00	5.90	6.10	0.15	27.00		
Ch:90-120	1		30.00	6.10	5.70	0.15	26.55		
Ch:120-150	1		30.00	5.70	5.90	0.15	26.10		
Ch:150-180	1		30.00	5.90	5.50	0.15	25.65		
Ch:180-210	1		30.00	5.50	6.00	0.15	25.88		
Ch:210-230	1		20.00	6.00	5.80	0.15	17.70		
Ch:00-70 1st cross									
Ch:00-30	1		30.00	4.50	4.40	0.15	20.03		
Ch:30-60	1		30.00	4.40	4.50	0.15	20.03		
Ch:60-70	1		10.00	4.50	4.40	0.15	6.68		
Ch:00-85 2nd Cross									
Ch:00-30	1		30.00	4.50	4.40	0.15	20.03		
Ch:30-60	1		30.00	4.40	4.50	0.15	20.03		
Ch:60-85	1		25.00	4.50	4.40	0.15	16.69		
Ch:00-80 3rd Cross							0.00		
Ch:00-30	1		30.00	4.50	4.40	0.15	20.03		
Ch:30-60	1		30.00	4.40	4.50	0.15	20.03		
Ch:60-80	1		20.00	4.50	4.40	0.15	13.35		
Ch:00-80 4rd Cross									
Ch:00-30	1		30.00	4.50	4.40	0.15	20.03		
Ch:30-60	1		30.00	4.40	4.50	0.15	20.03		
Ch:60-80	1		20.00	4.50	4.40	0.15	13.35		
NMH Layout									
Ch:00-220 Basava Dhyana Kendra									
Ch:00-30	1		30.00	4.30	4.30	0.15	19.35		
Ch:30-60	1		30.00	4.30	4.30	0.15	19.35		
Ch:60-90	1		30.00	4.30	4.30	0.15	19.35		
Ch:90-120	1		30.00	4.30	4.40	0.15	19.58		
Ch:120-150	1		30.00	4.40	4.40	0.15	19.80		
Ch:150-180	1		30.00	4.40	4.50	0.15	20.03		
Ch:180-210	1		30.00	4.50	4.50	0.15	20.25		
Ch:210-220	1		10.00	4.50	4.40	0.15	6.68		
Ch:00-180 BESCOM Bagalugunte									
Ch:00-30	1		30.00	5.30	5.30	0.15	23.85		
Ch:30-60	1		30.00	5.30	5.30	0.15	23.85		
Ch:60-90	1		30.00	5.30	5.40	0.15	24.08		
Ch:90-120	1		30.00	5.40	5.40	0.15	24.30		
Ch:120-150	1		30.00	5.40	5.50	0.15	24.53		
Ch:150-180	1		30.00	5.50	5.50	0.15	24.75		
Ch:00-230 1st main									
Ch:00-30	1		30.00	4.80	4.80	0.15	21.60		
Ch:30-60	1		30.00	4.80	4.80	0.15	21.60		
Ch:60-90	1		30.00	4.80	4.90	0.15	21.83		
Ch:90-120	1		30.00	4.90	4.90	0.15	22.05		
Ch:120-150	1		30.00	4.90	4.90	0.15	22.05		
Ch:150-180	1		30.00	4.90	4.90	0.15	22.05		
Ch:180-210	1		30.00	4.90	4.90	0.15	22.05		
Ch:210-230	1		20.00	4.90	4.90	0.15	14.70		
Ch:00-140 2nd main									
Ch:00-30	1		30.00	4.90	4.90	0.15	22.05		
Ch:30-60	1		30.00	4.90	4.90	0.15	22.05		
Ch:60-90	1		30.00	4.90	5.00	0.15	22.28		
Ch:90-120	1		30.00	5.00	5.00	0.15	22.50		
Ch:120-140	1		20.00	5.00	5.00	0.15	15.00		
Kirloskar connecting road									
Ch:00-370 4nd main									
Ch:00-30	1		30.00	5.80	5.80	0.15	26.10		

	Ch:30-60	1		30.00	5.80	5.80	0.15	26.10		
	Ch:60-90	1		30.00	5.80	5.80	0.15	26.10		
	Ch:90-120	1		30.00	5.80	5.80	0.15	26.10		
	Ch:120-150	1		30.00	5.80	5.80	0.15	26.10		
	Ch:150-180	1		30.00	5.80	5.80	0.15	26.10		
	Ch:180-210	1		30.00	5.80	5.80	0.15	26.10		
	Ch:210-240	1		30.00	5.80	5.80	0.15	26.10		
	Ch:240-270	1		30.00	5.80	5.70	0.15	25.88		
	Ch:270-300	1		30.00	5.70	5.70	0.15	25.65		
	Ch:300-330	1		30.00	5.70	5.70	0.15	25.65		
	Ch:330-360	1		30.00	5.70	5.70	0.15	25.65		
	Ch:360-370	1		10.00	5.70	5.70	0.15	8.55		
							Total Qty	**6882.20**	**1855.00**	**127,66,485.64**

18	KSRRB M400-17. Providing, laying, spreading and compacting cushed stone aggregates of granite / trap / basalt to wet mix macadam specifications including pre mixing the material with water at OMC in mechanical mix plant carriage of mixed materials by tipper to site, laying in uniform layers with paver in sub-base/base course on well prepared surface and compacting with vibratory roller to achieve the desired density complete as per specifications. MORTH Specification No. 406									
	KPWD S.R 2018-19	It. No.		20.18		Pg.No.		155		
	Byraveshwara circle									
	Ch:00-110 1st Cross									
	Ch:00-30	1		30.00	4.50	4.50	0.20	27.00		
	Ch:30-60	1		30.00	4.50	4.30	0.20	26.40		
	Ch:60-90	1		30.00	4.30	4.40	0.20	26.10		
	Ch:90-110	1		20.00	4.40	4.60	0.20	18.00		
	Ch:00-112 2nd Cross							0.00		
	Ch:00-30	1		30.00	5.00	5.00	0.20	30.00		
	Ch:30-60	1		30.00	4.80	4.90	0.20	29.10		
	Ch:60-90	1		30.00	4.90	5.10	0.20	30.00		
	Ch:90-112	1		22.00	5.10	4.90	0.20	22.00		
	Ch:00-110-3rd Cross									
	Ch:00-30	1		30.00	4.00	4.00	0.20	24.00		
	Ch:30-60	1		30.00	3.90	4.00	0.20	23.70		
	Ch:60-90	1		30.00	4.00	3.80	0.20	23.40		
	Ch:90-110	1		20.00	3.80	3.80	0.20	15.20		
	Ch:00-88 4th Cross									
	Ch:00-30	1		30.00	4.50	4.40	0.20	26.70		
	Ch:30-60	1		30.00	4.40	4.60	0.20	27.00		
	Ch:60-88	1		28.00	4.60	4.30	0.20	24.92		
	Ch:00-82 5th Cross							0.00		
	Ch:00-30	1		30.00	4.00	3.80	0.20	23.40		
	Ch:30-60	1		30.00	3.80	4.00	0.20	23.40		
	Ch:60-82	1		22.00	4.00	3.80	0.20	17.16		
	M.H.R. Layout									
	Ch:00-490(Chetana E lavada school Frant Rd to Siddhi Vinayaka Temple)									
	Ch:00-30	1		30.00	5.30	5.10	0.20	31.20		
	Ch:30-60	1		30.00	5.10	5.40	0.20	31.50		
	Ch:60-90	1		30.00	5.40	5.50	0.20	32.70		
	Ch:90-120	1		30.00	5.50	5.50	0.20	33.00		
	Ch:120-150	1		30.00	5.50	5.00	0.20	31.50		
	Ch:150-180	1		30.00	5.00	5.00	0.20	30.00		
	Ch:180-210	1		30.00	5.20	5.50	0.20	32.10		
	Ch:210-240	1		30.00	5.50	5.20	0.20	32.10		
	Ch:240-270	1		30.00	5.20	5.00	0.20	30.60		
	Ch:270-300	1		30.00	5.00	5.00	0.20	30.00		
	Ch:300-330	1		30.00	5.20	5.20	0.20	31.20		
	Ch:330-360	1		30.00	5.20	5.20	0.20	31.20		
	Ch:360-390	1		30.00	5.20	5.50	0.20	32.10		
	Ch:390-420	1		30.00	5.50	5.20	0.20	32.10		
	Ch:420-450	1		30.00	5.20	5.00	0.20	30.60		
	Ch:450-480	1		30.00	5.00	5.00	0.20	30.00		
	Ch:480-490	1		10.00	5.00	5.00	0.20	10.00		
	Ch:00-110 (4th Cross Road)									
	Ch:00-30	1		30.00	4.10	3.90	0.20	24.00		
	Ch:30-60	1		30.00	3.90	4.00	0.20	23.70		
	Ch:60-90	1		30.00	4.00	3.90	0.20	23.70		
	Ch:90-110	1		20.00	3.90	4.20	0.20	16.20		
	Ch:00-80 (5th Cross Road)									
	Ch:00-30	1		30.00	4.00	4.00	0.20	24.00		

Comprehensive development of bad roads and improvements to road side drain, footpaths, Asphalting and concreting including culvert selected main and other connecting roads of package No 1 in ward No 14, Begalagunte of Dasarahalli Division

Ch:30-60	1		30.00	3.80	4.20	0.20	24.00		
Ch:60-80	1		20.00	4.20	3.90	0.20	16.20		
Ch:00-75 (6th Cross Road)									
Ch:00-30	1		30.00	6.00	5.80	0.20	35.40		
Ch:30-60	1		30.00	5.80	5.90	0.20	35.10		
Ch:60-75	1		15.00	5.90	6.10	0.20	18.00		
Ch:00-110 (7th Cross Road)									
Ch:00-30	1		30.00	5.00	4.80	0.20	29.40		
Ch:30-60	1		30.00	4.80	5.20	0.20	30.00		
Ch:60-90	1		30.00	5.20	5.00	0.20	30.60		
Ch:90-110	1		20.00	5.00	5.00	0.20	20.00		
Ch:00-115 (8th Cross Road)									
Ch:00-30	1		30.00	4.90	4.80	0.20	29.10		
Ch:30-60	1		30.00	4.80	4.90	0.20	29.10		
Ch:60-90	1		30.00	4.90	5.00	0.20	29.70		
Ch:90-115	1		25.00	5.00	4.90	0.20	24.75		
Ch:00-210(1st Main)									
Ch:00-30	1		30.00	4.50	4.50	0.20	27.00		
Ch:30-60	1		30.00	4.50	4.50	0.20	27.00		
Ch:60-90	1		30.00	4.50	4.50	0.20	27.00		
Ch:90-120	1		30.00	4.50	4.50	0.20	27.00		
Ch:120-150	1		30.00	4.50	4.60	0.20	27.30		
Ch:150-180	1		30.00	4.60	4.60	0.20	27.60		
Ch:180-210	1		30.00	4.60	4.60	0.20	27.60		
MEENAKSHI layout									
Ch:00-280(1st Main)									
Ch:00-30	1		30.00	5.50	5.40	0.20	32.70		
Ch:30-60	1		30.00	5.40	5.50	0.20	32.70		
Ch:60-90	1		30.00	5.50	5.20	0.20	32.10		
Ch:90-120	1		30.00	5.20	5.40	0.20	31.80		
Ch:120-150	1		30.00	5.40	5.60	0.20	33.00		
Ch:150-180	1		30.00	5.60	5.40	0.20	33.00		
Ch:180-210	1		30.00	5.40	5.50	0.20	32.70		
Ch:210-240	1		30.00	5.50	5.50	0.20	33.00		
Ch:240-270	1		30.00	5.50	5.20	0.20	32.10		
Ch:270-280	1		10.00	5.20	5.40	0.20	10.60		
Ch:00-280(2nd Main)									
Ch:00-30	1		30.00	5.00	5.00	0.20	30.00		
Ch:30-60	1		30.00	5.00	4.80	0.20	29.40		
Ch:60-90	1		30.00	4.80	5.20	0.20	30.00		
Ch:90-120	1		30.00	5.20	4.60	0.20	29.40		
Ch:120-150	1		30.00	4.60	5.00	0.20	28.80		
Ch:150-180	1		30.00	5.00	4.80	0.20	29.40		
Ch:180-210	1		30.00	4.80	5.20	0.20	30.00		
Ch:210-240	1		30.00	5.20	4.80	0.20	30.00		
Ch:240-270	1		30.00	4.80	5.20	0.20	30.00		
Ch:270-280	1		10.00	5.20	5.00	0.20	10.20		
Ch:00-270(1st B Main)									
Ch:00-30	1		30.00	5.20	5.20	0.20	31.20		
Ch:30-60	1		30.00	5.20	5.20	0.20	31.20		
Ch:60-90	1		30.00	5.20	5.20	0.20	31.20		
Ch:90-120	1		30.00	5.20	5.20	0.20	31.20		
Ch:120-150	1		30.00	5.20	5.20	0.20	31.20		
Ch:150-180	1		30.00	5.20	5.30	0.20	31.50		
Ch:180-210	1		30.00	5.30	5.30	0.20	31.80		
Ch:210-240	1		30.00	5.30	5.30	0.20	31.80		
Ch:240-270	1		30.00	5.30	5.30	0.20	31.80		
Ch:00-280(1st C Main)									
Ch:00-30	1		30.00	5.50	5.50	0.20	33.00		
Ch:30-60	1		30.00	5.50	5.50	0.20	33.00		
Ch:60-90	1		30.00	5.50	5.50	0.20	33.00		
Ch:90-120	1		30.00	5.50	5.50	0.20	33.00		
Ch:120-150	1		30.00	5.50	5.50	0.20	33.00		
Ch:150-180	1		30.00	5.50	5.50	0.20	33.00		
Ch:180-210	1		30.00	5.50	5.40	0.20	32.70		
Ch:210-240	1		30.00	5.40	5.40	0.20	32.40		
Ch:240-270	1		30.00	5.40	5.40	0.20	32.40		
Ch:270-280	1		10.00	5.40	5.40	0.20	10.80		
Ch:00-95(14th Cross Road)									
Ch:00-30	1		30.00	5.00	4.80	0.20	29.40		

FOR 1SQM AREA

Ch:30-60	1		30.00	4.80	5.00	0.20	29.40		
Ch:60-95	1		35.00	5.00	5.20	0.20	35.70		
Ch:00-116(12th Cross Road)									
Ch:00-30	1		30.00	5.00	4.80	0.20	29.40		
Ch:30-60	1		30.00	4.80	5.20	0.20	30.00		
Ch:60-90	1		30.00	5.20	4.80	0.20	30.00		
Ch:90-110	1		20.00	4.80	4.90	0.20	19.40		
Ch:00-140(10th Cross Road)									
Ch:00-30	1		30.00	4.50	4.40	0.20	26.70		
Ch:30-60	1		30.00	4.40	4.50	0.20	26.70		
Ch:60-90	1		30.00	4.50	4.00	0.20	25.50		
Ch:90-120	1		30.00	4.00	4.20	0.20	24.60		
Ch:120-140	1		20.00	4.20	4.40	0.20	17.20		
Ch:00-96(9th Cross Road)									
Ch:00-30	1		30.00	4.50	4.40	0.20	26.70		
Ch:30-60	1		30.00	4.40	4.50	0.20	26.70		
Ch:60-96	1		36.00	4.50	4.40	0.20	32.04		
Ch:00-62(8th Cross Road)									
Ch:00-30	1		30.00	4.50	4.40	0.20	26.70		
Ch:30-62	1		32.00	4.40	4.50	0.20	28.48		
Ch:00-105(7th Cross Road)									
Ch:00-30	1		30.00	4.50	4.40	0.20	26.70		
Ch:30-60	1		30.00	4.40	4.50	0.20	26.70		
Ch:60-90	1		30.00	4.50	4.00	0.20	25.50		
Ch:90-105	1		15.00	4.00	4.20	0.20	12.30		
Ch:00-65(6th Cross Road)									
Ch:00-30	1		30.00	4.50	4.40	0.20	26.70		
Ch:30-65	1		35.00	4.40	4.50	0.20	31.15		
Ch:00-64(5th Cross Road)									
Ch:00-30	1		30.00	4.50	4.40	0.20	26.70		
Ch:30-64	1		34.00	4.40	4.50	0.20	30.26		
Ch:00-63(4th Cross Road)									
Ch:00-30	1		30.00	4.50	4.40	0.20	26.70		
Ch:30-63	1		33.00	4.40	4.50	0.20	29.37		
Ch:00-65(3rd Cross Road)									
Ch:00-30	1		30.00	4.50	4.40	0.20	26.70		
Ch:30-65	1		35.00	4.40	4.50	0.20	31.15		
Ch:00-66(2nd Cross Road)									
Ch:00-30	1		30.00	4.50	4.40	0.20	26.70		
Ch:30-66	1		36.00	4.40	4.50	0.20	32.04		
Ch:00-80(1st Cross Road)									
Ch:00-30	1		30.00	4.50	4.50	0.20	27.00		
Ch:30-60	1		30.00	4.50	4.40	0.20	26.70		
Ch:60-80	1		20.00	4.40	4.50	0.20	17.80		
Soundarya layout 2nd Main									
Ch00-95(11th Cross Road)									
Ch:00-30	1		30.00	5.00	4.80	0.20	29.40		
Ch:30-60	1		30.00	4.80	5.20	0.20	30.00		
Ch:60-95	1		35.00	5.20	4.80	0.20	35.00		
Ch:00-85(10th Cross Road)									
Ch:00-30	1		30.00	5.00	4.80	0.20	29.40		
Ch:30-60	1		30.00	4.80	5.20	0.20	30.00		
Ch:60-85	1		25.00	5.20	4.80	0.20	25.00		
Ch:00-75(9th Cross Road)									
Ch:00-30	1		30.00	5.00	4.80	0.20	29.40		
Ch:30-60	1		30.00	4.80	5.20	0.20	30.00		
Ch:60-75	1		15.00	5.20	4.80	0.20	15.00		
Ch:00-68(8th Cross Road)									
Ch:00-30	1		30.00	5.00	4.80	0.20	29.40		
Ch:30-68	1		38.00	4.80	5.20	0.20	38.00		
Ch:00-50(7th Cross Road)									
Ch:00-30	1		30.00	5.00	4.80	0.20	29.40		
Ch:30-50	1		20.00	4.80	5.20	0.20	20.00		
Ch:00-43(6th Cross Road)									
Ch:00-30	1		30.00	5.00	4.80	0.20	29.40		
Ch:30-43	1		13.00	4.80	5.20	0.20	13.00		
Ch:00-60(4th Cross Road)									
Ch:00-30	1		30.00	5.00	4.80	0.20	29.40		
Ch:30-60	1		30.00	4.80	5.20	0.20	30.00		
Ch:00-152(3rd Cross Road)									

Ch:00-30		1		30.00	5.00	4.80	0.20	29.40	
Ch:30-60		1		30.00	4.80	5.20	0.20	30.00	
Ch:60-90		1		30.00	5.20	4.80	0.20	30.00	
Ch:90-120		1		30.00	4.80	5.20	0.20	30.00	
Ch:120-152		1		32.00	5.20	5.00	0.20	32.64	
Ch:00-100 (Cross Road)									
Ch:00-30		1		30.00	5.00	4.80	0.20	29.40	
Ch:30-60		1		30.00	4.80	5.20	0.20	30.00	
Ch:60-90		1		30.00	5.20	4.80	0.20	30.00	
Ch:90-100		1		10.00	4.80	5.20	0.20	10.00	
Ch:00-225 (Cross Road)									
Ch:00-30		1		30.00	5.50	5.40	0.20	32.70	
Ch:30-60		1		30.00	5.40	5.50	0.20	32.70	
Ch:60-90		1		30.00	5.50	5.20	0.20	32.10	
Ch:90-120		1		30.00	5.20	5.40	0.20	31.80	
Ch:120-150		1		30.00	5.40	5.40	0.20	32.40	
Ch:150-180		1		30.00	5.40	5.50	0.20	32.70	
Ch:180-210		1		30.00	5.50	5.20	0.20	32.10	
Ch:210-225		1		15.00	5.20	5.40	0.20	15.90	
Ch:00-125(3rd Main Road)									
Ch:00-30		1		30.00	5.00	4.80	0.20	29.40	
Ch:30-60		1		30.00	4.80	5.20	0.20	30.00	
Ch:60-90		1		30.00	5.20	4.80	0.20	30.00	
Ch:90-120		1		35.00	4.80	5.20	0.20	35.00	
Ch:00-230(3rd Main Road)									
Ch:00-30		1		30.00	5.00	4.80	0.20	29.40	
Ch:30-60		1		30.00	4.80	5.20	0.20	30.00	
Ch:60-90		1		30.00	5.20	4.80	0.20	30.00	
Ch;90-120		1		30.00	4.80	5.20	0.20	30.00	
Ch:120-150		1		30.00	5.20	4.80	0.20	30.00	
Ch:150-180		1		30.00	4.80	5.20	0.20	30.00	
Ch:180-210		1		30.00	5.20	4.80	0.20	30.00	
Ch:210-230		1		20.00	4.80	5.20	0.20	20.00	
Soundarya layout 1st Main									
Ch:00-90(1st A Cross Road)									
Ch:00-30		1		30.00	5.00	4.80	0.20	29.40	
Ch:30-60		1		30.00	4.80	5.20	0.20	30.00	
Ch:60-90		1		30.00	5.20	4.80	0.20	30.00	
Ch:00-100(2nd A Cross Road)									
Ch:00-30	Cum	1		30.00	5.00	4.80	0.20	29.40	
Ch:30-60		1		30.00	4.80	5.20	0.20	30.00	
Ch:60-90		1		30.00	5.20	4.80	0.20	30.00	
Ch:90-100		1		10.00	4.80	4.90	0.20	9.70	
Ch:00-90(4th A Cross Road)									
Ch:00-30		1		30.00	5.00	4.80	0.20	29.40	
Ch:30-60		1		30.00	4.80	5.20	0.20	30.00	
Ch:60-90		1		30.00	5.20	4.80	0.20	30.00	
Ch:00-90(6th A Cross Road)									
Ch:00-30		1		30.00	5.00	4.80	0.20	29.40	
Ch:30-60		1		30.00	4.80	5.20	0.20	30.00	
Ch:60-90		1		30.00	5.20	4.80	0.20	30.00	
Ch:00-90(7th A Cross Road)									
Ch:00-30		1		30.00	5.00	4.90	0.20	29.70	
Ch:30-60		1		30.00	4.90	5.20	0.20	30.30	
Ch:60-90		1		30.00	5.20	4.80	0.20	30.00	
Ch:00-93(8th A Cross Road)									
Ch:00-30		1		30.00	5.00	4.80	0.20	29.40	
Ch:30-60		1		30.00	4.80	5.20	0.20	30.00	
Ch:60-93		1		33.00	5.20	4.80	0.20	33.00	
Ch:00-92(9th A Cross Road)									
Ch:00-30		1		30.00	5.00	4.90	0.20	29.70	
Ch:30-60		1		30.00	4.90	5.20	0.20	30.30	
Ch:60-92		1		32.00	5.20	4.80	0.20	32.00	
Ch:00-90(11th A Cross Road)									
Ch:00-30		1		30.00	5.00	4.80	0.20	29.40	
Ch:30-60		1		30.00	4.80	5.20	0.20	30.00	
Ch:60-90		1		30.00	5.20	4.80	0.20	30.00	
Ch:00-93(12th A Cross Road)									
Ch:00-30		1		30.00	5.00	4.80	0.20	29.40	
Ch:30-60		1		30.00	4.80	5.20	0.20	30.00	

Ch:60-93	1		33.00	5.20	4.80	0.20	33.00		
Ch:00-92(13th A Cross Road)									
Ch:00-30	1		30.00	5.00	4.80	0.20	29.40		
Ch:30-60	1		30.00	4.80	5.20	0.20	30.00		
Ch:60-92	1		32.00	5.20	4.80	0.20	32.00		
Ch:00-92(14th A Cross Road)									
Ch:00-30	1		30.00	5.00	4.80	0.20	29.40		
Ch:30-60	1		30.00	4.80	5.20	0.20	30.00		
Ch:60-92	1		32.00	5.20	4.80	0.20	32.00		
Ch:00-95(2nd B mainb Road)									
Ch:00-30	1		30.00	5.00	5.10	0.20	30.30		
Ch:30-60	1		30.00	5.10	5.20	0.20	30.90		
Ch:60-95	1		35.00	5.20	5.10	0.20	36.05		
Siddeshwara Layout									
Ch:00-950									
Ch:00-30	1		30.00	5.50	5.40	0.20	32.70		
Ch:30-60	1		30.00	5.40	5.50	0.20	32.70		
Ch:60-90	1		30.00	5.50	5.20	0.20	32.10		
Ch:90-120	1		30.00	5.20	5.40	0.20	31.80		
Ch:120-150	1		30.00	5.40	5.40	0.20	32.40		
Ch:150-180	1		30.00	5.40	5.50	0.20	32.70		
Ch:180-210	1		30.00	5.50	5.20	0.20	32.10		
Ch:210-240	1		30.00	5.20	5.40	0.20	31.80		
Ch:240-270	1		30.00	5.40	5.40	0.20	32.40		
Ch:270-300	1		30.00	5.40	5.50	0.20	32.70		
Ch:300-330	1		30.00	5.50	5.20	0.20	32.10		
Ch:330-360	1		30.00	5.20	5.40	0.20	31.80		
Ch:360-390	1		30.00	5.40	5.40	0.20	32.40		
Ch:390-420	1		30.00	5.40	5.50	0.20	32.70		
Ch:420-450	1		30.00	5.50	5.20	0.20	32.10		
Ch:450-480	1		30.00	5.20	5.40	0.20	31.80		
Ch:480-510	1		30.00	5.40	5.40	0.20	32.40		
Ch:510-540	1		30.00	5.40	5.50	0.20	32.70		
Ch:540-570	1		30.00	5.50	5.20	0.20	32.10		
Ch:570-600	1		30.00	5.20	5.40	0.20	31.80		
Ch:600-630	1		30.00	5.40	5.40	0.20	32.40		
Ch:630-660	1		30.00	5.40	5.50	0.20	32.70		
Ch:660-690	1		30.00	5.50	5.20	0.20	32.10		
Ch:690-720	1		30.00	5.20	5.40	0.20	31.80		
Ch:720-750	1		30.00	5.40	5.40	0.20	32.40		
Ch:750-780	1		30.00	5.40	5.50	0.20	32.70		
Ch:780-810	1		30.00	5.50	5.20	0.20	32.10		
Ch:810-840	1		30.00	5.20	5.40	0.20	31.80		
Ch:840-870	1		30.00	5.40	5.40	0.20	32.40		
Ch:870-900	1		30.00	5.40	5.50	0.20	32.70		
Ch:900-930	1		30.00	5.50	5.20	0.20	32.10		
Ch:930-950	1		20.00	5.20	5.40	0.20	21.20		
Ch:00-100 NMH Public school road									
Ch:00-30	1		30.00	5.00	4.80	0.20	29.40		
Ch:30-60	1		30.00	4.80	5.20	0.20	30.00		
Ch:60-90	1		30.00	5.20	4.80	0.20	30.00		
Ch:90-100	1		10.00	4.80	5.00	0.20	9.80		
Ch:00-145 8th cross									
Ch:00-30	1		30.00	5.20	5.20	0.20	31.20		
Ch:30-60	1		30.00	5.20	5.20	0.20	31.20		
Ch:60-90	1		30.00	5.20	5.20	0.20	31.20		
Ch:90-120	1		30.00	5.20	5.30	0.20	31.50		
Ch:120-145	1		25.00	5.30	5.30	0.20	26.50		
Royal Enclave Layout									
Ch:00-80 Cross rd beside NMH Convention Hall									
Ch:00-30	1		30.00	4.50	4.40	0.20	26.70		
Ch:30-60	1		30.00	4.40	4.50	0.20	26.70		
Ch:60-80	1		20.00	4.50	4.40	0.20	17.80		
Ch:00-230 Siddeshwara Temple Road									
Ch:00-30	1		30.00	6.00	5.80	0.20	35.40		
Ch:30-60	1		30.00	5.80	5.90	0.20	35.10		
Ch:60-90	1		30.00	5.90	6.10	0.20	36.00		
Ch:90-120	1		30.00	6.00	5.70	0.20	35.10		
Ch:120-150	1		30.00	5.70	5.90	0.20	34.80		

Comprehensive development of bad roads and improvements to road side drain, footpaths, Asphalting and concreting including culvert selected main and other connecting roads of package No 1 in ward No 1A, Bagalagunte & Dasarahalli Division

Ch:150-180	1		30.00	5.90	5.50	0.20	34.20	
Ch:180-210	1		30.00	5.50	6.00	0.20	34.50	
Ch:210-230	1		20.00	6.00	5.80	0.20	23.60	
Ch:00-70 1st cross								
Ch:00-30	1		30.00	4.50	4.40	0.20	26.70	
Ch:30-60	1		30.00	4.40	4.50	0.20	26.70	
Ch:60-70	1		10.00	4.50	4.40	0.20	8.90	
Ch:00-85 2nd Cross								
Ch:00-30	1		30.00	4.50	4.40	0.20	26.70	
Ch:30-60	1		30.00	4.40	4.50	0.20	26.70	
Ch:60-85	1		25.00	4.50	4.40	0.20	22.25	
Ch:00-80 3rd Cross								
Ch:00-30	1		30.00	4.50	4.40	0.20	26.70	
Ch:30-60	1		30.00	4.40	4.50	0.20	26.70	
Ch:60-80	1		20.00	4.50	4.40	0.20	17.80	
Ch:00-80 4rd Cross								
Ch:00-30	1		30.00	4.50	4.40	0.20	26.70	
Ch:30-60	1		30.00	4.40	4.50	0.20	26.70	
Ch:60-80	1		20.00	4.50	4.40	0.20	17.80	
NMH Layout								
Ch:00-220 Basava Dhyana Kendra								
Ch:00-30	1		30.00	4.30	4.30	0.20	25.80	
Ch:30-60	1		30.00	4.30	4.30	0.20	25.80	
Ch:60-90	1		30.00	4.30	4.30	0.20	25.80	
Ch:90-120	1		30.00	4.30	4.40	0.20	26.10	
Ch:120-150	1		30.00	4.40	4.40	0.20	26.40	
Ch:150-180	1		30.00	4.40	4.50	0.20	26.70	
Ch:180-210	1		30.00	4.50	4.50	0.20	27.00	
Ch:210-220	1		10.00	4.50	4.40	0.20	8.90	
Ch:00-180 BESCOM Bagalugunte								
Ch:00-30	1		30.00	5.30	5.30	0.20	31.80	
Ch:30-60	1		30.00	5.30	5.30	0.20	31.80	
Ch:60-90	1		30.00	5.30	5.40	0.20	32.10	
Ch:90-120	1		30.00	5.40	5.40	0.20	32.40	
Ch:120-150	1		30.00	5.40	5.50	0.20	32.70	
Ch:150-180	1		30.00	5.50	5.50	0.20	33.00	
Ch:00-230 1st main								
Ch:00-30	1		30.00	4.80	4.80	0.20	28.80	
Ch:30-60	1		30.00	4.80	4.80	0.20	28.80	
Ch:60-90	1		30.00	4.80	4.90	0.20	29.10	
Ch:90-120	1		30.00	4.90	4.90	0.20	29.40	
Ch:120-150	1		30.00	4.90	4.90	0.20	29.40	
Ch:150-180	1		30.00	4.90	4.90	0.20	29.40	
Ch:180-210	1		30.00	4.90	4.90	0.20	29.40	
Ch:210-230	1		20.00	4.90	4.90	0.20	19.60	
Ch:00-140 2nd main								
Ch:00-30	1		30.00	4.90	4.90	0.20	29.40	
Ch:30-60	1		30.00	4.90	4.90	0.20	29.40	
Ch:60-90	1		30.00	4.90	5.00	0.20	29.70	
Ch:90-120	1		30.00	5.00	5.00	0.20	30.00	
Ch:120-140	1		20.00	5.00	5.00	0.20	20.00	
Kirloskar connecting road								
Ch:00-370 4nd main								
Ch:00-30	1		30.00	5.80	5.80	0.20	34.80	
Ch:30-60	1		30.00	5.80	5.80	0.20	34.80	
Ch:60-90	1		30.00	5.80	5.80	0.20	34.80	
Ch:90-120	1		30.00	5.80	5.80	0.20	34.80	
Ch:120-150	1		30.00	5.80	5.80	0.20	34.80	
Ch:150-180	1		30.00	5.80	5.80	0.20	34.80	
Ch:180-210	1		30.00	5.80	5.80	0.20	34.80	
Ch:210-240	1		30.00	5.80	5.80	0.20	34.80	
Ch:240-270	1		30.00	5.80	5.70	0.20	34.50	
Ch:270-300	1		30.00	5.70	5.70	0.20	34.20	
Ch:300-330	1		30.00	5.70	5.70	0.20	34.20	
Ch:330-360	1		30.00	5.70	5.70	0.20	34.20	
Ch:360-370	1		10.00	5.70	5.70	0.20	11.40	
Overlay BC road								
Royal Enclave Layout								
Ch:00-310 (Naga Devaata Temple Road)								

Ch:00-30	2		30.00	0.80	0.80	0.20	9.60			
Ch:30-60	2		30.00	0.80	0.80	0.20	9.60			
Ch:60-90	2		30.00	0.80	0.80	0.20	9.60			
Ch:90-120	2		30.00	0.80	0.80	0.20	9.60			
Ch:120-150	2		30.00	0.80	0.80	0.20	9.60			
Ch:150-180	2		30.00	0.80	0.80	0.20	9.60			
Ch:180-210	2		30.00	0.80	0.80	0.20	9.60			
Ch:210-240	2		30.00	0.80	0.80	0.20	9.60			
Ch:240-270	2		30.00	0.80	0.80	0.20	9.60			
Ch:270-300	2		30.00	0.80	0.80	0.20	9.60			
Ch:300-310	2		10.00	0.80	0.80	0.20	3.20			
Ch:00-215 (From Byraveshwara Circle)										
Ch:00-30	2		30.00	0.80	0.80	0.20	9.60			
Ch:30-60	2		30.00	0.80	0.80	0.20	9.60			
Ch:60-90	2		30.00	0.80	0.80	0.20	9.60			
Ch:90-120	2		30.00	0.80	0.80	0.20	9.60			
Ch:120-150	2		30.00	0.80	0.80	0.20	9.60			
Ch:150-180	2		30.00	0.80	0.80	0.20	9.60			
Ch:180-215	2		35.00	0.80	0.80	0.20	11.20			
Soundarya layout 1st Main										
Ch:00-530(1st Main)										
Ch:00-30	2		30.00	0.80	0.80	0.20	9.60			
Ch:30-60	2		30.00	0.80	0.80	0.20	9.60			
Ch:60-90	2		30.00	0.80	0.80	0.20	9.60			
Ch:90-120	2		30.00	0.80	0.80	0.20	9.60			
Ch:120-150	2		30.00	0.80	0.80	0.20	9.60			
Ch:150-180	2		30.00	0.80	0.80	0.20	9.60			
Ch:180-210	2		30.00	0.80	0.80	0.20	9.60			
Ch:210-240	2		30.00	0.80	0.80	0.20	9.60			
Ch:240-270	2		30.00	0.80	0.80	0.20	9.60			
Ch:270-300	2		30.00	0.80	0.80	0.20	9.60			
Ch:300-330	2		30.00	0.80	0.80	0.20	9.60			
Ch:330-360	2		30.00	0.80	0.80	0.20	9.60			
Ch:360-390	2		30.00	0.80	0.80	0.20	9.60			
Ch:390-420	2		30.00	0.80	0.80	0.20	9.60			
Ch:420-450	2		30.00	0.80	0.80	0.20	9.60			
Ch:450-480	2		30.00	0.80	0.80	0.20	9.60			
Ch:480-510	2		30.00	0.80	0.80	0.20	9.60			
Ch:510-530	2		20.00	0.80	0.80	0.20	6.40			
Soundarya layout 2nd Main										
Ch:00-530(2nd Main)										
Ch:00-30	2		30.00	0.80	0.80	0.20	9.60			
Ch:30-60	2		30.00	0.80	0.80	0.20	9.60			
Ch:60-90	2		30.00	0.80	0.80	0.20	9.60			
Ch:90-120	2		30.00	0.80	0.80	0.20	9.60			
Ch:120-150	2		30.00	0.80	0.80	0.20	9.60			
Ch:150-180	2		30.00	0.80	0.80	0.20	9.60			
Ch:180-210	2		30.00	0.80	0.80	0.20	9.60			
Ch:210-240	2		30.00	0.80	0.80	0.20	9.60			
Ch:240-270	2		30.00	0.80	0.80	0.20	9.60			
Ch:270-300	2		30.00	0.80	0.80	0.20	9.60			
Ch:300-330	2		30.00	0.80	0.80	0.20	9.60			
Ch:330-360	2		30.00	0.80	0.80	0.20	9.60			
Ch:360-390	2		30.00	0.80	0.80	0.20	9.60			
Ch:390-420	2		30.00	0.80	0.80	0.20	9.60			
Ch:420-450	2		30.00	0.80	0.80	0.20	9.60			
Ch:450-480	2		30.00	0.80	0.80	0.20	9.60			
Ch:480-510	2		30.00	0.80	0.80	0.20	9.60			
Ch:510-530	2		20.00	0.80	0.80	0.20	6.40			
Restoration For BWSSB Cutting	2		9188.00	0.80		0.20	2940.16			
							Total Qty	**12626.42**	**2001.28**	**252,69,001.82**

19 KSRRB 500-2. Cleaning the existing black topped surface with Sqm brooms, soft brushes and finally dusting with old gunny bags and / or compressed air to receive bituminous treatment including cost of all materials, labour, HOM complete as per specifications. Clause 501 of MORTH V revision

KPWD 2018-19	It.no	21.20		Page.no	158				
Byraveshwara circle									
Ch:00-310 (Naga Devaata Temple Road)									
Ch:00-30	1		30.00	6.50	6.50		195.00		
Ch:30-60			30.00	6.50	6.60		196.50		
Ch:60-90	1		30.00	6.60	6.40		195.00		

	Ch:90-120		1		30.00	6.40	6.50		193.50		
	Ch:120-150		1		30.00	6.50	6.40		193.50		
	Ch:150-180		1		30.00	6.40	6.40		192.00		
	Ch:180-210		1		30.00	6.40	6.50		193.50		
	Ch:210-240		1		30.00	6.50	6.30		192.00		
	Ch:240-270		1		30.00	6.30	6.50		192.00		
	Ch:270-300		1		30.00	6.50	6.50		195.00		
	Ch:300-310		1		10.00	6.50	6.50		65.00		
	Ch:00-215 (From Byraveshwara Circle)										
	Ch:00-30		1		30.00	7.00	7.00		210.00		
	Ch:30-60		1		30.00	6.80	7.20		210.00		
	Ch:60-90		1		30.00	7.20	7.00		213.00		
	Ch:90-120		1		30.00	7.00	6.80		207.00		
	Ch:120-150		1		30.00	6.80	6.60		201.00		
	Ch:150-180		1		30.00	6.60	6.80		201.00		
	Ch:180-215		1		35.00	6.80	7.20		245.00		
	Soundarya layout 2nd Main										
	Ch:00-510(2nd Main Road)										
	Ch:00-30		1		30.00	8.00	7.50		232.50		
	Ch:30-60		1		30.00	7.50	7.80		229.50		
	Ch:60-90		1		30.00	7.80	7.90		235.50		
	Ch:90-120		1		30.00	7.90	7.70		234.00		
	Ch:120-150		1		30.00	7.70	8.00		235.50		
	Ch:150-180		1		30.00	8.00	8.20		243.00		
	Ch:180-210		1		30.00	8.20	8.00		243.00		
	Ch:210-240		1		30.00	8.00	7.90		238.50		
	Ch:240-270	Sqm	1		30.00	7.90	7.80		235.50		
	Ch:270-300		1		30.00	7.80	8.20		240.00		
	Ch:300-330		1		30.00	8.20	8.00		243.00		
	Ch:330-360		1		30.00	8.00	7.90		238.50		
	Ch:360-390		1		30.00	7.90	7.80		235.50		
	Ch:390-420		1		30.00	7.80	8.00		237.00		
	Ch:420-450		1		30.00	8.00	8.20		243.00		
	Ch:450-480		1		30.00	8.20	8.00		243.00		
	Ch:480-510		1		30.00	8.00	8.00		240.00		
	Ch:210-530		1		20.00	8.00	8.00		160.00		
	Soundarya layout 1st Main										
	Ch:00-530(1st Main)										
	Ch:00-30		1		30.00	7.00	6.80		207.00		
	Ch:30-60		1		30.00	6.80	7.00		207.00		
	Ch:60-90		1		30.00	7.00	6.90		208.50		
	Ch:90-120		1		30.00	6.90	6.80		205.50		
	Ch:120-150		1		30.00	6.80	6.50		199.50		
	Ch:150-180		1		30.00	6.50	6.80		199.50		
	Ch:180-210		1		30.00	6.80	7.20		210.00		
	Ch:210-240		1		30.00	7.20	7.00		213.00		
	Ch:240-270		1		30.00	7.00	7.00		210.00		
	Ch:270-300		1		30.00	7.00	6.90		208.50		
	Ch:300-330		1		30.00	6.90	6.80		205.50		
	Ch:330-360		1		30.00	6.80	7.10		208.50		
	Ch:360-390		1		30.00	7.10	7.00		211.50		
	Ch:390-420		1		30.00	7.00	6.80		207.00		
	Ch:420-450		1		30.00	6.80	6.90		205.50		
	Ch:450-480		1		30.00	6.90	7.10		210.00		
	Ch:480-510		1		30.00	7.10	7.00		211.50		
	Ch:510-530		1		20.00	7.00	7.00		140.00		
								Total Qty	**11365.00**	**5.30**	60,234.50
20	KSRRB M500-6. Providing and applying primer coat with S.S. bitumen emulsion on prepared surface of granular base such as WMM including cleaning of road surface and spraying primer at the rate of 0.60 kg / sqm using mechanical means complete as per specifications.Clause 502 of MORTH V revision										
	KPWD Issue S.R 2020-21	It. No.			21.6		Pg.No.	158			
	Byraveshwara circle										
	Ch:00-310 (Naga Devaata Temple Road)										
	Ch:00-30		1		30.00	6.50	6.50		195.00		
	Ch:30-60		1		30.00	6.50	6.60		196.50		
	Ch:60-90		1		30.00	6.60	6.40		195.00		
	Ch:90-120		1		30.00	6.40	6.50		193.50		
	Ch:120-150		1		30.00	6.50	6.40		193.50		
	Ch:150-180		1		30.00	6.40	6.40		192.00		
	Ch:180-210		1		30.00	6.40	6.50		193.50		

Ch:210-240	1		30.00	6.50	6.30		192.00		
Ch:240-270	1		30.00	6.30	6.50		192.00		
Ch:270-300	1		30.00	6.50	6.50		195.00		
Ch:300-310	1		10.00	6.50	6.50		65.00		
Ch:00-215 (From Byraveshwara Circle)									
Ch:00-30	1		30.00	7.00	7.00		210.00		
Ch:30-60	1		30.00	6.80	7.20		210.00		
Ch:60-90	1		30.00	7.20	7.00		213.00		
Ch:90-120	1		30.00	7.00	6.80		207.00		
Ch:120-150	1		30.00	6.80	6.60		201.00		
Ch:150-180	1		30.00	6.60	6.80		201.00		
Ch:180-215	1		35.00	6.80	7.20		245.00		
Ch:00-110 1st Cross									
Ch:00-30	1		30.00	4.50	4.50		135.00		
Ch:30-60	1		30.00	4.50	4.30		132.00		
Ch:60-90	1		30.00	4.30	4.40		130.50		
Ch:90-110	1		20.00	4.40	4.60		90.00		
Ch:00-112 2nd Cross									
Ch:00-30	1		30.00	5.00	5.00		150.00		
Ch:30-60	1		30.00	4.80	4.90		145.50		
Ch:60-90	1		30.00	4.90	5.10		150.00		
Ch:90-112	1		22.00	5.10	4.90		110.00		
Ch:00-110-3rd Cross									
Ch:00-30	1		30.00	4.00	4.00		120.00		
Ch:30-60	1		30.00	3.90	4.00		118.50		
Ch:60-90	1		30.00	4.00	3.80		117.00		
Ch:90-110	1		20.00	3.80	3.80		76.00		
Ch:00-88 4th Cross									
Ch:00-30	1		30.00	4.50	4.40		133.50		
Ch:30-60	1		30.00	4.40	4.60		135.00		
Ch:60-88	1		28.00	4.60	4.30		124.60		
Ch:00-82 5th Cross									
Ch:00-30	1		30.00	4.00	3.80		117.00		
Ch:30-60	1		30.00	3.80	4.00		117.00		
Ch:60-82	1		22.00	4.00	3.80		85.80		
M.H.R. Layout									
Ch:00-490(Chetana E lavada school Frant Rd to Siddhi Vinayaka Temple)									
Ch:00-30	1		30.00	5.30	5.10		156.00		
Ch:30-60	1		30.00	5.10	5.40		157.50		
Ch:60-90	1		30.00	5.40	5.50		163.50		
Ch:90-120	1		30.00	5.50	5.50		165.00		
Ch:120-150	1		30.00	5.50	5.00		157.50		
Ch:150-180	1		30.00	5.00	5.00		150.00		
Ch:180-210	1		30.00	5.20	5.50		160.50		
Ch:210-240	1		30.00	5.50	5.20		160.50		
Ch:240-270	1		30.00	5.20	5.00		153.00		
Ch:270-300	1		30.00	5.00	5.00		150.00		
Ch:300-330	1		30.00	5.20	5.20		156.00		
Ch:330-360	1		30.00	5.20	5.20		156.00		
Ch:360-390	1		30.00	5.20	5.50		160.50		
Ch:390-420	1		30.00	5.50	5.20		160.50		
Ch:420-450	1		30.00	5.20	5.00		153.00		
Ch:450-480	1		30.00	5.00	5.00		150.00		
Ch:480-490	1		10.00	5.00	5.00		50.00		
Ch:00-110 (4th Cross Road)									
Ch:00-30	1		30.00	4.10	3.90		120.00		
Ch:30-60	1		30.00	3.90	4.00		118.50		
Ch:60-90	1		30.00	4.00	3.90		118.50		
Ch:90-110	1		20.00	3.90	4.20		81.00		
Ch:00-80 (5th Cross Road)									
Ch:00-30	1		30.00	4.00	4.00		120.00		
Ch:30-60	1		30.00	3.80	4.20		120.00		
Ch:60-80	1		20.00	4.20	3.90		81.00		
Ch:00-75 (6th Cross Road)									
Ch:00-30	1		30.00	6.00	5.80		177.00		
Ch:30-60	1		30.00	5.80	5.90		175.50		
Ch:60-75	1		15.00	5.90	6.10		90.00		
Ch:00-110 (7th Cross Road)									
Ch:00-30	1		30.00	5.00	4.80		147.00		

Ch:30-60	1		30.00	4.80	5.20		150.00		
Ch:60-90	1		30.00	5.20	5.00		153.00		
Ch:90-110	1		20.00	5.00	5.00		100.00		
Ch:00-115 (8th Cross Road)									
Ch:00-30	1		30.00	4.90	4.80		145.50		
Ch:30-60	1		30.00	4.80	4.90		145.50		
Ch:60-90	1		30.00	4.90	5.00		148.50		
Ch:90-115	1		25.00	5.00	4.90		123.75		
Ch:00-210(1st Main)									
Ch:00-30	1		30.00	4.50	4.50		135.00		
Ch:30-60	1		30.00	4.50	4.50		135.00		
Ch:60-90	1		30.00	4.50	4.50		135.00		
Ch:90-120	1		30.00	4.50	4.50		135.00		
Ch:120-150	1		30.00	4.50	4.60		136.50		
Ch:150-180	1		30.00	4.60	4.60		138.00		
Ch:180-210	1		30.00	4.60	4.60		138.00		
MEENAKSHI layout									
Ch:00-280(1st Main)									
Ch:00-30	1		30.00	5.50	5.40		163.50		
Ch:30-60	1		30.00	5.40	5.50		163.50		
Ch:60-90	1		30.00	5.50	5.20		160.50		
Ch:90-120	1		30.00	5.20	5.40		159.00		
Ch:120-150	1		30.00	5.40	5.60		165.00		
Ch:150-180	1		30.00	5.60	5.40		165.00		
Ch:180-210	1		30.00	5.40	5.50		163.50		
Ch:210-240	1		30.00	5.50	5.50		165.00		
Ch:240-270	1		30.00	5.50	5.20		160.50		
Ch:270-280	1		10.00	5.20	5.40		53.00		
Ch:00-280(2nd Main)									
Ch:00-30	1		30.00	5.00	5.00		150.00		
Ch:30-60	1		30.00	5.00	4.80		147.00		
Ch:60-90	1		30.00	4.80	5.20		150.00		
Ch:90-120	1		30.00	5.20	4.60		147.00		
Ch:120-150	1		30.00	4.60	5.00		144.00		
Ch:150-180	1		30.00	5.00	4.80		147.00		
Ch:180-210	1		30.00	4.80	5.20		150.00		
Ch:210-240	1		30.00	5.20	4.80		150.00		
Ch:240-270	1		30.00	4.80	5.20		150.00		
Ch:270-280	1		10.00	5.20	5.00		51.00		
Ch:00-270(1st B Main)									
Ch:00-30	1		30.00	5.20	5.20		156.00		
Ch:30-60	1		30.00	5.20	5.20		156.00		
Ch:60-90	1		30.00	5.20	5.20		156.00		
Ch:90-120	1		30.00	5.20	5.20		156.00		
Ch:120-150	1		30.00	5.20	5.20		156.00		
Ch:150-180	1		30.00	5.20	5.30		157.50		
Ch:180-210	1		30.00	5.30	5.30		159.00		
Ch:210-240	1		30.00	5.30	5.30		159.00		
Ch:240-270	1		30.00	5.30	5.30		159.00		
Ch:00-280(1st C Main)									
Ch:00-30	1		30.00	5.50	5.50		165.00		
Ch:30-60	1		30.00	5.50	5.50		165.00		
Ch:60-90	1		30.00	5.50	5.50		165.00		
Ch:90-120	1		30.00	5.50	5.50		165.00		
Ch:120-150	1		30.00	5.50	5.50		165.00		
Ch:150-180	1		30.00	5.50	5.50		165.00		
Ch:180-210	1		30.00	5.50	5.40		163.50		
Ch:210-240	1		30.00	5.40	5.40		162.00		
Ch:240-270	1		30.00	5.40	5.40		162.00		
Ch:270-280	1		10.00	5.40	5.40		54.00		
Ch:00-95(14th Cross Road)									
Ch:00-30	1		30.00	5.00	4.80		147.00		
Ch:30-60	1		30.00	4.80	5.00		147.00		
Ch:60-95	1		35.00	5.00	5.20		178.50		
Ch:00-110(12th Cross Road)									
Ch:00-30	1		30.00	5.00	4.80		147.00		
Ch:30-60	1		30.00	4.80	5.20		150.00		
Ch:60-90	1		30.00	5.20	4.80		150.00		
Ch:90-110	1		20.00	4.80	4.90		97.00		
Ch:00-140(10th Cross Road)									

Ch:00-30	1		30.00	4.50	4.40		133.50		
Ch:30-60	1		30.00	4.40	4.50		133.50		
Ch:60-90	1		30.00	4.50	4.00		127.50		
Ch:90-120	1		30.00	4.00	4.20		123.00		
Ch:120-140	1		20.00	4.20	4.40		86.00		
Ch:00-90(9th Cross Road)									
Ch:00-30	1		30.00	4.50	4.40		133.50		
Ch:30-60	1		30.00	4.40	4.50		133.50		
Ch:60-96	1		36.00	4.50	4.40		160.20		
Ch:00-62(8th Cross Road)									
Ch:00-30	1		30.00	4.50	4.40		133.50		
Ch:30-62	1		32.00	4.40	4.50		142.40		
Ch:00-105(7th Cross Road)									
Ch:00-30	1		30.00	4.50	4.40		133.50		
Ch:30-60	1		30.00	4.40	4.50		133.50		
Ch:60-90	1		30.00	4.50	4.00		127.50		
Ch:90-105	1		15.00	4.00	4.20		61.50		
Ch:00-65(6th Cross Road)									
Ch:00-30	1		30.00	4.50	4.40		133.50		
Ch:30-65	1		35.00	4.40	4.50		155.75		
Ch:00-64(5th Cross Road)									
Ch:00-30	1		30.00	4.50	4.40		133.50		
Ch:30-64	1		34.00	4.40	4.50		151.30		
Ch:00-63(4th Cross Road)									
Ch:00-30	1		30.00	4.50	4.40		133.50		
Ch:30-63	1		33.00	4.40	4.50		146.85		
Ch:00-65(3rd Cross Road)									
Ch:00-30	1		30.00	4.50	4.40		133.50		
Ch:30-65	1		35.00	4.40	4.50		155.75		
Ch:00-66(2nd Cross Road)									
Ch:00-30	1		30.00	4.50	4.40		133.50		
Ch:30-66	1		36.00	4.40	4.50		160.20		
Ch:00-80(1st Cross Road)									
Ch:00-30	1		30.00	4.50	4.50		135.00		
Ch:30-60	1		30.00	4.50	4.40		133.50		
Ch:60-80	1		20.00	4.40	4.50		89.00		
Soundarya layout 2nd Main									
Ch:00-530(2nd Main Road)									
Ch:00-30	1		30.00	8.00	7.50		232.50		
Ch:30-60	1		30.00	7.50	7.80		229.50		
Ch:60-90	1		30.00	7.80	7.90		235.50		
Ch:90-120	1		30.00	7.90	7.70		234.00		
Ch:120-150	1		30.00	7.70	8.00		235.50		
Ch:150-180	1		30.00	8.00	8.20		243.00		
Ch:180-210	1		30.00	8.20	8.00		243.00		
Ch:210-240	1		30.00	8.00	7.90		238.50		
Ch:240-270	1		30.00	7.90	7.80		235.50		
Ch:270-300	1		30.00	7.80	8.20		240.00		
Ch:300-330	1		30.00	8.20	8.00		243.00		
Ch:330-360	1		30.00	8.00	7.90		238.50		
Ch:360-390	1		30.00	7.90	7.80		235.50		
Ch:390-420	1		30.00	7.80	8.00		237.00		
Ch:420-450	1		30.00	8.00	8.00		240.00		
Ch:450-480	1		30.00	8.00	8.00		240.00		
Ch:480-510	1		30.00	8.00	8.00		240.00		
Ch:510-530	1		20.00	8.00	8.00		160.00		
Ch00-95(11th Cross Road)									
Ch:00-30	1		30.00	5.00	4.80		147.00		
Ch:30-60	1		30.00	4.80	5.20		150.00		
Ch:60-95	1		35.00	5.20	4.80		175.00		
Ch:00-85(10th Cross Road)									
Ch:00-30	1		30.00	5.00	4.80		147.00		
Ch:30-60	1		30.00	4.80	5.20		150.00		
Ch:60-85	1		25.00	5.20	4.80		125.00		
Ch:00-75(9th Cross Road)									
Ch:00-30	1		30.00	5.00	4.80		147.00		
Ch:30-60	1		30.00	4.80	5.20		150.00		
Ch:60-75	1		15.00	5.20	4.80		75.00		
Ch:00-68(8th Cross Road)									
Ch:00-30	1		30.00	5.00	4.80		147.00		

Ch:30-68		1		38.00	4.80	5.20		190.00		
Ch:00-50(7th Cross Road)										
Ch:00-30		1		30.00	5.00	4.80		147.00		
Ch:30-50		1		20.00	4.80	5.20		100.00		
Ch:00-43(6th Cross Road)										
Ch:00-30		1		30.00	5.00	4.80		147.00		
Ch:30-43		1		13.00	4.80	5.20		65.00		
Ch:00-60(4th Cross Road)										
Ch:00-30	Sqm	1		30.00	5.00	4.80		147.00		
Ch:30-60		1		30.00	4.80	5.20		150.00		
Ch:00-152(3rd Cross Road)										
Ch:00-30		1		30.00	5.00	4.80		147.00		
Ch:30-60		1		30.00	4.80	5.20		150.00		
Ch:60-90		1		30.00	5.20	4.80		150.00		
Ch:90-120		1		30.00	4.80	5.20		150.00		
Ch:120-152		1		32.00	5.20	5.00		163.20		
Ch:00-100 (Cross Road)										
Ch:00-30		1		30.00	5.00	4.80		147.00		
Ch:30-60		1		30.00	4.80	5.20		150.00		
Ch:60-90		1		30.00	5.20	4.80		150.00		
Ch:90-100		1		10.00	4.80	5.20		50.00		
Ch:00-225 (Cross Road)										
Ch:00-30		1		30.00	5.50	5.40		163.50		
Ch:30-60		1		30.00	5.40	5.50		163.50		
Ch:60-90		1		30.00	5.50	5.20		160.50		
Ch:90-120		1		30.00	5.20	5.40		159.00		
Ch:120-150		1		30.00	5.40	5.40		162.00		
Ch:150-180		1		30.00	5.40	5.50		163.50		
Ch:180-210		1		30.00	5.50	5.20		160.50		
Ch:210-225		1		15.00	5.20	5.40		79.50		
Ch:00-125(3rd Main Road)										
Ch:00-30		1		30.00	5.00	4.80		147.00		
Ch:30-60		1		30.00	4.80	5.20		150.00		
Ch:60-90		1		30.00	5.20	4.80		150.00		
Ch:90-125		1		35.00	4.80	5.20		175.00		
Ch:00-230(3rd Main Road)										
Ch:00-30		1		30.00	5.00	4.80		147.00		
Ch:30-60		1		30.00	4.80	5.20		150.00		
Ch:60-90		1		30.00	5.20	4.80		150.00		
Ch:90-120		1		30.00	4.80	5.20		150.00		
Ch:120-150		1		30.00	5.20	4.80		150.00		
Ch:150-180		1		30.00	4.80	5.20		150.00		
Ch:180-210		1		30.00	5.20	4.80		150.00		
Ch:210-230		1		20.00	4.80	5.20		100.00		
Soundarya layout 1st Main										
Ch:00-530(1st Main)										
Ch:00-30		1		30.00	7.00	6.80		207.00		
Ch:30-60		1		30.00	6.80	7.00		207.00		
Ch:60-90		1		30.00	7.00	6.90		208.50		
Ch:90-120		1		30.00	6.90	6.80		205.50		
Ch:120-150		1		30.00	6.80	6.50		199.50		
Ch:150-180		1		30.00	6.50	6.80		199.50		
Ch:180-210		1		30.00	6.80	7.20		210.00		
Ch:210-240		1		30.00	7.20	7.00		213.00		
Ch:240-270		1		30.00	7.00	7.00		210.00		
Ch:270-300		1		30.00	7.00	6.90		208.50		
Ch:300-330		1		30.00	6.90	6.80		205.50		
Ch:330-360		1		30.00	6.80	7.10		208.50		
Ch:360-390		1		30.00	7.10	7.00		211.50		
Ch:390-420		1		30.00	7.00	6.80		207.00		
Ch:420-450		1		30.00	6.80	6.90		205.50		
Ch:450-480		1		30.00	6.90	7.10		210.00		
Ch:480-510		1		30.00	7.10	7.00		211.50		
Ch:510-530		1		20.00	7.00	7.00		140.00		
Ch:00-90(1st A Cross Road)										
Ch:00-30		1		30.00	5.00	4.80		147.00		
Ch:30-60		1		30.00	4.80	5.20		150.00		
Ch:60-90		1		30.00	5.20	4.80		150.00		
Ch:00-100(2nd A Cross Road)										
Ch:00-30		1		30.00	5.00	4.80		147.00		

E N FOR 1SQM AREA

Ch:30-60	1		30.00	4.80	5.20		150.00	
Ch:60-90	1		30.00	5.20	4.80		150.00	
Ch:90-100	1		10.00	4.80	4.90		48.50	
Ch:00-90(4th A Cross Road)								
Ch:00-30	1		30.00	5.00	4.80		147.00	
Ch:30-60	1		30.00	4.80	5.20		150.00	
Ch:60-90	1		30.00	5.20	4.80		150.00	
Ch:00-90(6th A Cross Road)								
Ch:00-30	1		30.00	5.00	4.80		147.00	
Ch:30-60	1		30.00	4.80	5.20		150.00	
Ch:60-90	1		30.00	5.20	4.80		150.00	
Ch:00-90(7th A Cross Road)								
Ch:00-30	1		30.00	5.00	4.90		148.50	
Ch:30-60	1		30.00	4.90	5.20		151.50	
Ch:60-90	1		30.00	5.20	4.80		150.00	
Ch:00-93(8th A Cross Road)								
Ch:00-30	1		30.00	5.00	4.80		147.00	
Ch:30-60	1		30.00	4.80	5.20		150.00	
Ch:60-93	1		33.00	5.20	4.80		165.00	
Ch:00-92(9th A Cross Road)								
Ch:00-30	1		30.00	5.00	4.90		148.50	
Ch:30-60	1		30.00	4.90	5.20		151.50	
Ch:60-92	1		32.00	5.20	4.80		160.00	
Ch:00-90(11th A Cross Road)								
Ch:00-30	1		30.00	5.00	4.80		147.00	
Ch:30-60	1		30.00	4.80	5.20		150.00	
Ch:60-90	1		30.00	5.20	4.80		150.00	
Ch:00-93(12th A Cross Road)								
Ch:00-30	1		30.00	5.00	4.80		147.00	
Ch:30-60	1		30.00	4.80	5.20		150.00	
Ch:60-93	1		33.00	5.20	4.80		165.00	
Ch:00-92(13th A Cross Road)								
Ch:00-30	1		30.00	5.00	4.80		147.00	
Ch:30-60	1		30.00	4.80	5.20		150.00	
Ch:60-92	1		32.00	5.20	4.80		160.00	
Ch:00-92(14th A Cross Road)								
Ch:00-30	1		30.00	5.00	4.80		147.00	
Ch:30-60	1		30.00	4.80	5.20		150.00	
Ch:60-92	1		32.00	5.20	4.80		160.00	
Ch:00-92(14th A Cross Road)								
Ch:00-30	1		30.00	5.00	5.10		151.50	
Ch:30-60	1		30.00	5.10	5.20		154.50	
Ch:60-92	1		32.00	5.20	5.10		164.80	
Siddeshwara Layout								
Ch:00-950								
Ch:00-30	1		30.00	5.50	5.40		163.50	
Ch:30-60	1		30.00	5.40	5.50		163.50	
Ch:60-90	1		30.00	5.50	5.20		160.50	
Ch:90-120	1		30.00	5.20	5.40		159.00	
Ch:120-150	1		30.00	5.40	5.40		162.00	
Ch:150-180	1		30.00	5.40	5.50		163.50	
Ch:180-210	1		30.00	5.50	5.20		160.50	
Ch:210-240	1		30.00	5.20	5.40		159.00	
Ch:240-270	1		30.00	5.40	5.40		162.00	
Ch:270-300	1		30.00	5.40	5.50		163.50	
Ch:300-330	1		30.00	5.50	5.20		160.50	
Ch:330-360	1		30.00	5.20	5.40		159.00	
Ch:360-390	1		30.00	5.40	5.40		162.00	
Ch:390-420	1		30.00	5.40	5.50		163.50	
Ch:420-450	1		30.00	5.50	5.20		160.50	
Ch:450-480	1		30.00	5.20	5.40		159.00	
Ch:480-510	1		30.00	5.40	5.40		162.00	
Ch:510-540	1		30.00	5.40	5.50		163.50	
Ch:540-570	1		30.00	5.50	5.20		160.50	
Ch:570-600	1		30.00	5.20	5.40		159.00	
Ch:600-630	1		30.00	5.40	5.40		162.00	
Ch:630-660	1		30.00	5.40	5.50		163.50	
Ch:660-690	1		30.00	5.50	5.20		160.50	
Ch:690-720	1		30.00	5.20	5.40		159.00	
Ch:720-750	1		30.00	5.40	5.40		162.00	

Ch:750-780	1		30.00	5.40	5.50		163.50		
Ch:780-810	1		30.00	5.50	5.20		160.50		
Ch:810-840	1		30.00	5.20	5.40		159.00		
Ch:840-870	1		30.00	5.40	5.40		162.00		
Ch:870-900	1		30.00	5.40	5.50		163.50		
Ch:900-930	1		30.00	5.50	5.20		160.50		
Ch:930-950	1		20.00	5.20	5.40		106.00		
Ch:00-100 NMH Public school road									
Ch:00-30	1		30.00	5.00	4.80		147.00		
Ch:30-60	1		30.00	4.80	5.20		150.00		
Ch:60-90	1		30.00	5.20	4.80		150.00		
Ch:90-100	1		10.00	4.80	5.00		49.00		
Ch:00-145 8th cross									
Ch:00-30	1		30.00	5.20	5.20		156.00		
Ch:30-60	1		30.00	5.20	5.20		156.00		
Ch:60-90	1		30.00	5.20	5.20		156.00		
Ch:90-120	1		30.00	5.20	5.30		157.50		
Ch:120-145	1		25.00	5.30	5.30		132.50		
Royal Enclave Layout									
Ch:00-80 Cross rd beside NMH Convention Hall									
Ch:00-30	1		30.00	4.50	4.40		133.50		
Ch:30-60	1		30.00	4.40	4.50		133.50		
Ch:60-80	1		20.00	4.50	4.40		89.00		
Ch:00-230 Siddeshwara Temple Road									
Ch:00-30	1		30.00	6.00	5.80		177.00		
Ch:30-60	1		30.00	5.80	5.90		175.50		
Ch:60-90	1		30.00	5.90	6.10		180.00		
Ch:90-120	1		30.00	6.10	5.70		177.00		
Ch:120-150	1		30.00	5.70	5.90		174.00		
Ch:150-180	1		30.00	5.90	5.50		171.00		
Ch:180-210	1		30.00	5.50	6.00		172.50		
Ch:210-230	1		20.00	6.00	5.80		118.00		
Ch:00-70 1st cross									
Ch:00-30	1		30.00	4.50	4.40		133.50		
Ch:30-60	1		30.00	4.40	4.50		133.50		
Ch:60-70	1		10.00	4.50	4.40		44.50		
Ch:00-85 2nd Cross									
Ch:00-30	1		30.00	4.50	4.40		133.50		
Ch:30-60	1		30.00	4.40	4.50		133.50		
Ch:60-85	1		25.00	4.50	4.40		111.25		
Ch:00-80 3rd Cross									
Ch:00-30	1		30.00	4.50	4.40		133.50		
Ch:30-60	1		30.00	4.40	4.50		133.50		
Ch:60-80	1		20.00	4.50	4.40		89.00		
Ch:00-80 4rd Cross									
Ch:00-30	1		30.00	4.50	4.40		133.50		
Ch:30-60	1		30.00	4.40	4.50		133.50		
Ch:60-80	1		20.00	4.50	4.40		89.00		
NMH Layout									
Ch:00-220 Basava Dhyana Kendra									
Ch:00-30	1		30.00	4.30	4.30		129.00		
Ch:30-60	1		30.00	4.30	4.30		129.00		
Ch:60-90	1		30.00	4.30	4.30		129.00		
Ch:90-120	1		30.00	4.30	4.40		130.50		
Ch:120-150	1		30.00	4.40	4.40		132.00		
Ch:150-180	1		30.00	4.40	4.50		133.50		
Ch:180-210	1		30.00	4.50	4.50		135.00		
Ch:210-220	1		10.00	4.50	4.40		44.50		
Ch:00-180 BESCOM Bagalugunte									
Ch:00-30	1		30.00	5.30	5.30		159.00		
Ch:30-60	1		30.00	5.30	5.30		159.00		
Ch:60-90	1		30.00	5.30	5.40		160.50		
Ch:90-120	1		30.00	5.40	5.40		162.00		
Ch:120-150	1		30.00	5.40	5.50		163.50		
Ch:150-180	1		30.00	5.50	5.50		165.00		
Ch:00-230 1st main									
Ch:00-30	1		30.00	4.80	4.80		144.00		
Ch:30-60	1		30.00	4.80	4.80		144.00		
Ch:60-90	1		30.00	4.80	4.90		145.50		

	Ch:90-120								
	Ch:120-150								
	Ch:150-180								
	Ch:180-210								
	Ch:210-230								
	Ch:00-140 2nd main								
	Ch:00-30		1		30.00	4.90	4.90		147.00
	Ch:30-60		1		30.00	4.90	4.90		147.00
	Ch:60-90		1		30.00	4.90	4.90		147.00
	Ch:90-120		1		30.00	4.90	4.90		147.00
	Ch:120-140		1		20.00	4.90	4.90		98.00
	Kirloskar connecting road								
	Ch:00-370 4nd main								
	Ch:00-30		1		30.00	4.90	4.90		147.00
	Ch:30-60		1		30.00	4.90	4.90		147.00
	Ch:60-90		1		30.00	4.90	5.00		148.50
	Ch:90-120		1		30.00	5.00	5.00		150.00
	Ch:120-150		1		30.00	5.80	5.80		174.00
	Ch:150-180		1		30.00	5.80	5.80		174.00
	Ch:180-210		1		30.00	5.80	5.80		174.00
	Ch:210-240		1		30.00	5.80	5.80		174.00
	Ch:240-270		1		30.00	5.80	5.80		174.00
	Ch:270-300		1		30.00	5.80	5.80		174.00
	Ch:300-330		1		30.00	5.80	5.80		174.00
	Ch:330-360		1		30.00	5.80	5.70		172.50
	Ch:360-370		1		30.00	5.70	5.70		171.00
			1		30.00	5.70	5.70		171.00
			1		30.00	5.70	5.70		171.00
			1		10.00	5.70	5.70		57.00
								Total Qty	57240.35

21	KSRRB M500-17. Providing and laying dense graded bituminous macadam using crushed aggregates of specified grading; premixed with VG30 grade bituminous binder and, transporting the hot mix to work site, laying to the required grade, level and ialignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction in all respects complete as per specifications. Clause 505 of MORTH V revision do - using 40/60 TPH capacity H.M.P. with Mechanical paver Gr-II (50 mm to 75 mm) with 4.5 % VG-30 Bitumen							29.68	16,98,893.59
	KPWD Issue S.R 2020-21	It. No.		21.17.2	Pg.No.		160		
	Byraveshwara circle								
	Ch:00-310 (Naga Devaata Temple Road)								
	Ch:00-30		1		30.00	6.50	6.50	0.05	9.75
	Ch:30-60		1		30.00	6.50	6.60	0.05	9.83
	Ch:60-90		1		30.00	6.60	6.40	0.05	9.75
	Ch:90-120		1		30.00	6.40	6.50	0.05	9.68
	Ch:120-150		1		30.00	6.50	6.40	0.05	9.68
	Ch:150-180		1		30.00	6.40	6.40	0.05	9.60
	Ch:180-210		1		30.00	6.40	6.50	0.05	9.68
	Ch:210-240		1		30.00	6.50	6.30	0.05	9.60
	Ch:240-270		1		30.00	6.30	6.50	0.05	9.60
	Ch:270-300		1		30.00	6.50	6.50	0.05	9.75
	Ch:300-310		1		10.00	6.50	6.50	0.05	3.25
	Ch:00-215 (From Byraveshwara Circle)								
	Ch:00-30		1		30.00	7.00	7.00	0.05	10.50
	Ch:30-60		1		30.00	6.80	7.20	0.05	10.50
	Ch:60-90		1		30.00	7.20	7.00	0.05	10.65
	Ch:90-120		1		30.00	7.00	6.80	0.05	10.35
	Ch:120-150		1		30.00	6.80	6.60	0.05	10.05
	Ch:150-180		1		30.00	6.60	6.80	0.05	10.05
	Ch:180-215		1		35.00	6.80	7.20	0.05	12.25
	Ch:00-110 1st Cross								
	Ch:00-30		1		30.00	4.50	4.50	0.05	6.75
	Ch:30-60		1		30.00	4.50	4.30	0.05	6.60
	Ch:60-90		1		30.00	4.30	4.40	0.05	6.53
	Ch:90-110		1		20.00	4.40	4.60	0.05	4.50
	Ch:00-112 2nd Cross								
	Ch:00-30		1		30.00	5.00	5.00	0.05	7.50
	Ch:30-60		1		30.00	4.80	4.90	0.05	7.28
	Ch:60-90		1		30.00	4.90	5.10	0.05	7.50
	Ch:90-112		1		22.00	5.10	4.90	0.05	5.50
	Ch:00-110-3rd Cross								
	Ch:00-30		1		30.00	4.00	4.00	0.05	6.00
	Ch:30-60		1		30.00	3.90	4.00	0.05	5.93
	Ch:60-90		1		30.00	4.00	3.80	0.05	5.85
	Ch:90-110		1		20.00	3.80	3.80	0.05	3.80

Ch:00-88 4th Cross								
Ch:00-30	1		30.00	4.50	4.40	0.05	6.68	
Ch:30-60	1		30.00	4.40	4.60	0.05	6.75	
Ch:60-88	1		28.00	4.60	4.30	0.05	6.23	
Ch:00-82 5th Cross								
Ch:00-30	1		30.00	4.00	3.80	0.05	5.85	
Ch:30-60	1		30.00	3.80	4.00	0.05	5.85	
Ch:60-82	1		22.00	4.00	3.80	0.05	4.29	
M.H.R. Layout								
Ch:00-490(Chetana E lavada school Frant Rd to Siddhi Vinayaka Temple)								
Ch:00-30	1		30.00	5.30	5.10	0.05	7.80	
Ch:30-60	1		30.00	5.10	5.40	0.05	7.88	
Ch:60-90	1		30.00	5.40	5.50	0.05	8.18	
Ch:90-120	1		30.00	5.50	5.50	0.05	8.25	
Ch:120-150	1		30.00	5.50	5.00	0.05	7.88	
Ch:150-180	1		30.00	5.00	5.00	0.05	7.50	
Ch:180-210	1		30.00	5.20	5.50	0.05	8.03	
Ch:210-240	1		30.00	5.50	5.20	0.05	8.03	
Ch:240-270	1		30.00	5.20	5.00	0.05	7.65	
Ch:270-300	1		30.00	5.00	5.00	0.05	7.50	
Ch:300-330	1		30.00	5.20	5.20	0.05	7.80	
Ch:330-360	1		30.00	5.20	5.20	0.05	7.80	
Ch:360-390	1		30.00	5.20	5.50	0.05	8.03	
Ch:390-420	1		30.00	5.50	5.20	0.05	8.03	
Ch:420-450	1		30.00	5.20	5.00	0.05	7.65	
Ch:450-480	1		30.00	5.00	5.00	0.05	7.50	
Ch:480-490	1		10.00	5.00	5.00	0.05	2.50	
Ch:00-110 (4th Cross Road)								
Ch:00-30	1		30.00	4.10	3.90	0.05	6.00	
Ch:30-60	1		30.00	3.90	4.00	0.05	5.93	
Ch:60-90	1		30.00	4.00	3.90	0.05	5.93	
Ch:90-110	1		20.00	3.90	4.20	0.05	4.05	
Ch:00-80 (5th Cross Road)								
Ch:00-30	1		30.00	4.00	4.00	0.05	6.00	
Ch:30-60	1		30.00	3.80	4.20	0.05	6.00	
Ch:60-80	1		20.00	4.20	3.90	0.05	4.05	
Ch:00-75 (6th Cross Road)								
Ch:00-30	1		30.00	6.00	5.80	0.05	8.85	
Ch:30-60	1		30.00	5.80	5.90	0.05	8.78	
Ch:60-75	1		15.00	5.90	6.10	0.05	4.50	
Ch:00-110 (7th Cross Road)								
Ch:00-30	1		30.00	5.00	4.80	0.05	7.35	
Ch:30-60	1		30.00	4.80	5.20	0.05	7.50	
Ch:60-90	1		30.00	5.20	5.00	0.05	7.65	
Ch:90-110	1		20.00	5.00	5.00	0.05	5.00	
Ch:00-115 (8th Cross Road)								
Ch:00-30	1		30.00	4.90	4.80	0.05	7.28	
Ch:30-60	1		30.00	4.80	4.90	0.05	7.28	
Ch:60-90	1		30.00	4.90	5.00	0.05	7.43	
Ch:90-115	1		25.00	5.00	4.90	0.05	6.19	
Ch:00-210(1st Main)								
Ch:00-30	1		30.00	4.50	4.50	0.05	6.75	
Ch:30-60	1		30.00	4.50	4.50	0.05	6.75	
Ch:60-90	1		30.00	4.50	4.50	0.05	6.75	
Ch:90-120	1		30.00	4.50	4.50	0.05	6.75	
Ch:120-150	1		30.00	4.50	4.60	0.05	6.83	
Ch:150-180	1		30.00	4.60	4.60	0.05	6.90	
Ch:180-210	1		30.00	4.60	4.60	0.05	6.90	
MEENAKSHI layout								
Ch:00-280(1st Main)								
Ch:00-30	1		30.00	5.50	5.40	0.05	8.18	
Ch:30-60	1		30.00	5.40	5.50	0.05	8.18	
Ch:60-90	1		30.00	5.50	5.20	0.05	8.03	
Ch:90-120	1		30.00	5.20	5.40	0.05	7.95	
Ch:120-150	1		30.00	5.40	5.60	0.05	8.25	
Ch:150-180	1		30.00	5.60	5.40	0.05	8.25	
Ch:180-210	1		30.00	5.40	5.50	0.05	8.18	
Ch:210-240	1		30.00	5.50	5.50	0.05	8.25	
Ch:240-270	1		30.00	5.50	5.20	0.05	8.03	

Comprehensive development of bad roads and improvements to road side drain, footpaths, Asphalting and concreting including culvert selected main and other connecting roads of package No.1 in ward No.14, Rajagopala st Dasarahalli Division

Ch:270-280	1		10.00	5.20	5.40	0.05	2.65	
Ch:00-280(2nd Main)								
Ch:00-30	1		30.00	5.00	5.00	0.05	7.50	
Ch:30-60	1		30.00	5.00	4.80	0.05	7.35	
Ch:60-90	1		30.00	4.80	5.20	0.05	7.50	
Ch:90-120	1		30.00	5.20	4.60	0.05	7.35	
Ch:120-150	1		30.00	4.60	5.00	0.05	7.20	
Ch:150-180	1		30.00	5.00	4.80	0.05	7.35	
Ch:180-210	1		30.00	4.80	5.20	0.05	7.50	
Ch:210-240	1		30.00	5.20	4.80	0.05	7.50	
Ch:240-270	1		30.00	4.80	5.20	0.05	7.50	
Ch:270-280	1		10.00	5.20	5.00	0.05	2.55	
Ch:00-270(1st B Main)								
Ch:00-30	1		30.00	5.20	5.20	0.05	7.80	
Ch:30-60	1		30.00	5.20	5.20	0.05	7.80	
Ch:60-90	1		30.00	5.20	5.20	0.05	7.80	
Ch:90-120	1		30.00	5.20	5.20	0.05	7.80	
Ch:120-150	1		30.00	5.20	5.20	0.05	7.80	
Ch:150-180	1		30.00	5.20	5.30	0.05	7.88	
Ch:180-210	1		30.00	5.30	5.30	0.05	7.95	
Ch:210-240	1		30.00	5.30	5.30	0.05	7.95	
Ch:240-270	1		30.00	5.30	5.30	0.05	7.95	
Ch:00-280(1st C Main)								
Ch:00-30	1		30.00	5.50	5.50	0.05	8.25	
Ch:30-60	1		30.00	5.50	5.50	0.05	8.25	
Ch:60-90	1		30.00	5.50	5.50	0.05	8.25	
Ch:90-120	1		30.00	5.50	5.50	0.05	8.25	
Ch:120-150	1		30.00	5.50	5.50	0.05	8.25	
Ch:150-180	1		30.00	5.50	5.50	0.05	8.25	
Ch:180-210	1		30.00	5.50	5.40	0.05	8.18	
Ch:210-240	1		30.00	5.40	5.40	0.05	8.10	
Ch:240-270	1		30.00	5.40	5.40	0.05	8.10	
Ch:270-280	1		10.00	5.40	5.40	0.05	2.70	
Ch:00-95(14th Cross Road)								
Ch:00-30	1		30.00	5.00	4.80	0.05	7.35	
Ch:30-60	1		30.00	4.80	5.00	0.05	7.35	
Ch:60-95	1		35.00	5.00	5.20	0.05	8.93	
Ch:00-110(12th Cross Road)								
Ch:00-30	1		30.00	5.00	4.80	0.05	7.35	
Ch:30-60	1		30.00	4.80	5.20	0.05	7.50	
Ch:60-90	1		30.00	5.20	4.80	0.05	7.50	
Ch:90-110	1		20.00	4.80	4.90	0.05	4.85	
Ch:00-140(10th Cross Road)								
Ch:00-30	1		30.00	4.50	4.40	0.05	6.68	
Ch:30-60	1		30.00	4.40	4.50	0.05	6.68	
Ch:60-90	1		30.00	4.50	4.00	0.05	6.38	
Ch:90-120	1		30.00	4.00	4.20	0.05	6.15	
Ch:120-140	1		20.00	4.20	4.40	0.05	4.30	
Ch:00-96(9th Cross Road)								
Ch:00-30	1		30.00	4.50	4.40	0.05	6.68	
Ch:30-60	1		30.00	4.40	4.50	0.05	6.68	
Ch:60-96	1		36.00	4.50	4.40	0.05	8.01	
Ch:00-62(8th Cross Road)								
Ch:00-30	1		30.00	4.50	4.40	0.05	6.68	
Ch:30-62	1		32.00	4.40	4.50	0.05	7.12	
Ch:00-105(7th Cross Road)								
Ch:00-30	1		30.00	4.50	4.40	0.05	6.68	
Ch:30-60	1		30.00	4.40	4.50	0.05	6.68	
Ch:60-90	1		30.00	4.50	4.00	0.05	6.38	
Ch:90-105	1		15.00	4.00	4.20	0.05	3.08	
Ch:00-65(6th Cross Road)								
Ch:00-30	1		30.00	4.50	4.40	0.05	6.68	
Ch:30-65	1		35.00	4.40	4.50	0.05	7.79	
Ch:00-64(5th Cross Road)								
Ch:00-30	1		30.00	4.50	4.40	0.05	6.68	
Ch:30-64	1		34.00	4.40	4.50	0.05	7.57	
Ch:00-63(4th Cross Road)								
Ch:00-30	1		30.00	4.50	4.40	0.05	6.68	
Ch:30-63	1		33.00	4.40	4.50	0.05	7.34	
Ch:00-65(3rd Cross Road)								

Ch:00-30	1		30.00	4.50	4.40	0.05	6.68	
Ch:30-65	1		35.00	4.40	4.50	0.05	7.79	
Ch:00-66(2nd Cross Road)								
Ch:00-30	1		30.00	4.50	4.40	0.05	6.68	
Ch:30-66	1		36.00	4.40	4.50	0.05	8.01	
Ch:00-80(1st Cross Road)								
Ch:00-30	1		30.00	4.50	4.50	0.05	6.75	
Ch:30-60	1		30.00	4.50	4.40	0.05	6.68	
Ch:60-80	1		20.00	4.40	4.50	0.05	4.45	
Soundarya layout 2nd Main								
Ch:00-530(2nd Main Road)								
Ch:00-30	1		30.00	8.00	7.50	0.05	11.63	
Ch:30-60	1		30.00	7.50	7.80	0.05	11.48	
Ch:60-90	1		30.00	7.80	7.90	0.05	11.78	
Ch:90-120	1		30.00	7.90	7.70	0.05	11.70	
Ch:120-150	1		30.00	7.70	8.00	0.05	11.78	
Ch:150-180	1		30.00	8.00	8.20	0.05	12.15	
Ch:180-210	1		30.00	8.20	8.00	0.05	12.15	
Ch:210-240	1		30.00	8.00	7.90	0.05	11.93	
Ch:240-270	1		30.00	7.90	7.80	0.05	11.78	
Ch:270-300	1		30.00	7.80	8.20	0.05	12.00	
Ch:300-330	1		30.00	8.20	8.00	0.05	12.15	
Ch:330-360	1		30.00	8.00	7.90	0.05	11.93	
Ch:360-390	1		30.00	7.90	7.80	0.05	11.78	
Ch:390-420	1		30.00	7.80	8.00	0.05	11.85	
Ch:420-450	1		30.00	8.00	8.20	0.05	12.15	
Ch:450-480	1		30.00	8.20	8.00	0.05	12.15	
Ch:480-510	1		30.00	8.00	8.00	0.05	12.00	
Ch:510-530	1		20.00	8.00	8.00	0.05	8.00	
Ch00-95(11th Cross Road)								
Ch:00-30	1		30.00	5.00	4.80	0.05	7.35	
Ch:30-60	1		30.00	4.80	5.20	0.05	7.50	
Ch:60-95	1		35.00	5.20	4.80	0.05	8.75	
Ch:00-85(10th Cross Road)								
Ch:00-30	1		30.00	5.00	4.80	0.05	7.35	
Ch:30-60	1		30.00	4.80	5.20	0.05	7.50	
Ch:60-85	1		25.00	5.20	4.80	0.05	6.25	
Ch:00-75(9th Cross Road)								
Ch:00-30	1		30.00	5.00	4.80	0.05	7.35	
Ch:30-60	1		30.00	4.80	5.20	0.05	7.50	
Ch:60-75	1		15.00	5.20	4.80	0.05	3.75	
Ch:00-68(8th Cross Road)								
Ch:00-30	1		30.00	5.00	4.80	0.05	7.35	
Ch:30-68	1		38.00	4.80	5.20	0.05	9.50	
Ch:00-50(7th Cross Road)								
Ch:00-30	1		30.00	5.00	4.80	0.05	7.35	
Ch:30-50	1		20.00	4.80	5.20	0.05	5.00	
Ch:00-43(6th Cross Road)								
Ch:00-30	1		30.00	5.00	4.80	0.05	7.35	
Ch:30-43	1		13.00	4.80	5.20	0.05	3.25	
Ch:00-60(4th Cross Road)								
Ch:00-30	1		30.00	5.00	4.80	0.05	7.35	
Ch:30-60	1		30.00	4.80	5.20	0.05	7.50	
Ch:00-152(3rd Cross Road)								
Ch:00-30	1		30.00	5.00	4.80	0.05	7.35	
Ch:30-60	1		30.00	4.80	5.20	0.05	7.50	
Ch:60-90	1		30.00	5.20	4.80	0.05	7.50	
Ch:90-120	1		30.00	4.80	5.20	0.05	7.50	
Ch:120-152	1		32.00	5.20	5.00	0.05	8.16	
Ch:00-100 (Cross Road)								
Ch:00-30	1		30.00	5.00	4.80	0.05	7.35	
Ch:30-60	1		30.00	4.80	5.20	0.05	7.50	
Ch:60-90	1		30.00	5.20	4.80	0.05	7.50	
Ch:90-100	1		10.00	4.80	5.20	0.05	2.50	
Ch:00-225 (Cross Road)								
Ch:00-30	1		30.00	5.50	5.40	0.05	8.18	
Ch:30-60	1		30.00	5.40	5.50	0.05	8.18	
Ch:60-90	1		30.00	5.50	5.20	0.05	8.03	
Ch:90-120	1		30.00	5.20	5.40	0.05	7.95	
Ch:120-150	1		30.00	5.40	5.40	0.05	8.10	

Cum

Ch:150-180								
Ch:180-210	1		30.00	5.40	5.50	0.05	8.18	
Ch:210-225	1		30.00	5.50	5.20	0.05	8.03	
Ch:00-125(3rd Main Road)	1		15.00	5.20	5.40	0.05	3.98	
Ch:00-30								
Ch:30-60	1		30.00	5.00	4.80	0.05	7.35	
Ch:60-90	1		30.00	4.80	5.20	0.05	7.50	
Ch:90-120	1		30.00	5.20	4.80	0.05	7.50	
Ch:00-230(3rd Main Road)	1		35.00	4.80	5.20	0.05	8.75	
Ch:00-30								
Ch:30-60	1		30.00	5.00	4.80	0.05	7.35	
Ch:60-90	1		30.00	4.80	5.20	0.05	7.50	
Ch:90-120	1		30.00	5.20	4.80	0.05	7.50	
Ch:120-150	1		30.00	4.80	5.20	0.05	7.50	
Ch:150-180	1		30.00	5.20	4.80	0.05	7.50	
Ch:180-210	1		30.00	4.80	5.20	0.05	7.50	
Ch:210-230	1		30.00	5.20	4.80	0.05	7.50	
Soundarya layout 1st Main	1		20.00	4.80	5.20	0.05	5.00	
Ch:00-530(1st Main)								
Ch:00-30								
Ch:30-60	1		30.00	7.00	6.80	0.05	10.35	
Ch:60-90	1		30.00	6.80	7.00	0.05	10.35	
Ch:90-120	1		30.00	7.00	6.90	0.05	10.43	
Ch:120-150	1		30.00	6.90	6.80	0.05	10.28	
Ch:150-180	1		30.00	6.80	6.50	0.05	9.98	
Ch:180-210	1		30.00	6.50	6.80	0.05	9.98	
Ch:210-240	1		30.00	6.80	7.20	0.05	10.50	
Ch:240-270	1		30.00	7.20	7.00	0.05	10.65	
Ch:270-300	1		30.00	7.00	7.00	0.05	10.50	
Ch:300-330	1		30.00	7.00	6.90	0.05	10.43	
Ch:330-360	1		30.00	6.90	6.80	0.05	10.28	
Ch:360-390	1		30.00	6.80	7.10	0.05	10.43	
Ch:390-420	1		30.00	7.10	7.00	0.05	10.58	
Ch:420-450	1		30.00	7.00	6.80	0.05	10.35	
Ch:450-480	1		30.00	6.80	6.90	0.05	10.28	
Ch:480-510	1		30.00	6.90	7.10	0.05	10.50	
Ch:510-530	1		30.00	7.10	7.00	0.05	10.58	
Ch:00-90(1st A Cross Road)	1		20.00	7.00	7.00	0.05	7.00	
Ch:00-30								
Ch:30-60	1		30.00	5.00	4.80	0.05	7.35	
Ch:60-90	1		30.00	4.80	5.20	0.05	7.50	
Ch:00-100(2nd A Cross Road)	1		30.00	5.20	4.80	0.05	7.50	
Ch:00-30								
Ch:30-60	1		30.00	5.00	4.80	0.05	7.35	
Ch:60-90	1		30.00	4.80	5.20	0.05	7.50	
Ch:90-100	1		30.00	5.20	4.80	0.05	7.50	
Ch:00-90(4th A Cross Road)	1		10.00	4.80	4.90	0.05	2.43	
Ch:00-30								
Ch:30-60	1		30.00	5.00	4.80	0.05	7.35	
Ch:60-90	1		30.00	4.80	5.20	0.05	7.50	
Ch:00-90(6th A Cross Road)	1		30.00	5.20	4.80	0.05	7.50	
Ch:00-30								
Ch:30-60	1		30.00	5.00	4.90	0.05	7.43	
Ch:60-90	1		30.00	4.90	5.20	0.05	7.58	
Ch:00-90(7th A Cross Road)	1		30.00	5.20	4.80	0.05	7.50	
Ch:00-30								
Ch:30-60	1		30.00	5.00	4.80	0.05	7.35	
Ch:60-90	1		30.00	4.80	5.20	0.05	7.50	
Ch:00-93(8th A Cross Road)	1		33.00	5.20	4.80	0.05	8.25	
Ch:00-30								
Ch:30-60	1		30.00	5.00	4.90	0.05	7.43	
Ch:60-93	1		30.00	4.90	5.20	0.05	7.58	
Ch:00-92(9th A Cross Road)	1		32.00	5.20	4.80	0.05	8.00	
Ch:00-30								
Ch:30-60	1		30.00	5.00	4.80	0.05	7.35	
Ch:60-92	1		30.00	4.80	5.20	0.05	7.50	
Ch:00-90(11th A Cross Road)	1		30.00	5.20	4.80	0.05	7.50	
Ch:00-30								
Ch:30-60								
Ch:60-90								

Ch:00-90(12th A Cross Road)								
Ch:00-30	1		30.00	5.00	4.80	0.05	7.35	
Ch:30-60	1		30.00	4.80	5.20	0.05	7.50	
Ch:60-90	1		33.00	5.20	4.80	0.05	8.25	
Ch:00-92(13th A Cross Road)								
Ch:00-30	1		30.00	5.00	4.80	0.05	7.35	
Ch:30-60	1		30.00	4.80	5.20	0.05	7.50	
Ch:60-92	1		32.00	5.20	4.80	0.05	8.00	
Ch:00-92(14th A Cross Road)								
Ch:00-30	1		30.00	5.00	4.80	0.05	7.35	
Ch:30-60	1		30.00	4.80	5.20	0.05	7.50	
Ch:60-92	1		32.00	5.20	4.80	0.05	8.00	
Ch:00-95(2nd B main Road)								
Ch:00-30	1		30.00	5.00	5.10	0.05	7.58	
Ch:30-60	1		30.00	5.10	5.20	0.05	7.73	
Ch:60-95	1		35.00	5.20	5.10	0.05	9.01	
Siddeshwara Layout								
Ch:00-950								
Ch:00-30	1		30.00	5.50	5.40	0.05	8.18	
Ch:30-60	1		30.00	5.40	5.50	0.05	8.18	
Ch:60-90	1		30.00	5.50	5.20	0.05	8.03	
Ch:90-120	1		30.00	5.20	5.40	0.05	7.95	
Ch:120-150	1		30.00	5.40	5.40	0.05	8.10	
Ch:150-180	1		30.00	5.40	5.50	0.05	8.18	
Ch:180-210	1		30.00	5.50	5.20	0.05	8.03	
Ch:210-240	1		30.00	5.20	5.40	0.05	7.95	
Ch:240-270	1		30.00	5.40	5.40	0.05	8.10	
Ch:270-300	1		30.00	5.40	5.50	0.05	8.18	
Ch:300-330	1		30.00	5.50	5.20	0.05	8.03	
Ch:330-360	1		30.00	5.20	5.40	0.05	7.95	
Ch:360-390	1		30.00	5.40	5.40	0.05	8.10	
Ch:390-420	1		30.00	5.40	5.50	0.05	8.18	
Ch:420-450	1		30.00	5.50	5.20	0.05	8.03	
Ch:450-480	1		30.00	5.20	5.40	0.05	7.95	
Ch:480-510	1		30.00	5.40	5.40	0.05	8.10	
Ch:510-540	1		30.00	5.40	5.50	0.05	8.18	
Ch:540-570	1		30.00	5.50	5.20	0.05	8.03	
Ch:570-600	1		30.00	5.20	5.40	0.05	7.95	
Ch:600-630	1		30.00	5.40	5.40	0.05	8.10	
Ch:630-660	1		30.00	5.40	5.50	0.05	8.18	
Ch:660-690	1		30.00	5.50	5.20	0.05	8.03	
Ch:690-720	1		30.00	5.20	5.40	0.05	7.95	
Ch:720-750	1		30.00	5.40	5.40	0.05	8.10	
Ch:750-780	1		30.00	5.40	5.50	0.05	8.18	
Ch:780-810	1		30.00	5.50	5.20	0.05	8.03	
Ch:810-840	1		30.00	5.20	5.40	0.05	7.95	
Ch:840-870	1		30.00	5.40	5.40	0.05	8.10	
Ch:870-900	1		30.00	5.40	5.50	0.05	8.18	
Ch:900-930	1		30.00	5.50	5.20	0.05	8.03	
Ch:930-950	1		20.00	5.20	5.40	0.05	5.30	
Ch:00-100 NMH Public school road								
Ch:00-30	1		30.00	5.00	4.80	0.05	7.35	
Ch:30-60	1		30.00	4.80	5.20	0.05	7.50	
Ch:60-90	1		30.00	5.20	4.80	0.05	7.50	
Ch:90-100	1		10.00	4.80	5.00	0.05	2.45	
Ch:00-145 8th cross								
Ch:00-30	1		30.00	5.20	5.20	0.05	7.80	
Ch:30-60	1		30.00	5.20	5.20	0.05	7.80	
Ch:60-90	1		30.00	5.20	5.20	0.05	7.80	
Ch:90-120	1		30.00	5.20	5.30	0.05	7.88	
Ch:120-145	1		25.00	5.30	5.30	0.05	6.63	
Royal Enclave Layout								
Ch:00-80 Cross rd beside NMH Convention Hall	1		30.00	4.50	4.40	0.05	6.68	
Ch:00-30	1		30.00	4.40	4.50	0.05	6.68	
Ch:30-60	1		20.00	4.50	4.40	0.05	4.45	
Ch:60-80								
Ch:00-230 Siddeshwara Temple Road	1		30.00	6.00	5.80	0.05	8.85	
Ch:00-30	1		30.00	5.80	5.90	0.05	8.78	
Ch:30-60								

Ch:60-90	1		30.00	5.90	6.10	0.05	9.00		
Ch:90-120	1		30.00	6.10	5.70	0.05	8.85		
Ch:120-150	1		30.00	5.70	5.90	0.05	8.70		
Ch:150-180	1		30.00	5.90	5.50	0.05	8.55		
Ch:180-210	1		30.00	5.50	6.00	0.05	8.63		
Ch:210-230	1		20.00	6.00	5.80	0.05	5.90		
Ch:00-70 1st cross									
Ch:00-30	1		30.00	4.50	4.40	0.05	6.68		
Ch:30-66	1		30.00	4.40	4.50	0.05	6.68		
Ch:60-70	1		10.00	4.50	4.40	0.05	2.23		
Ch:00-85 2nd Cross									
Ch:00-30	1		30.00	4.50	4.40	0.05	6.68		
Ch:30-60	1		30.00	4.40	4.50	0.05	6.68		
Ch:60-85	1		25.00	4.50	4.40	0.05	5.56		
Ch:00-80 3rd Cross									
Ch:00-30	1		30.00	4.50	4.40	0.05	6.68		
Ch:30-60	1		30.00	4.40	4.50	0.05	6.68		
Ch:60-80	1		20.00	4.50	4.40	0.05	4.45		
Ch:00-80 4rd Cross									
Ch:00-30	1		30.00	4.50	4.40	0.05	6.68		
Ch:30-60	1		30.00	4.40	4.50	0.05	6.68		
Ch:60-80	1		20.00	4.50	4.40	0.05	4.45		
NMH Layout									
Ch:00-220 Basava Dhyana Kendra									
Ch:00-30	1		30.00	4.30	4.30	0.05	6.45		
Ch:30-60	1		30.00	4.30	4.30	0.05	6.45		
Ch:60-90	1		30.00	4.30	4.30	0.05	6.45		
Ch:90-120	1		30.00	4.30	4.40	0.05	6.53		
Ch:120-150	1		30.00	4.40	4.40	0.05	6.60		
Ch:150-180	1		30.00	4.40	4.50	0.05	6.68		
Ch:180-210	1		30.00	4.50	4.50	0.05	6.75		
Ch:210-220	1		10.00	4.50	4.40	0.05	2.23		
Ch:00-180 BESCOM Bagalugunte									
Ch:00-30	1		30.00	5.30	5.30	0.05	7.95		
Ch:30-60	1		30.00	5.30	5.30	0.05	7.95		
Ch:60-90	1		30.00	5.30	5.40	0.05	8.03		
Ch:90-120	1		30.00	5.40	5.40	0.05	8.10		
Ch:120-150	1		30.00	5.40	5.50	0.05	8.18		
Ch:150-180	1		30.00	5.50	5.50	0.05	8.25		
Ch:00-230 1st main									
Ch:00-30	1		30.00	4.80	4.80	0.05	7.20		
Ch:30-60	1		30.00	4.80	4.80	0.05	7.20		
Ch:60-90	1		30.00	4.80	4.90	0.05	7.28		
Ch:90-120	1		30.00	4.90	4.90	0.05	7.35		
Ch:120-150	1		30.00	4.90	4.90	0.05	7.35		
Ch:150-180	1		30.00	4.90	4.90	0.05	7.35		
Ch:180-210	1		30.00	4.90	4.90	0.05	7.35		
Ch:210-230	1		20.00	4.90	4.90	0.05	4.90		
Ch:00-140 2nd main									
Ch:00-30	1		30.00	4.90	4.90	0.05	7.35		
Ch:30-60	1		30.00	4.90	4.90	0.05	7.35		
Ch:60-90	1		30.00	4.90	5.00	0.05	7.43		
Ch:90-120	1		30.00	5.00	5.00	0.05	7.50		
Ch:120-140	1		20.00	5.00	5.00	0.05	5.00		
Kirloskar connecting road									
Ch:00-370 4nd main									
Ch:00-30	1		30.00	5.80	5.80	0.05	8.70		
Ch:30-60	1		30.00	5.80	5.80	0.05	8.70		
Ch:60-90	1		30.00	5.80	5.80	0.05	8.70		
Ch:90-120	1		30.00	5.80	5.80	0.05	8.70		
Ch:120-150	1		30.00	5.80	5.80	0.05	8.70		
Ch:150-180	1		30.00	5.80	5.80	0.05	8.70		
Ch:180-210	1		30.00	5.80	5.80	0.05	8.70		
Ch:210-240	1		30.00	5.80	5.80	0.05	8.70		
Ch:240-270	1		30.00	5.80	5.70	0.05	8.63		
Ch:270-300	1		30.00	5.70	5.70	0.05	8.55		
Ch:300-330	1		30.00	5.70	5.70	0.05	8.55		
Ch:330-360	1		30.00	5.70	5.70	0.05	8.55		
Ch:360-370	1		10.00	5.70	5.70	0.05	2.85		
						Total Qty	**2863.09**	**6407.70**	**183,45,821.79**

22	KSRRB MS00-10. Providing and applying tack coat using 80/100 grade Sqm bitumen(VG10) in boiler fitted with spray set distributor at the rate of 0.25 kg per sqm on the existing prepared bituminous surface (primed surface) cleaned with mechanical broom, complete as per specifications. Clause 503 of MORTH V revision									
KPWD Issue S.R 2020-21		IL No.		21.7.		Pg.No.		158		
Byraveshwara circle										
Ch:00-310 (Naga Devaata Temple Road)										
Ch:00-30			1		30.00	6.50	6.50		195.00	
Ch:30-60			1		30.00	6.50	6.60		196.50	
Ch:60-90			1		30.00	6.60	6.40		195.00	
Ch:90-120			1		30.00	6.40	6.50		193.50	
Ch:120-150			1		30.00	6.50	6.40		193.50	
Ch:150-180			1		30.00	6.40	6.40		192.00	
Ch:180-210			1		30.00	6.40	6.50		193.50	
Ch:210-240			1		30.00	6.50	6.30		192.00	
Ch:240-270			1		30.00	6.30	6.50		192.00	
Ch:270-300			1		30.00	6.50	6.50		195.00	
Ch:300-310			1		10.00	6.50	6.50		65.00	
Ch:00-215 (From Byraveshwara Circle)										
Ch:00-30			1		30.00	7.00	7.00		210.00	
Ch:30-60			1		30.00	6.80	7.20		210.00	
Ch:60-90			1		30.00	7.20	7.00		213.00	
Ch:90-120			1		30.00	7.00	6.80		207.00	
Ch:120-150			1		30.00	6.80	6.60		201.00	
Ch:150-180			1		30.00	6.60	6.80		201.00	
Ch:180-215			1		35.00	6.80	7.20		245.00	
Ch:00-110 1st Cross										
Ch:00-30			1		30.00	4.50	4.50		135.00	
Ch:30-60			1		30.00	4.50	4.30		132.00	
Ch:60-90			1		30.00	4.30	4.40		130.50	
Ch:90-110			1		20.00	4.40	4.60		90.00	
Ch:00-112 2nd Cross										
Ch:00-30			1		30.00	5.00	5.00		150.00	
Ch:30-60			1		30.00	4.80	4.90		145.50	
Ch:60-90			1		30.00	4.90	5.10		150.00	
Ch:90-112			1		22.00	5.10	4.90		110.00	
Ch:00-110-3rd Cross										
Ch:00-30			1		30.00	4.00	4.00		120.00	
Ch:30-60			1		30.00	3.90	4.00		118.50	
Ch:60-90			1		30.00	4.00	3.80		117.00	
Ch:90-110			1		20.00	3.80	3.80		76.00	
Ch:00-88 4th Cross										
Ch:00-30			1		30.00	4.50	4.40		133.50	
Ch:30-60			1		30.00	4.40	4.60		135.00	
Ch:60-88			1		28.00	4.60	4.30		124.60	
Ch:00-82 5th Cross										
Ch:00-30			1		30.00	4.00	3.80		117.00	
Ch:30-60			1		30.00	3.80	4.00		117.00	
Ch:60-82			1		22.00	4.00	3.80		85.80	
M.H.R. Layout										
Ch:00-490(Chetana E lavada school Frant Rd to Siddhi Vinayaka Temple)										
Ch:00-30			1		30.00	5.30	5.10		156.00	
Ch:30-60			1		30.00	5.10	5.40		157.50	
Ch:60-90			1		30.00	5.40	5.50		163.50	
Ch:90-120			1		30.00	5.50	5.50		165.00	
Ch:120-150			1		30.00	5.50	5.00		157.50	
Ch:150-180			1		30.00	5.00	5.00		150.00	
Ch:180-210			1		30.00	5.20	5.50		160.50	
Ch:210-240			1		30.00	5.50	5.20		160.50	
Ch:240-270			1		30.00	5.20	5.00		153.00	
Ch:270-300			1		30.00	5.00	5.00		150.00	
Ch:300-330			1		30.00	5.20	5.20		156.00	
Ch:330-360			1		30.00	5.20	5.20		156.00	
Ch:360-390			1		30.00	5.20	5.50		160.50	
Ch:390-420			1		30.00	5.50	5.20		160.50	
Ch:420-450			1		30.00	5.20	5.00		153.00	
Ch:450-480			1		30.00	5.00	5.00		150.00	
Ch:480-490			1		10.00	5.00	5.00		50.00	
Ch:00-110 (4th Cross Road)										
Ch:00-30			1		30.00	4.10	3.90		120.00	

Ch:30-60	1		30.00	3.90	4.00		118.50	
Ch:60-90	1		30.00	4.00	3.90		118.50	
Ch:90-110	1		20.00	3.90	4.20		81.00	
Ch:00-80 (5th Cross Road)								
Ch:00-30	1		30.00	4.00	4.00		120.00	
Ch:30-60	1		30.00	3.80	4.20		120.00	
Ch:60-80	1		20.00	4.20	3.90		81.00	
Ch:00-75 (6th Cross Road)								
Ch:00-30	1		30.00	6.00	5.80		177.00	
Ch:30-60	1		30.00	5.80	5.90		175.50	
Ch:60-75	1		15.00	5.90	6.10		90.00	
Ch:00-110 (7th Cross Road)								
Ch:00-30	1		30.00	5.00	4.80		147.00	
Ch:30-60	1		30.00	4.80	5.20		150.00	
Ch:60-90	1		30.00	5.20	5.00		153.00	
Ch:90-110	1		20.00	5.00	5.00		100.00	
Ch:00-115 (8th Cross Road)								
Ch:00-30	1		30.00	4.90	4.80		145.50	
Ch:30-60	1		30.00	4.80	4.90		145.50	
Ch:60-90	1		30.00	4.90	5.00		148.50	
Ch:90-115	1		25.00	5.00	4.90		123.75	
Ch:00-210(1st Main)								
Ch:00-30	1		30.00	4.50	4.50		135.00	
Ch:30-60	1		30.00	4.50	4.50		135.00	
Ch:60-90	1		30.00	4.50	4.50		135.00	
Ch:90-120	1		30.00	4.50	4.50		135.00	
Ch:120-150	1		30.00	4.50	4.60		136.50	
Ch:150-180	1		30.00	4.60	4.60		138.00	
Ch:180-210	1		30.00	4.60	4.60		138.00	
MEENAKSHI layout								
Ch:00-280(1st Main)								
Ch:00-30	1		30.00	5.50	5.40		163.50	
Ch:30-60	1		30.00	5.40	5.50		163.50	
Ch:60-90	1		30.00	5.50	5.20		160.50	
Ch:90-120	1		30.00	5.20	5.40		159.00	
Ch:120-150	1		30.00	5.40	5.60		165.00	
Ch:150-180	1		30.00	5.60	5.40		165.00	
Ch:180-210	1		30.00	5.40	5.50		163.50	
Ch:210-240	1		30.00	5.50	5.50		165.00	
Ch:240-270	1		30.00	5.50	5.20		160.50	
Ch:270-280	1		10.00	5.20	5.40		53.00	
Ch:00-280(2nd Main)								
Ch:00-30	1		30.00	5.00	5.00		150.00	
Ch:30-60	1		30.00	5.00	4.80		147.00	
Ch:60-90	1		30.00	4.80	5.20		150.00	
Ch:90-120	1		30.00	5.20	4.60		147.00	
Ch:120-150	1		30.00	4.60	5.00		144.00	
Ch:150-180	1		30.00	5.00	4.80		147.00	
Ch:180-210	1		30.00	4.80	5.20		150.00	
Ch:210-240	1		30.00	5.20	4.80		150.00	
Ch:240-270	1		30.00	4.80	5.20		150.00	
Ch:270-280	1		10.00	5.20	5.00		51.00	
Ch:00-280(1st B Main)								
Ch:00-30	1		30.00	5.20	5.20		156.00	
Ch:30-60	1		30.00	5.20	5.20		156.00	
Ch:60-90	1		30.00	5.20	5.20		156.00	
Ch:90-120	1		30.00	5.20	5.20		156.00	
Ch:120-150	1		30.00	5.20	5.20		156.00	
Ch:150-180	1		30.00	5.20	5.30		157.50	
Ch:180-210	1		30.00	5.30	5.30		159.00	
Ch:210-240	1		30.00	5.30	5.30		159.00	
Ch:240-270	1		30.00	5.30	5.30		159.00	
Ch:00-280(1st C Main)								
Ch:00-30	1		30.00	5.50	5.50		165.00	
Ch:30-60	1		30.00	5.50	5.50		165.00	
Ch:60-90	1		30.00	5.50	5.50		165.00	
Ch:90-120	1		30.00	5.50	5.50		165.00	
Ch:120-150	1		30.00	5.50	5.50		165.00	
Ch:150-180	1		30.00	5.50	5.50		165.00	
Ch:180-210	1		30.00	5.50	5.40		163.50	

Ch:270-240	1		30.00	5.40	5.40		162.00		
Ch:240-270	1		30.00	5.40	5.40		162.00		
Ch:270-280	1		10.00	5.40	5.40		54.00		
Ch:00-95(14th Cross Road)									
Ch:00-30	1		30.00	5.00	4.80		147.00		
Ch:30-60	1		30.00	4.80	5.00		147.00		
Ch:60-95	1		35.00	5.00	5.20		178.50		
Ch:00-110(12th Cross Road)									
Ch:00-30	1		30.00	5.00	4.80		147.00		
Ch:30-60	1		30.00	4.80	5.20		150.00		
Ch:60-90	1		30.00	5.20	4.80		150.00		
Ch:90-110	1		20.00	4.80	4.90		97.00		
Ch:00-140(10th Cross Road)									
Ch:00-30	1		30.00	4.50	4.40		133.50		
Ch:30-60	1		30.00	4.40	4.50		133.50		
Ch:60-90	1		30.00	4.50	4.00		127.50		
Ch:90-120	1		30.00	4.00	4.20		123.00		
Ch:120-140	1		20.00	4.20	4.40		86.00		
Ch:00-96(9th Cross Road)									
Ch:00-30	1		30.00	4.50	4.40		133.50		
Ch:30-60	1		30.00	4.40	4.50		133.50		
Ch:60-96	1		36.00	4.50	4.40		160.20		
Ch:00-62(8th Cross Road)									
Ch:00-30	1		30.00	4.50	4.40		133.50		
Ch:30-62	1		32.00	4.40	4.50		142.40		
Ch:00-105(7th Cross Road)									
Ch:00-30	1		30.00	4.50	4.40		133.50		
Ch:30-60	1		30.00	4.40	4.50		133.50		
Ch:60-90	1		30.00	4.50	4.00		127.50		
Ch:90-105	1		15.00	4.00	4.20		61.50		
Ch:00-65(6th Cross Road)									
Ch:00-30	1		30.00	4.50	4.40		133.50		
Ch:30-65	1		35.00	4.40	4.50		155.75		
Ch:00-64(5th Cross Road)									
Ch:00-30	1		30.00	4.50	4.40		133.50		
Ch:30-64	1		34.00	4.40	4.50		151.30		
Ch:00-63(4th Cross Road)									
Ch:00-30	1		30.00	4.50	4.40		133.50		
Ch:30-63	1		33.00	4.40	4.50		146.85		
Ch:00-65(3rd Cross Road)									
Ch:00-30	1		30.00	4.50	4.40		133.50		
Ch:30-65	1		35.00	4.40	4.50		155.75		
Ch:00-66(2nd Cross Road)									
Ch:00-30	1		30.00	4.50	4.40		133.50		
Ch:30-66	1		36.00	4.40	4.50		160.20		
Ch:00-80(1st Cross Road)									
Ch:00-30	1		30.00	4.50	4.50		135.00		
Ch:30-60	1		30.00	4.50	4.40		133.50		
Ch:60-80	1		20.00	4.40	4.50		89.00		
Soundarya layout 2nd Main									
Ch:00-530(2nd Main Road)									
Ch:00-30	1		30.00	8.00	7.50		232.50		
Ch:30-60	1		30.00	7.50	7.80		229.50		
Ch:60-90	1		30.00	7.80	7.90		235.50		
Ch:90-120	1		30.00	7.90	7.70		234.00		
Ch:120-150	1		30.00	7.70	8.00		235.50		
Ch:150-180	1		30.00	8.00	8.20		243.00		
Ch:180-210	1		30.00	8.20	8.00		243.00		
Ch:210-240	1		30.00	8.00	7.90		238.50		
Ch:240-270	1		30.00	7.90	7.80		235.50		
Ch:270-300	1		30.00	7.80	8.20		240.00		
Ch:300-330	1		30.00	8.20	8.00		243.00		
Ch:330-360	1		30.00	8.00	7.90		238.50		
Ch:360-390	1		30.00	7.90	7.80		235.50		
Ch:390-420	1		30.00	7.80	8.00		237.00		
Ch:420-450	1		30.00	8.00	8.20		243.00		
Ch:450-480	1		30.00	8.20	8.00		243.00		
Ch:480-510	1		30.00	8.00	8.00		240.00		
Ch:510-530	1		20.00	8.00	8.00		160.00		
Ch:00-95(11th Cross Road)									

Comprehensive development of bad roads and improvements to road side drain, footpaths, Asphalting and concreting including culvert selected main and other connecting roads of package No.1 in ward No.14, Bagalagunte of Dasarahalli Division

Ch:00-30									
Ch:30-60	1		30.00	5.00	4.80		147.00		
Ch:60-95	1		30.00	4.80	5.20		150.00		
Ch:00-85(10th Cross Road)	1		35.00	5.20	4.80		175.00		
Ch:00-30									
Ch:30-60	1		30.00	5.00	4.80		147.00		
Ch:60-85	1		30.00	4.80	5.20		150.00		
Ch:00-75(9th Cross Road)	1		25.00	5.20	4.80		125.00		
Ch:00-30									
Ch:30-60	1		30.00	5.00	4.80		147.00		
Ch:60-75	1		30.00	4.80	5.20		150.00		
Ch:00-68(8th Cross Road)	1		15.00	5.20	4.80		75.00		
Ch:00-30									
Ch:30-68	1		30.00	5.00	4.80		147.00		
Ch:00-50(7th Cross Road)	1		38.00	4.80	5.20		190.00		
Ch:00-30									
Ch:30-50	1		30.00	5.00	4.80		147.00		
Ch:00-43(6th Cross Road)	1		20.00	4.80	5.20		100.00		
Ch:00-30									
Ch:30-43	1		30.00	5.00	4.80		147.00		
Ch:00-60(4th Cross Road)	1		13.00	4.80	5.20		65.00		
Ch:00-30									
Ch:30-60	1		30.00	5.00	4.80		147.00		
Ch:00-152(3rd Cross Road)	1		30.00	4.80	5.20		150.00		
Ch:00-30									
Ch:30-60	1		30.00	5.00	4.80		147.00		
Ch:60-90	1		30.00	4.80	5.20		150.00		
Ch:90-120	1		30.00	5.20	4.80		150.00		
Ch:120-152	1		30.00	4.80	5.20		150.00		
Ch:00-100 (Cross Road)	1		32.00	5.20	5.00		163.20		
Ch:00-30									
Ch:30-60	1		30.00	5.00	4.80		147.00		
Ch:60-90	1		30.00	4.80	5.20		150.00		
Ch:90-100	1		30.00	5.20	4.80		150.00		
Ch:00-225 (Cross Road)	1		10.00	4.80	5.20		50.00		
Ch:00-30									
Ch:30-60	1		30.00	5.50	5.40		163.50		
Ch:60-90	1		30.00	5.40	5.50		163.50		
Ch:90-120	1		30.00	5.50	5.20		160.50		
Ch:120-150	1		30.00	5.20	5.40		159.00		
Ch:150-180	1		30.00	5.40	5.40		162.00		
Ch:180-210	1		30.00	5.40	5.50		163.50		
Ch:210-225	1		30.00	5.50	5.20		160.50		
Ch:00-125(3rd Main Road)	1		15.00	5.20	5.40		79.50		
Ch:00-30									
Ch:30-60	1		30.00	5.00	4.80		147.00		
Ch:60-90	1		30.00	4.80	5.20		150.00		
Ch:90-120	1		30.00	5.20	4.80		150.00		
Ch:00-230(3rd Main Road)	1		35.00	4.80	5.20		175.00		
Ch:00-30									
Ch:30-60	1		30.00	5.00	4.80		147.00		
Ch:60-90	1		30.00	4.80	5.20		150.00		
Ch:90-120	1		30.00	5.20	4.80		150.00		
Ch:120-150	1		30.00	4.80	5.20		150.00		
Ch:150-180	1		30.00	5.20	4.80		150.00		
Ch:180-210	1		30.00	4.80	5.20		150.00		
Ch:210-230	1		30.00	5.20	4.80		150.00		
Soundarya layout 1st Main	1		20.00	4.80	5.20		100.00		
Ch:00-530(1st Main)									
Ch:00-30									
Ch:30-60	1		30.00	7.00	6.80		207.00		
Ch:60-90	1		30.00	6.80	7.00		207.00		
Ch:90-120	1		30.00	7.00	6.90		208.50		
Ch:120-150	1		30.00	6.90	6.80		205.50		
Ch:150-180	1		30.00	6.80	6.50		199.50		
Ch:180-210	1		30.00	6.50	6.80		199.50		
Ch:210-240	1		30.00	6.80	7.20		210.00		
Ch:240-270	1		30.00	7.20	7.00		213.00		
Ch:270-300	1		30.00	7.00	7.00		210.00		
Ch:300-330	1		30.00	7.00	6.90		208.50		
	1		30.00	6.90	6.80		205.50		

Sqm

Ch:330-360	1		30.00	6.80	7.10		208.50		
Ch:360-390	1		30.00	7.10	7.00		211.50		
Ch:390-420	1		30.00	7.00	6.80		207.00		
Ch:420-450	1		30.00	6.80	6.90		205.50		
Ch:450-480	1		30.00	6.90	7.10		210.00		
Ch:480-510	1		30.00	7.10	7.00		211.50		
Ch:510-530	1		20.00	7.00	7.00		140.00		
Ch:00-90(1st A Cross Road)									
Ch:00-30	1		30.00	5.00	4.80		147.00		
Ch:30-60	1		30.00	4.80	5.20		150.00		
Ch:60-90	1		30.00	5.20	4.80		150.00		
Ch:00-100(2nd A Cross Road)									
Ch:00-30	1		30.00	5.00	4.80		147.00		
Ch:30-60	1		30.00	4.80	5.20		150.00		
Ch:60-90	1		30.00	5.20	4.80		150.00		
Ch:90-100	1		10.00	4.80	4.90		48.50		
Ch:00-90(4th A Cross Road)									
Ch:00-30	1		30.00	5.00	4.80		147.00		
Ch:30-60	1		30.00	4.80	5.20		150.00		
Ch:60-90	1		30.00	5.20	4.80		150.00		
Ch:00-90(6th A Cross Road)									
Ch:00-30	1		30.00	5.00	4.80		147.00		
Ch:30-60	1		30.00	4.80	5.20		150.00		
Ch:60-90	1		30.00	5.20	4.80		150.00		
Ch:00-90(7th A Cross Road)									
Ch:00-30	1		30.00	5.00	4.90		148.50		
Ch:30-60	1		30.00	4.90	5.20		151.50		
Ch:60-90	1		30.00	5.20	4.80		150.00		
Ch:00-93(8th A Cross Road)									
Ch:00-30	1		30.00	5.00	4.80		147.00		
Ch:30-60	1		30.00	4.80	5.20		150.00		
Ch:60-93	1		33.00	5.20	4.80		165.00		
Ch:00-92(9th A Cross Road)									
Ch:00-30	1		30.00	5.00	4.90		148.50		
Ch:30-60	1		30.00	4.90	5.20		151.50		
Ch:60-92	1		32.00	5.20	4.80		160.00		
Ch:00-90(11th A Cross Road)									
Ch:00-30	1		30.00	5.00	4.80		147.00		
Ch:30-60	1		30.00	4.80	5.20		150.00		
Ch:60-90	1		30.00	5.20	4.80		150.00		
Ch:00-93(12th A Cross Road)									
Ch:00-30	1		30.00	5.00	4.80		147.00		
Ch:30-60	1		30.00	4.80	5.20		150.00		
Ch:60-93	1		33.00	5.20	4.80		165.00		
Ch:00-92(13th A Cross Road)									
Ch:00-30	1		30.00	5.00	4.80		147.00		
Ch:30-60	1		30.00	4.80	5.20		150.00		
Ch:60-92	1		32.00	5.20	4.80		160.00		
Ch:00-92(14th A Cross Road)									
Ch:00-30	1		30.00	5.00	4.80		147.00		
Ch:30-60	1		30.00	4.80	5.20		150.00		
Ch:60-92	1		32.00	5.20	4.80		160.00		
Ch:00-95(2nd B main Road)									
Ch:00-30	1		30.00	5.00	5.10		151.50		
Ch:30-60	1		30.00	5.10	5.20		154.50		
Ch:60-95	1		35.00	5.20	5.10		180.25		
Siddeshwara Layout									
Ch:00-950									
Ch:00-30	1		30.00	5.50	5.40		163.50		
Ch:30-60	1		30.00	5.40	5.50		163.50		
Ch:60-90	1		30.00	5.50	5.20		160.50		
Ch:90-120	1		30.00	5.20	5.40		159.00		
Ch:120-150	1		30.00	5.40	5.40		162.00		
Ch:150-180	1		30.00	5.40	5.50		163.50		
Ch:180-210	1		30.00	5.50	5.20		160.50		
Ch:210-240	1		30.00	5.20	5.40		159.00		
Ch:240-270	1		30.00	5.40	5.40		162.00		
Ch:270-300	1		30.00	5.40	5.50		163.50		
Ch:300-330	1		30.00	5.50	5.20		160.50		
Ch:330-360	1		30.00	5.20	5.40		159.00		

Ch:360-390	1		30.00	5.40	5.40		162.00	
Ch:390-420	1		30.00	5.40	5.50		163.50	
Ch:420-450	1		30.00	5.50	5.20		160.50	
Ch:450-480	1		30.00	5.20	5.40		159.00	
Ch:480-510	1		30.00	5.40	5.40		162.00	
Ch:510-540	1		30.00	5.40	5.50		163.50	
Ch:540-570	1		30.00	5.50	5.20		160.50	
Ch:570-600	1		30.00	5.20	5.40		159.00	
Ch:600-630	1		30.00	5.40	5.40		162.00	
Ch:630-660	1		30.00	5.40	5.50		163.50	
Ch:660-690	1		30.00	5.50	5.20		160.50	
Ch:690-720	1		30.00	5.20	5.40		159.00	
Ch:720-750	1		30.00	5.40	5.40		162.00	
Ch:750-780	1		30.00	5.40	5.50		163.50	
Ch:780-810	1		30.00	5.50	5.20		160.50	
Ch:810-840	1		30.00	5.20	5.40		159.00	
Ch:840-870	1		30.00	5.40	5.40		162.00	
Ch:870-900	1		30.00	5.40	5.50		163.50	
Ch:900-930	1		30.00	5.50	5.20		160.50	
Ch:930-950	1		20.00	5.20	5.40		106.00	
Ch:00-100 NMH Public school road								
Ch:00-30	1		30.00	5.00	4.80		147.00	
Ch:30-60	1		30.00	4.80	5.20		150.00	
Ch:60-90	1		30.00	5.20	4.80		150.00	
Ch:90-100	1		10.00	4.80	5.00		49.00	
Ch:00-145 8th cross								
Ch:00-30	1		30.00	5.20	5.20		156.00	
Ch:30-60	1		30.00	5.20	5.20		156.00	
Ch:60-90	1		30.00	5.20	5.20		156.00	
Ch:90-120	1		30.00	5.20	5.30		157.50	
Ch:120-145	1		25.00	5.30	5.30		132.50	
Royal Enclave Layout								
Ch:00-80 Cross rd beside NMH Convention Hall								
Ch:00-30	1		30.00	4.50	4.40		133.50	
Ch:30-60	1		30.00	4.40	4.50		133.50	
Ch:60-80	1		20.00	4.50	4.40		89.00	
Ch:00-230 Siddeshwara Temple Road								
Ch:00-30	1		30.00	6.00	5.80		177.00	
Ch:30-60	1		30.00	5.80	5.90		175.50	
Ch:60-90	1		30.00	5.90	6.10		180.00	
Ch:90-120	1		30.00	6.10	5.70		177.00	
Ch:120-150	1		30.00	5.70	5.90		174.00	
Ch:150-180	1		30.00	5.90	5.50		171.00	
Ch:180-210	1		30.00	5.50	6.00		172.50	
Ch:210-230	1		20.00	6.00	5.80		118.00	
Ch:00-70 1st cross								
Ch:00-30	1		30.00	4.50	4.40		133.50	
Ch:30-60	1		30.00	4.40	4.50		133.50	
Ch:60-70	1		10.00	4.50	4.40		44.50	
Ch:00-85 2nd Cross								
Ch:00-30	1		30.00	4.50	4.40		133.50	
Ch:30-60	1		30.00	4.40	4.50		133.50	
Ch:60-85	1		25.00	4.50	4.40		111.25	
Ch:00-80 3rd Cross								
Ch:00-30	1		30.00	4.50	4.40		133.50	
Ch:30-60	1		30.00	4.40	4.50		133.50	
Ch:60-80	1		20.00	4.50	4.40		89.00	
Ch:00-80 4rd Cross								
Ch:00-30	1		30.00	4.50	4.40		133.50	
Ch:30-60	1		30.00	4.40	4.50		133.50	
Ch:60-80	1		20.00	4.50	4.40		89.00	
NMH Layout								
Ch:00-220 Basava Dhyana Kendra								
Ch:00-30	1		30.00	4.30	4.30		129.00	
Ch:30-60	1		30.00	4.30	4.30		129.00	
Ch:60-90	1		30.00	4.30	4.30		129.00	
Ch:90-120	1		30.00	4.30	4.40		130.50	
Ch:120-150	1		30.00	4.40	4.40		132.00	
Ch:150-180	1		30.00	4.40	4.50		133.50	

Ch:180-210									
Ch:210-220	1		30.00	4.50	4.50		135.00		
Ch:00-180 BESCOM Bagalugunte	1		10.00	4.50	4.40		44.50		
Ch:00-30									
Ch:30-60	1		30.00	5.30	5.30		159.00		
Ch:60-90	1		30.00	5.30	5.30		159.00		
Ch:90-120	1		30.00	5.30	5.40		160.50		
Ch:120-150	1		30.00	5.40	5.40		162.00		
Ch:150-180	1		30.00	5.40	5.50		163.50		
Ch:00-230 1st main	1		30.00	5.50	5.50		165.00		
Ch:00-30									
Ch:30-60	1		30.00	4.80	4.80		144.00		
Ch:60-90	1		30.00	4.80	4.80		144.00		
Ch:90-120	1		30.00	4.80	4.90		145.50		
Ch:120-150	1		30.00	4.90	4.90		147.00		
Ch:150-180	1		30.00	4.90	4.90		147.00		
Ch:180-210	1		30.00	4.90	4.90		147.00		
Ch:210-230	1		30.00	4.90	4.90		147.00		
Ch:00-140 2nd main	1		20.00	4.90	4.90		98.00		
Ch:00-30									
Ch:30-60	1		30.00	4.90	4.90		147.00		
Ch:60-90	1		30.00	4.90	4.90		147.00		
Ch:90-120	1		30.00	4.90	5.00		148.50		
Ch:120-140	1		30.00	5.00	5.00		150.00		
Kirloskar connecting road	1		20.00	5.00	5.00		100.00		
Ch:00-370 4nd main									
Ch:00-30									
Ch:30-60	1		30.00	5.80	5.80		174.00		
Ch:60-90	1		30.00	5.80	5.80		174.00		
Ch:90-120	1		30.00	5.80	5.80		174.00		
Ch:120-150	1		30.00	5.80	5.80		174.00		
Ch:150-180	1		30.00	5.80	5.80		174.00		
Ch:180-210	1		30.00	5.80	5.80		174.00		
Ch:210-240	1		30.00	5.80	5.80		174.00		
Ch:240-270	1		30.00	5.80	5.70		172.50		
Ch:270-300	1		30.00	5.70	5.70		171.00		
Ch:300-330	1		30.00	5.70	5.70		171.00		
Ch:330-360	1		30.00	5.70	5.70		171.00		
Ch:360-370	1		10.00	5.70	5.70		57.00		
						Total Qty	**57261.80**	**12.72**	**7,28,370.10**

23	Providing and laying bituminous concrete 40mm thick with hot mix plant, using 40-60 TPH capacity HMP with mechanical paver grading II (30-45mm) with 5.4 % of modified bituminous binder consisting of 4.97% of VG-30 bitumen (60/70 grade) and 0.43% of plastomeric thermoplastics (waste plastic) crushed aggregates of specified grading, premixed with bituminous binder and filler, transporting the hot mix to work site, laying with a paver finisher to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction in all respects complete as per specifications. Clause 507 of MORTH V revision as per IRC SP-53-2015.								
	KPWD Issue S.R 2020-21	It. No.		21.78.12.		Pg.No	162		
	Byraveshwara circle								
	Ch:00-310 (Naga Devaata Temple Road)								
	Ch:00-30	1		30.00	6.50	6.50	0.03	5.85	
	Ch:30-60	1		30.00	6.50	6.60	0.03	5.90	
	Ch:60-90	1		30.00	6.60	6.40	0.03	5.85	
	Ch:90-120	1		30.00	6.40	6.50	0.03	5.81	
	Ch:120-150	1		30.00	6.50	6.40	0.03	5.81	
	Ch:150-180	1		30.00	6.40	6.40	0.03	5.76	
	Ch:180-210	1		30.00	6.40	6.50	0.03	5.81	
	Ch:210-240	1		30.00	6.50	6.30	0.03	5.76	
	Ch:240-270	1		30.00	6.30	6.50	0.03	5.76	
	Ch:270-300	1		30.00	6.50	6.50	0.03	5.85	
	Ch:300-310	1		10.00	6.50	6.50	0.03	1.95	
	Ch:00-215 (From Byraveshwara Circle)								
	Ch:00-30	1		30.00	7.00	7.00	0.03	6.30	
	Ch:30-60	1		30.00	6.80	7.20	0.03	6.30	
	Ch:60-90	1		30.00	7.20	7.00	0.03	6.39	
	Ch:90-120	1		30.00	7.00	6.80	0.03	6.21	
	Ch:120-150	1		30.00	6.80	6.60	0.03	6.03	
	Ch:150-180	1		30.00	6.60	6.80	0.03	6.03	
	Ch:180-215	1		35.00	6.80	7.20	0.03	7.35	
	Ch:00-110 1st Cross								

Ch:00-30	1		30.00	4.50	4.50	0.03	4.05	
Ch:30-60	1		30.00	4.50	4.30	0.03	3.96	
Ch:60-90	1		30.00	4.30	4.40	0.03	3.92	
Ch:90-110	1		20.00	4.40	4.60	0.03	2.70	
Ch:00-112 2nd Cross								
Ch:00-30	1		30.00	5.00	5.00	0.03	4.50	
Ch:30-60	1		30.00	4.80	4.90	0.03	4.37	
Ch:60-90	1		30.00	4.90	5.10	0.03	4.50	
Ch:90-112	1		22.00	5.10	4.90	0.03	3.30	
Ch:00-110-3rd Cross								
Ch:00-30	1		30.00	4.00	4.00	0.03	3.60	
Ch:30-60	1		30.00	3.90	4.00	0.03	3.56	
Ch:60-90	1		30.00	4.00	3.80	0.03	3.51	
Ch:90-110	1		20.00	3.80	3.80	0.03	2.28	
Ch:00-88 4th Cross								
Ch:00-30	1		30.00	4.50	4.40	0.03	4.01	
Ch:30-60	1		30.00	4.40	4.60	0.03	4.05	
Ch:60-88	1		28.00	4.60	4.30	0.03	3.74	
Ch:00-82 5th Cross								
Ch:00-30	1		30.00	4.00	3.80	0.03	3.51	
Ch:30-60	1		30.00	3.80	4.00	0.03	3.51	
Ch:60-82	1		22.00	4.00	3.80	0.03	2.57	
M.H.R. Layout								
Ch:00-490(Chetana E lavada school Frant Rd to Siddhi Vinayaka Temple)								
Ch:00-30	1		30.00	5.30	5.10	0.03	4.68	
Ch:30-60	1		30.00	5.10	5.40	0.03	4.73	
Ch:60-90	1		30.00	5.40	5.50	0.03	4.91	
Ch:90-120	1		30.00	5.50	5.50	0.03	4.95	
Ch:120-150	1		30.00	5.50	5.00	0.03	4.73	
Ch:150-180	1		30.00	5.00	5.00	0.03	4.50	
Ch:180-210	1		30.00	5.20	5.50	0.03	4.82	
Ch:210-240	1		30.00	5.50	5.20	0.03	4.82	
Ch:240-270	1		30.00	5.20	5.00	0.03	4.59	
Ch:270-300	1		30.00	5.00	5.00	0.03	4.50	
Ch:300-330	1		30.00	5.20	5.20	0.03	4.68	
Ch:330-360	1		30.00	5.20	5.20	0.03	4.68	
Ch:360-390	1		30.00	5.20	5.50	0.03	4.82	
Ch:390-420	1		30.00	5.50	5.20	0.03	4.82	
Ch:420-450	1		30.00	5.20	5.00	0.03	4.59	
Ch:450-480	1		30.00	5.00	5.00	0.03	4.50	
Ch:480-490	1		10.00	5.00	5.00	0.03	1.50	
Ch:00-110 (4th Cross Road)								
Ch:00-30	1		30.00	4.10	3.90	0.03	3.60	
Ch:30-60	1		30.00	3.90	4.00	0.03	3.56	
Ch:60-90	1		30.00	4.00	3.90	0.03	3.56	
Ch:90-110	1		20.00	3.90	4.20	0.03	2.43	
Ch:00-80 (5th Cross Road)								
Ch:00-30	1		30.00	4.00	4.00	0.03	3.60	
Ch:30-60	1		30.00	3.80	4.20	0.03	3.60	
Ch:60-80	1		20.00	4.20	3.90	0.03	2.43	
Ch:00-75 (6th Cross Road)								
Ch:00-30	1		30.00	6.00	5.80	0.03	5.31	
Ch:30-60	1		30.00	5.80	5.90	0.03	5.27	
Ch:60-75	1		15.00	5.90	6.10	0.03	2.70	
Ch:00-110 (7th Cross Road)								
Ch:00-30	1		30.00	5.00	4.80	0.03	4.41	
Ch:30-60	1		30.00	4.80	5.20	0.03	4.50	
Ch:60-90	1		30.00	5.20	5.00	0.03	4.59	
Ch:90-110	1		20.00	5.00	5.00	0.03	3.00	
Ch:00-115 (8th Cross Road)								
Ch:00-30	1		30.00	4.90	4.80	0.03	4.37	
Ch:30-60	1		30.00	4.80	4.90	0.03	4.37	
Ch:60-90	1		30.00	4.90	5.00	0.03	4.46	
Ch:90-115	1		25.00	5.00	4.90	0.03	3.71	
Ch:00-210(1st Main)								
Ch:00-30	1		30.00	4.50	4.50	0.03	4.05	
Ch:30-60	1		30.00	4.50	4.50	0.03	4.05	
Ch:60-90	1		30.00	4.50	4.50	0.03	4.05	
Ch:90-120	1		30.00	4.50	4.50	0.03	4.05	

Ch:120-150	1		30.00	4.50	4.60	0.03	4.10	
Ch:150-180	1		30.00	4.60	4.60	0.03	4.14	
Ch:180-210	1		30.00	4.60	4.60	0.03	4.14	
MEENAKSHI layout								
Ch:00-280(1st Main)								
Ch:00-30	1		30.00	5.50	5.40	0.03	4.91	
Ch:30-60	1		30.00	5.40	5.50	0.03	4.91	
Ch:60-90	1		30.00	5.50	5.20	0.03	4.82	
Ch:90-120	1		30.00	5.20	5.40	0.03	4.77	
Ch:120-150	1		30.00	5.40	5.60	0.03	4.95	
Ch:150-180	1		30.00	5.60	5.40	0.03	4.95	
Ch:180-210	1		30.00	5.40	5.50	0.03	4.91	
Ch:210-240	1		30.00	5.50	5.50	0.03	4.95	
Ch:240-270	1		30.00	5.50	5.20	0.03	4.82	
Ch:270-280	1		10.00	5.20	5.40	0.03	1.59	
Ch:00-280(2nd Main)								
Ch:00-30	1		30.00	5.00	5.00	0.03	4.50	
Ch:30-60	1		30.00	5.00	4.80	0.03	4.41	
Ch:60-90	1		30.00	4.80	5.20	0.03	4.50	
Ch:90-120	1		30.00	5.20	4.60	0.03	4.41	
Ch:120-150	1		30.00	4.60	5.00	0.03	4.32	
Ch:150-180	1		30.00	5.00	4.80	0.03	4.41	
Ch:180-210	1		30.00	4.80	5.20	0.03	4.50	
Ch:210-240	1		30.00	5.20	4.80	0.03	4.50	
Ch:240-270	1		30.00	4.80	5.20	0.03	4.50	
Ch:270-280	1		10.00	5.20	5.00	0.03	1.53	
Ch:00-270(1st BMain)								
Ch:00-30	1		30.00	5.20	5.20	0.03	4.68	
Ch:30-60	1		30.00	5.20	5.20	0.03	4.68	
Ch:60-90	1		30.00	5.20	5.20	0.03	4.68	
Ch:90-120	1		30.00	5.20	5.20	0.03	4.68	
Ch:120-150	1		30.00	5.20	5.20	0.03	4.68	
Ch:150-180	1		30.00	5.20	5.30	0.03	4.73	
Ch:180-210	1		30.00	5.30	5.30	0.03	4.77	
Ch:210-240	1		30.00	5.30	5.30	0.03	4.77	
Ch:240-270	1		30.00	5.30	5.30	0.03	4.77	
Ch:00-280(1st C Main)								
Ch:00-30	1		30.00	5.50	5.50	0.03	4.95	
Ch:30-60	1		30.00	5.50	5.50	0.03	4.95	
Ch:60-90	1		30.00	5.50	5.50	0.03	4.95	
Ch:90-120	1		30.00	5.50	5.50	0.03	4.95	
Ch:120-150	1		30.00	5.50	5.50	0.03	4.95	
Ch:150-180	1		30.00	5.50	5.50	0.03	4.95	
Ch:180-210	1		30.00	5.50	5.40	0.03	4.91	
Ch:210-240	1		30.00	5.40	5.40	0.03	4.86	
Ch:240-270	1		30.00	5.40	5.40	0.03	4.86	
Ch:270-280	1		10.00	5.40	5.40	0.03	1.62	
Ch:00-95(14th Cross Road)								
Ch:00-30	1		30.00	5.00	4.80	0.03	4.41	
Ch:30-60	1		30.00	4.80	5.00	0.03	4.41	
Ch:60-95	1		35.00	5.00	5.20	0.03	5.36	
Ch:00-110(12th Cross Road)								
Ch:00-30	1		30.00	5.00	4.80	0.03	4.41	
Ch:30-60	1		30.00	4.80	5.20	0.03	4.50	
Ch:60-90	1		30.00	5.20	4.80	0.03	4.50	
Ch:90-110	1		20.00	4.80	4.90	0.03	2.91	
Ch:00-140(10th Cross Road)								
Ch:00-30	1		30.00	4.50	4.40	0.03	4.01	
Ch:30-60	1		30.00	4.40	4.50	0.03	4.01	
Ch:60-90	1		30.00	4.50	4.00	0.03	3.83	
Ch:90-120	1		30.00	4.00	4.20	0.03	3.69	
Ch:120-140	1		20.00	4.20	4.40	0.03	2.58	
Ch:00-96(9th Cross Road)								
Ch:00-30	1		30.00	4.50	4.40	0.03	4.01	
Ch:30-60	1		30.00	4.40	4.50	0.03	4.01	
Ch:60-96	1		36.00	4.50	4.40	0.03	4.81	
Ch:00-62(8th Cross Road)								
Ch:00-30	1		30.00	4.50	4.40	0.03	4.01	
Ch:30-62	1		32.00	4.40	4.50	0.03	4.27	
Ch:00-105(7th Cross Road)								

Comprehensive development of bad roads and improvements to road side drain, footpaths, Asphalting and concreting including culvert selected main and other connecting roads of package No.1 in ward No.14, Bagalagunte of Dasarahalli Division

Ch:00-30	1		30.00	4.50	4.40	0.03	4.01	
Ch:30-60	1		30.00	4.40	4.50	0.03	4.01	
Ch:60-90	1		30.00	4.50	4.00	0.03	3.83	
Ch:90-105	1		15.00	4.00	4.20	0.03	1.85	
Ch:00-65(6th Cross Road)								
Ch:00-30	1		30.00	4.50	4.40	0.03	4.01	
Ch:30-65	1		35.00	4.40	4.50	0.03	4.67	
Ch:00-64(5th Cross Road)								
Ch:00-30	1		30.00	4.50	4.40	0.03	4.01	
Ch:30-64	1		34.00	4.40	4.50	0.03	4.54	
Ch:00-63(4th Cross Road)								
Ch:00-30	1		30.00	4.50	4.40	0.03	4.01	
Ch:30-63	1		33.00	4.40	4.50	0.03	4.41	
Ch:00-65(3rd Cross Road)								
Ch:00-30	1		30.00	4.50	4.40	0.03	4.01	
Ch:30-65	1		35.00	4.40	4.50	0.03	4.67	
Ch:00-66(2nd Cross Road)								
Ch:00-30	1		30.00	4.50	4.40	0.03	4.01	
Ch:30-66	1		36.00	4.40	4.50	0.03	4.81	
Ch:00-80(1st Cross Road)								
Ch:00-30	1		30.00	4.50	4.50	0.03	4.05	
Ch:30-60	1		30.00	4.50	4.40	0.03	4.01	
Ch:60-80	1		20.00	4.40	4.50	0.03	2.67	
Soundarya layout 2nd Main								
Ch:00-530(2nd Main Road)								
Ch:00-30	1		30.00	8.00	7.50	0.03	6.98	
Ch:30-60	1		30.00	7.50	7.80	0.03	6.89	
Ch:60-90	1		30.00	7.80	7.90	0.03	7.07	
Ch:90-120	1		30.00	7.90	7.70	0.03	7.02	
Ch:120-150	1		30.00	7.70	8.00	0.03	7.07	
Ch:150-180	1		30.00	8.00	8.20	0.03	7.29	
Ch:180-210	1		30.00	8.20	8.00	0.03	7.29	
Ch:210-240	1		30.00	8.00	7.90	0.03	7.16	
Ch:240-270	1		30.00	7.90	7.80	0.03	7.07	
Ch:270-300	1		30.00	7.80	8.20	0.03	7.20	
Ch:300-330	1		30.00	8.20	8.00	0.03	7.29	
Ch:330-360	1		30.00	8.00	7.90	0.03	7.16	
Ch:360-390	1		30.00	7.90	7.80	0.03	7.07	
Ch:390-420	1		30.00	7.80	8.00	0.03	7.11	
Ch:420-450	1		30.00	8.00	8.20	0.03	7.29	
Ch:450-480	1		30.00	8.20	8.00	0.03	7.29	
Ch:480-510	1		30.00	8.00	8.00	0.03	7.20	
Ch:510-530	1		20.00	8.00	8.00	0.03	4.80	
Ch00-95(11th Cross Road)								
Ch:00-30	1		30.00	5.00	4.80	0.03	4.41	
Ch:30-60	1		30.00	4.80	5.20	0.03	4.50	
Ch:60-95	1		35.00	5.20	4.80	0.03	5.25	
Ch:00-85(10th Cross Road)								
Ch:00-30	1		30.00	5.00	4.80	0.03	4.41	
Ch:30-60	1		30.00	4.80	5.20	0.03	4.50	
Ch:60-85	1		25.00	5.20	4.80	0.03	3.75	
Ch:00-75(9th Cross Road)								
Ch:00-30	1		30.00	5.00	4.80	0.03	4.41	
Ch:30-60	1		30.00	4.80	5.20	0.03	4.50	
Ch:60-75	1		15.00	5.20	4.80	0.03	2.25	
Ch:00-68(8th Cross Road)								
Ch:00-30	1		30.00	5.00	4.80	0.03	4.41	
Ch:30-68	1		38.00	4.80	5.20	0.03	5.70	
Ch:00-50(7th Cross Road)								
Ch:00-30	1		30.00	5.00	4.80	0.03	4.41	
Ch:30-50	1		20.00	4.80	5.20	0.03	3.00	
Ch:00-43(6th Cross Road)								
Ch:00-30	1		30.00	5.00	4.80	0.03	4.41	
Ch:30-43	1		13.00	4.80	5.20	0.03	1.95	
Ch:00-60(4th Cross Road)								
Ch:00-30	1		30.00	5.00	4.80	0.03	4.41	
Ch:30-60	1		30.00	4.80	5.20	0.03	4.50	
Ch:00-152(3rd Cross Road)								
Ch:00-30	1		30.00	5.00	4.80	0.03	4.41	
Ch:30-60	1		30.00	4.80	5.20	0.03	4.50	

Cum

Ch:60-90	1		30.00	5.20	4.80	0.03	4.50	
Ch:90-120	1		30.00	4.80	5.20	0.03	4.50	
Ch:120-152	1		32.00	5.20	5.00	0.03	4.90	
Ch:00-100 (Cross Road)								
Ch:00-30	1		30.00	5.00	4.80	0.03	4.41	
Ch:30-60	1		30.00	4.80	5.20	0.03	4.50	
Ch:60-90	1		30.00	5.20	4.80	0.03	4.50	
Ch:90-100	1		10.00	4.80	5.20	0.03	1.50	
Ch:00-225 (Cross Road)								
Ch:00-30	1		30.00	5.50	5.40	0.03	4.91	
Ch:30-60	1		30.00	5.40	5.50	0.03	4.91	
Ch:60-90	1		30.00	5.50	5.20	0.03	4.82	
Ch:90-120	1		30.00	5.20	5.40	0.03	4.77	
Ch:120-150	1		30.00	5.40	5.40	0.03	4.86	
Ch:150-180	1		30.00	5.40	5.50	0.03	4.91	
Ch:180-210	1		30.00	5.50	5.20	0.03	4.82	
Ch:210-225	1		15.00	5.20	5.40	0.03	2.39	
Ch:00-125(3rd Main Road)								
Ch:00-30	1		30.00	5.00	4.80	0.03	4.41	
Ch:30-60	1		30.00	4.80	5.20	0.03	4.50	
Ch:60-90	1		30.00	5.20	4.80	0.03	4.50	
Ch:90-120	1		35.00	4.80	5.20	0.03	5.25	
Ch:00-230(3rd Main Road)								
Ch:00-30	1		30.00	5.00	4.80	0.03	4.41	
Ch:30-60	1		30.00	4.80	5.20	0.03	4.50	
Ch:60-90	1		30.00	5.20	4.80	0.03	4.50	
Ch:90-120	1		30.00	4.80	5.20	0.03	4.50	
Ch:120-150	1		30.00	5.20	4.80	0.03	4.50	
Ch:150-180	1		30.00	4.80	5.20	0.03	4.50	
Ch:180-210	1		30.00	5.20	4.80	0.03	4.50	
Ch:210-230	1		20.00	4.80	5.20	0.03	3.00	
Soundarya layout 1st Main								
Ch:00-530(1st Main)								
Ch:00-30	1		30.00	7.00	6.80	0.03	6.21	
Ch:30-60	1		30.00	6.80	7.00	0.03	6.21	
Ch:60-90	1		30.00	7.00	6.90	0.03	6.26	
Ch:90-120	1		30.00	6.90	6.80	0.03	6.17	
Ch:120-150	1		30.00	6.80	6.50	0.03	5.99	
Ch:150-180	1		30.00	6.50	6.80	0.03	5.99	
Ch:180-210	1		30.00	6.80	7.20	0.03	6.30	
Ch:210-240	1		30.00	7.20	7.00	0.03	6.39	
Ch:240-270	1		30.00	7.00	7.00	0.03	6.30	
Ch:270-300	1		30.00	7.00	6.90	0.03	6.26	
Ch:300-330	1		30.00	6.90	6.80	0.03	6.17	
Ch:330-360	1		30.00	6.80	7.10	0.03	6.26	
Ch:360-390	1		30.00	7.10	7.00	0.03	6.35	
Ch:390-420	1		30.00	7.00	6.80	0.03	6.21	
Ch:420-450	1		30.00	6.80	6.90	0.03	6.17	
Ch:450-480	1		30.00	6.90	7.10	0.03	6.30	
Ch:480-510	1		30.00	7.10	7.00	0.03	6.35	
Ch:510-530	1		20.00	7.00	7.00	0.03	4.20	
Ch:00-90(1st A Cross Road)								
Ch:00-30	1		30.00	5.00	4.80	0.03	4.41	
Ch:30-60	1		30.00	4.80	5.20	0.03	4.50	
Ch:60-90	1		30.00	5.20	4.80	0.03	4.50	
Ch:00-100(2nd A Cross Road)								
Ch:00-30	1		30.00	5.00	4.80	0.03	4.41	
Ch:30-60	1		30.00	4.80	5.20	0.03	4.50	
Ch:60-90	1		30.00	5.20	4.80	0.03	4.50	
Ch:90-100	1		10.00	4.80	4.90	0.03	1.46	
Ch:00-90(4th A Cross Road)								
Ch:00-30	1		30.00	5.00	4.80	0.03	4.41	
Ch:30-60	1		30.00	4.80	5.20	0.03	4.50	
Ch:60-90	1		30.00	5.20	4.80	0.03	4.50	
Ch:00-90(6th A Cross Road)								
Ch:00-30	1		30.00	5.00	4.80	0.03	4.41	
Ch:30-60	1		30.00	4.80	5.20	0.03	4.50	
Ch:60-90	1		30.00	5.20	4.80	0.03	4.50	
Ch:00-90(7th A Cross Road)								
Ch:00-30	1		30.00	5.00	4.90	0.03	4.46	

N FOR 1SQM AREA

Ch:30-60	1		30.00	4.90	5.20	0.03	4.55	
Ch:60-90	1		30.00	5.20	4.80	0.03	4.50	
Ch:00-93(8th A Cross Road)								
Ch:00-30	1		30.00	5.00	4.80	0.03	4.41	
Ch:30-60	1		30.00	4.80	5.20	0.03	4.50	
Ch:60-93	1		33.00	5.20	4.80	0.03	4.95	
Ch:00-92(9th A Cross Road)								
Ch:00-30	1		30.00	5.00	4.90	0.03	4.46	
Ch:30-60	1		30.00	4.90	5.20	0.03	4.55	
Ch:60-92	1		32.00	5.20	4.80	0.03	4.80	
Ch:00-90(11th A Cross Road)								
Ch:00-30	1		30.00	5.00	4.80	0.03	4.41	
Ch:30-60	1		30.00	4.80	5.20	0.03	4.50	
Ch:60-90	1		30.00	5.20	4.80	0.03	4.50	
Ch:00-93(12th A Cross Road)								
Ch:00-30	1		30.00	5.00	4.80	0.03	4.41	
Ch:30-60	1		30.00	4.80	5.20	0.03	4.50	
Ch:60-93	1		33.00	5.20	4.80	0.03	4.95	
Ch:00-92(13th A Cross Road)								
Ch:00-30	1		30.00	5.00	4.80	0.03	4.41	
Ch:30-60	1		30.00	4.80	5.20	0.03	4.50	
Ch:60-92	1		32.00	5.20	4.80	0.03	4.80	
Ch:00-92(14th A Cross Road)								
Ch:00-30	1		30.00	5.00	4.80	0.03	4.41	
Ch:30-60	1		30.00	4.80	5.20	0.03	4.50	
Ch:60-92	1		32.00	5.20	4.80	0.03	4.80	
Ch:00-95(14th A Cross Road)								
Ch:00-30	1		30.00	5.00	4.80	0.03	4.41	
Ch:30-60	1		30.00	4.80	5.20	0.03	4.50	
Ch:60-95	1		35.00	5.20	4.80	0.03	5.25	
Siddeshwara Layout								
Ch:00-950								
Ch:00-30	1		30.00	5.50	5.40	0.03	4.91	
Ch:30-60	1		30.00	5.40	5.50	0.03	4.91	
Ch:60-90	1		30.00	5.50	5.20	0.03	4.82	
Ch:90-120	1		30.00	5.20	5.40	0.03	4.77	
Ch:120-150	1		30.00	5.40	5.40	0.03	4.86	
Ch:150-180	1		30.00	5.40	5.50	0.03	4.91	
Ch:180-210	1		30.00	5.50	5.20	0.03	4.82	
Ch:210-240	1		30.00	5.20	5.40	0.03	4.77	
Ch:240-270	1		30.00	5.40	5.40	0.03	4.86	
Ch:270-300	1		30.00	5.40	5.50	0.03	4.91	
Ch:300-330	1		30.00	5.50	5.20	0.03	4.82	
Ch:330-360	1		30.00	5.20	5.40	0.03	4.77	
Ch:360-390	1		30.00	5.40	5.40	0.03	4.86	
Ch:390-420	1		30.00	5.40	5.50	0.03	4.91	
Ch:420-450	1		30.00	5.50	5.20	0.03	4.82	
Ch:450-480	1		30.00	5.20	5.40	0.03	4.77	
Ch:480-510	1		30.00	5.40	5.40	0.03	4.86	
Ch:510-540	1		30.00	5.40	5.50	0.03	4.91	
Ch:540-570	1		30.00	5.50	5.20	0.03	4.82	
Ch:570-600	1		30.00	5.20	5.40	0.03	4.77	
Ch:600-630	1		30.00	5.40	5.40	0.03	4.86	
Ch:630-660	1		30.00	5.40	5.50	0.03	4.91	
Ch:660-690	1		30.00	5.50	5.20	0.03	4.82	
Ch:690-720	1		30.00	5.20	5.40	0.03	4.77	
Ch:720-750	1		30.00	5.40	5.40	0.03	4.86	
Ch:750-780	1		30.00	5.40	5.50	0.03	4.91	
Ch:780-810	1		30.00	5.50	5.20	0.03	4.82	
Ch:810-840	1		30.00	5.20	5.40	0.03	4.77	
Ch:840-870	1		30.00	5.40	5.40	0.03	4.86	
Ch:870-900	1		30.00	5.40	5.50	0.03	4.91	
Ch:900-930	1		30.00	5.50	5.20	0.03	4.82	
Ch:930-950	1		20.00	5.20	5.40	0.03	3.18	
Ch:00-100 NMH Public school road								
Ch:00-30	1		30.00	5.00	4.80	0.03	4.41	
Ch:30-60	1		30.00	4.80	5.20	0.03	4.50	
Ch:60-90	1		30.00	5.20	4.80	0.03	4.50	
Ch:90-100	1		10.00	4.80	5.00	0.03	1.47	
Ch:00-145 8th cross								

Ch:00-30								
Ch:30-60								
Ch:60-90								
Ch:90-120								
Ch:120-145								
Royal Enclave Layout								
Ch:00-80 Cross rd beside NMH Convention Hall								
Ch:00-30								
Ch:30-60								
Ch:60-80								
Ch:00-230 Siddeshwara Temple Road								
Ch:00-30	1		30.00	5.20	5.20	0.03	4.68	
Ch:30-60	1		30.00	5.20	5.20	0.03	4.68	
Ch:60-90	1		30.00	5.20	5.20	0.03	4.68	
Ch:90-120	1		30.00	5.20	5.30	0.03	4.73	
Ch:120-150	1		25.00	5.30	5.30	0.03	3.98	
Ch:150-180								
Ch:180-210								
Ch:210-230								
Ch:00-70 1st cross								
Ch:00-30	1		30.00	4.50	4.40	0.03	4.01	
Ch:30-60	1		30.00	4.40	4.50	0.03	4.01	
Ch:60-70	1		20.00	4.50	4.40	0.03	2.67	
Ch:00-85 2nd Cross								
Ch:00-30	1		30.00	6.00	5.80	0.03	5.31	
Ch:30-60	1		30.00	5.80	5.90	0.03	5.27	
Ch:60-85	1		30.00	5.90	6.10	0.03	5.40	
Ch:00-80 3rd Cross	1		30.00	6.10	5.70	0.03	5.31	
Ch:00-30	1		30.00	5.70	5.90	0.03	5.22	
Ch:30-60	1		30.00	5.90	5.50	0.03	5.13	
Ch:60-80	1		30.00	5.50	6.00	0.03	5.18	
Ch:00-80 4rd Cross	1		20.00	6.00	5.80	0.03	3.54	
Ch:00-30								
Ch:30-60	1		30.00	4.50	4.40	0.03	4.01	
Ch:60-80	1		30.00	4.40	4.50	0.03	4.01	
NMH Layout	1		10.00	4.50	4.40	0.03	1.34	
Ch:00-220 Basava Dhyana Kendra								
Ch:00-30	1		30.00	4.30	4.30	0.03	3.87	
Ch:30-60	1		30.00	4.30	4.30	0.03	3.87	
Ch:60-90	1		30.00	4.30	4.30	0.03	3.87	
Ch:90-120	1		30.00	4.30	4.40	0.03	3.92	
Ch:120-150	1		30.00	4.40	4.40	0.03	3.96	
Ch:150-180	1		30.00	4.40	4.50	0.03	4.01	
Ch:180-210	1		30.00	4.50	4.50	0.03	4.05	
Ch:210-220	1		10.00	4.50	4.40	0.03	1.34	
Ch:00-180 BESCOM Bagalugunte								
Ch:00-30	1		30.00	5.30	5.30	0.03	4.77	
Ch:30-60	1		30.00	5.30	5.30	0.03	4.77	
Ch:60-90	1		30.00	5.30	5.40	0.03	4.82	
Ch:90-120	1		30.00	5.40	5.40	0.03	4.86	
Ch:120-150	1		30.00	5.40	5.50	0.03	4.91	
Ch:150-180	1		30.00	5.50	5.50	0.03	4.95	
Ch:00-230 1st main								
Ch:00-30	1		30.00	4.80	4.80	0.03	4.32	
Ch:30-60	1		30.00	4.80	4.80	0.03	4.32	
Ch:60-90	1		30.00	4.80	4.90	0.03	4.37	
Ch:90-120	1		30.00	4.90	4.90	0.03	4.41	
Ch:120-150	1		30.00	4.90	4.90	0.03	4.41	
Ch:150-180	1		30.00	4.90	4.90	0.03	4.41	
Ch:180-210	1		30.00	4.90	4.90	0.03	4.41	
Ch:210-230	1		20.00	4.90	4.90	0.03	2.94	
Ch:00-140 2nd main								
Ch:00-30	1		30.00	4.90	4.90	0.03	4.41	
Ch:30-60	1		30.00	4.90	4.90	0.03	4.41	
Ch:60-90	1		30.00	4.90	5.00	0.03	4.46	
Ch:90-120	1		30.00	5.00	5.00	0.03	4.50	
Ch:120-140	1		20.00	5.00	5.00	0.03	3.00	
Kirloskar connecting road								
Ch:00-370 4nd main								

Ch:00-30	1		30.00	5.80	5.80	0.03	5.22		
Ch:30-60	1		30.00	5.80	5.80	0.03	5.22		
Ch:60-90	1		30.00	5.80	5.80	0.03	5.22		
Ch:90-120	1		30.00	5.80	5.80	0.03	5.22		
Ch:120-150	1		30.00	5.80	5.80	0.03	5.22		
Ch:150-180	1		30.00	5.80	5.80	0.03	5.22		
Ch:180-210	1		30.00	5.80	5.80	0.03	5.22		
Ch:210-240	1		30.00	5.80	5.80	0.03	5.22		
Ch:240-270	1		30.00	5.80	5.70	0.03	5.18		
Ch:270-300	1		30.00	5.70	5.70	0.03	5.13		
Ch:300-330	1		30.00	5.70	5.70	0.03	5.13		
Ch:330-360	1		30.00	5.70	5.70	0.03	5.13		
Ch:360-370	1		10.00	5.70	5.70	0.03	1.71		
							Total Qty	**1717.43**	**7537.66**	**129,45,403.41**

24 KSRRB M800-13.Road Marking with Hot Applied Thermoplastic Compound with Reflectrising Glass Beads on Bituminous Surface/ Concrete Surface: Providing and laying of hot applied thermoplastic compound 2.5 mm thick including reflectorising glass beads at 250 gms per sqm area, thickness of 2.5 mm is exclusive of surface applied glass beads as per IRC:35 standards specified. The finished surface to be level, uniform and free from streaks and holes complete as per specifications. MORTH Specification No. 803

KPWD S.R 2018-19 — It. No. 24.15 — Pg.No. 182

Byraveshwara circle									
Edge lane Road Both Side									
Centre	1	1	525.00	0.1			52.50		
Road Both Side	1	2	1027.00	0.1			205.40		
M.H.R. Layout									
Central	1	1	675.00	0.1			67.50		
Road Both Side	1	2	1190.00	0.1			238.00		
MEENAKSHI Layout									
Central	1	1	560.00	0.1			56.00		
Road Both Side	1	2	1846.00	0.1			369.20		
Soundarya layout 2nd Main									
Central	1	1	510.00	0.1			51.00		
Road Both Side	1	2	1818.00	0.1			363.60		
Soundarya layout 1st Main									
Central	1	1	892.00	0.1			89.20		
Road Both Side	1	2	1542.00	0.1			308.40		
Siddeshwara Layout									
Ch:00-950	1	1	950.00	0.1			95.00		
Road Both Side	1	2	1195.00	0.1			239.00		
NMH Layout									
Central	1	1	180.00	0.1			18.00		
Road Both Side	1	2	770.00	0.1			154.00		
Kirloskar connecting road									
Central	1	1	370.00	0.1			37.00		
Road Both Side	1	2	370.00	0.1			74.00		
							Total Qty	**2417.80**	**454.74**	**10,99,470.37**

Sqm

25 0829 RCC pipes NP3 900 mm dia including collars

KPWD S.R 2018-19 — It. No. 584 — Pg.No XXIII

Recharge Pit 1.0m Dia									
Byraveshwara circle	M	12					2.50	30.00		
Soundarya layout 2nd Main		10					2.50	25.00		
Soundarya layout 1st Main		20					2.50	50.00		
Siddeshwara Layout		22					2.50	55.00		
Royal Enclave Layout		6					2.50	15.00		
							Total Qty	**175.00**	**4383.73**	**7,67,151.95**

26 0750 40 mm nominal size Couse aggregate

KPWD S.R 2018-19 — It. No. 25 — Pg.No II

Recharge Pit									
Byraveshwara circle	Cum	12		0.80			1.25	12.00		
Soundarya layout 2nd Main		10		0.80			1.25	10.00		
Soundarya layout 1st Main		20		0.80			1.25	20.00		
Siddeshwara Layout		22		0.80			1.25	22.00		
Royal Enclave Layout		6		0.80			1.25	6.00		
							Total Qty	**70.00**	**1156.92**	**80,984.11**

Comprehensive development of bad roads and impro... footpaths, Asphalting and concreting including culvert selected main and other connecting roads of package No.1 in ward no... Bagalagunte of Dasarahalli Division

Pg.No. 111

27	0772 Natural sand 5.6 to 75 m							
	KPWD S.R 2018-19	No	54	Pg.No.	111			
	Recharge Pit							
	Byraveshwara circle	Cum	12	0.80	1.25	12.00		
	Soundarya layout 2nd Main		10	0.80	1.25	10.00		
	Soundarya layout 1st Main		20	0.80	1.25	20.00		
	Siddeshwara Layout		22	0.80	1.25	22.00		
	Royal Enclave Layout		6	0.80	1.25	6.00		
					Total Qty	70.00	1781.81	1,24,726.49
							Total Constrution cost	1315,84,233.80
							GST 12%	157,90,108.06
							Design Report,Proof Checking & PMC Amount	26,25,000.00
							Sub Total	1499,99,341.86
							Miscellaneous & Rounding Off	658.14
							Grand Total	1500,00,000.00

Certificate:-

1. The workspot was inspected and work is found to be necessary.
2. The area comes within the Bruhat Bangalore Mahanagara Palike Limits.
3. The rates adopted based on the PWD SR Bangalore Circle for year 2018-19
4. The provisions made in the estimate are necessary and essential.

For Sri Sai Consultants

Assistant Engineer
Ward 14
BBMP - Bangalore

Assistant Executive Engineer
Dasarahalli Sub-Division
BBMP - Bangalore

Executive Engineer
Dasarahalli
BBMP - Bangalore

Technically Sanctione for Rs. 1500.00 lakhs

Rs. In words Rs. One Thousand five Hundred lakhs only

Under P-3158

Job Code No. 014-20-000102

Register d a ... No. CE/D2/TS.107/20-21 Subject

to conditions contained in Enclosed Memo

No. CE/D2/TS.107/2020-21 Dt. 14/09/2020

AE/JE. TA

CE(D)

14/9/2

ADMINISTRATIVELY SANCTIONED FOR

(Rupees 1500.00 lakhs

(Rs. One thousand five hundred lakhs only

Under the Head of Account P-3158

S.I.P. Infrastructure project work

Registered as no EE(D.D.)/AS.18/21-22 Subject

to conditions contained in Enclosed Memo

No. 18/2021-22 Dt. 05.07.21

Exe...

(DASARAHALL...

JE/AE.